

Article

# Daytime Lighting Assessment in Textile Factories Using Connected Windows in Slovakia: A Case Study

Dušan Katunský<sup>1,\*</sup> Erika Dolníková<sup>2</sup> and Bystrík Dolník<sup>3</sup>

<sup>1</sup> Department of Architecture and Building Structures, Institute of Architectural Engineering, Faculty of Civil Engineering, , Technical University of Kosice, Slovak Republic

<sup>2</sup> Department of Building Physics, Institute of Architectural Engineering, Faculty of Civil Engineering, Technical University of Kosice, Slovak Republic

<sup>3</sup> Department of Electric Power Engineering, Faculty of Electrical Engineering and Informatics, Technical University of Kosice, Slovak Republic

\* Correspondence: dusan.katunsky@tuke.sk; Tel.: +421-055-602-4157

**Abstract:** This paper highlights the problems associated with daylight use in industrial facilities. In a case study of a multi-story textile factory, we report how to evaluate daylight (as part of integral light) in the production halls marked F and G. This study follows the article in the Buildings journal, where Hall E was evaluated (unilateral daylight). These two additional halls have large areas that are 54 × 54 meters and are more than 5 meters high. The daylight is only on the side through the attached windows in envelope structures in the vertical position. In this paper, we want to present two case studies of these two production halls in a textile factory in the eastern part of Slovakia. These are halls that are illuminated by daylight from two sides through exterior peripheral walls that are against or next to each other. The results of the case studies can be applied in similar production halls illuminated by a 'double-sided' (bilateral) daylight system. This means that they are illuminated by natural illumination through windows on two sides in a vertical position. Such a situation is typical for multi-storied industrial buildings. The proposed approximate calculation method for the daylight factor can be used to predict the daylight in similar spaces in other similar buildings.

**Keywords:** sustainable architecture; industrial building; indoor environment; lighting conditions; computational simulation; luminance

## 1. Introduction

Many authors deal with daylight systems. An active solar daylighting system behind the perimeter wall is described by Kontadakis, A. et al. [1]. Furthermore, Tsangrassoulis, A. et al. [2] deals with the prototype of the hybrid daylight system. Some other aspects play important roles for daylight, such as dimming in relation to daylight (Doulos, L. et al. [3]). Doulos, L., et al. [4] also describes the role of the spectral response of photosensors in daylight response systems. One of the well-known authors dealing with daylighting and its impact on building users is Belia, L. [5,6].

The influence of daylight during the daytime on human health was studied by Shishegar, N. et al. [7] and Friberg, O. et al. [8]. Daylight affects the physiological and biological processes in the human body (McColl, S. L. et al. [9] and Smolders, K. C. et al. [10]) as well as the visual perception of interiors (Yao, J. et al. [11] and Fabi, V. et al. [12]). Gou studied the visual comfort and light simulated effects in relation to workers' productivity and well-being [13,14]. Daily lighting and its visual and non-visual perceptions of the indoor environment impacts the performance of people in the building. Research on the nonvisual daytime light effects on humans in buildings for non-visual health potentials, visual interest and observed behaviour is found in the work by Amundadottir, M. L. et al. [15] and visual perception (Lee, J. H. et al. [16]). Direct sunlight and its effects are investigated by Wang, N. et al. [17],

Yokoya, M. et al. [18], and Lee, K. S. et al. [19]. A barrier to dazzle and unpleasant dazzling is described by Hirning, M. B. et al. [20,21]. Shen monitors a model containing a synchronized daylight shadow operation with simplified control (Shen, H. & Tzempelikos, A. [22]). Research in this field is also focused on different types of microclimates, as well as on the overall assessment of the internal environment (Švajlenka, J. et al. [23,24]).

Building design, depending on the daylight, is described in the book *Handbook for Architects and Engineers* (Baker, M. & Steemers, K. [25]). Industrial buildings have certain features when designing lighting. This problem is addressed in the book *Handbook of Industrial Lighting* (Lyons, L.S. [26]). A whole range of problems related to the design of lighting openings in industrial buildings has been described by Dolníková, E. and Katunský, D. [27]. The problem associated with designing and evaluating windows in terms of daylight lighting is given by Kalousek, M. & Mohelníková, J. [28].

In terms of indoor lighting, various types of buildings that require demanding visual activities are examined in the literature. Educational buildings and schools are dealt with by Ferencikova, M. and Darula, S. [29], Moazzeni, M. H. et al. [30], Kruger, E. L. et al. [31], Piderit Moreno, M. B. et al. [32], and others. Residential buildings are followed by Xue, P. et al. [33], Nebia, B. et al. [34]; apartment buildings by Iringova, A. et al. [35]; and atrium building by Mohsenin, M. et al. [36], Berrardi, U. et al. [37], Gonzales, J. et al. [38], Pellegrino, A. et al. [39], Costanzo, V. et al. [40]), and Konis, K. [41].

Different types of light or lighting are the sum of the research activities of the team (Mistrick, R. et al. [42]), which deals with computer modelling of the photocontrols of electric lighting systems that are integrated daily. The simulation and modelling of daylight are monitored by Nasrollahi, N. et al. [43]. The energy efficiency of light is monitored by Reinhart, C. F. et al. [44]. The use of daylight when confronted with cold LED illumination is described by Amorim, R. et al. [45], the energy and visual control is described by Shen, E. et al. [46], and the lateral and visible atmosphere is described by Uriarte, U. et al. [47]. Adaptive light is tracked by Gunay, H. B. et al. [48] and a simulation to visualize and debug the behaviour of the lighting regulator is done by Jia, L. et al. [49]. An analysis of several criteria for selecting the optimal position and the correct field of view of the photosensor that is required in a building as well as the quantification of energy savings in daylight response systems in the dimming function of electronic ballasts is studied by Doulos, L. et al. [50,51]. Chromaticity-matched but spectrally different light effects sources on simple and complex colour judgments are studied by Veitch, J. A. et al. [52]. The meteorological models of the distribution of the brightness of the sky of external lighting and the approximate configuration and validation of the sky were studied by Perez, R. [53] and Igawa, N. [54].

As a result, daylight is very important in industrial halls for visual convenience. Especially for human vision and circadian rhythms, this is very important and effectively stimulates them. Unless we take into account all the needs and benefits, daylight can affect visual performance. It can cause discomfort by dazzling eyes and cause unpleasant scattering in the interior. Daylight may also weaken performance by creating shadows in the workplace. The effectiveness of electrical artificial lighting during the daylight depends on the quality of the light sources and their similarity to the radiation of daylight. Therefore, the negative aspects are also positive in daylight. Integral lighting is dealt with and certain conditions are proposed by Katunský D. [55]. Lighting conditions at the workplaces were examined using both practical and mathematical methods by Van Bommel, W. J. M. and van den Beld, G. J. [56]. The influence of user behaviour on unsatisfactory indoor thermal environments is described by Yan, B. et al. [57].

The incorporation of methods of daylight assessment into urbanization was studied by Sokol, N. and Martyniuk-Peczek, J. [58] and Chen, K. W. and Norford, L. [59]. These considerations have motivated us to do this research into daylight systems in order to improve the quality and comfort of interiors for workers while reducing energy consumption. The study of six industrial halls in France was published by Labat, M. and Attonaty, K. [60]. A similar problem in the industry is also addressed by Gourlis, G. and Ivacic, I. [61] and Pham, K. et al. [62].

One of the first to focus on the assessment of the impact of industrial buildings on the environment in terms of their sustainability is Alarcon, B. et al., [63]. The effectiveness of lighting in an

industrial factory (a case study in Slovakia) was examined by Katunský, D. et al. [64]. New models for sustainability assessment criteria in industrial buildings have been developed (Lombera, J. T. & Rojo, J. C. [65]). The modified criteria for the assessment of the sustainability of industrial buildings have resulted in the development of new models by Lombera, J. T. and Aprea, I. G. [66]. In this text, we want to outline the continuation of research aimed at ensuring minimal daylight conditions throughout the day in large-scale floor plans.

2. The Aim of the Research

In the design, construction, and operation of manufacturing buildings, it is necessary to consider the requirements for the sustainability of the buildings. Specifically, we are interested in the microclimate of the interior of industrial buildings focusing on the indoor light microclimate, the thermal humidity, and other factors with an emphasis on energy saving in operation. Last but not least, is building sustainability. The design requirements for the construction and operation of production facilities should consider the requirements in order to achieve sustainability. In particular, we are interested in the indoor climate in the interior of industrial buildings, focusing on indoor light, acoustic, thermal-humidity and other types of microclimates with an emphasis on energy saving aimed at building sustainability conditions.




Figure 1. The design of industrial buildings and the role of daylight for the indoor environment and the sustainability requirements.

An industrial building must be environmentally relevant, economically efficient, with stately architecture so that it leads to sustainability even within the industry (see Figure 1). In this paper, we are primarily concerned with the daytime lighting through window constructions in industrial and indoor environments and the lighting conditions in industrial buildings.

2.1. Methodology

In this article, we take into account the daytime lighting in an industrial factory (a textile factory) outside the city where one hall is above the other (one interior is above the other and there is no shading). The production halls are referred to as A, B, C, D, and so on. We are only interested in one part of the indoor environment—daylighting. It is not possible to meet the daylight requirement for visibility at remote locations with unilateral daytime lighting (on only one side), as shown in Reference [64], where the hall is marked as 'E'. The case study in this document points out how there is illumination from two parties (that is, bilaterally) in the 'F' and 'G' halls.

If we cannot meet the requirements for daylight there must be a combination of daylight and artificial lighting; for example, integral or integrated lighting. The task is to determine the methodology for determining the minimum required Daylight Factor (DF) for integral lighting, as prescribed by the Czech Technical Standards (CSN). The research was carried out in textile halls in a

town located in the eastern part of Slovakia. In this work, we present two knitting factories of the textile industry which have different window locations. The predominant role of this research is to analyze the impact of window placement on the daylight industrial hall lighting with regard to integrated dynamic simulations and real in situ measurement methods. The on-going view offers an analysis of the daylight conditions that also use measurements in situ and calculation by simulation, leading to the design of windows and the optimization of sustainability monitoring.


This work is a continuation of the comprehensive research of the quality of the internal working environments (internal microenvironments) of industrial buildings.

2.2. Daylighting According to Czech (CSN) and Slovak (STN) Standards

In the recent past, a number of technical lighting standards which deal with natural daylight and artificial illumination have changed. The associated lighting is addressed in many standards as part of artificial lighting regulations. The Standard for Building Integral Lighting was also valid in the Czech Republic after the revision. The Daylight Factor (DF) is considered and determined for the assessment of the indoor daylight environment. Equation (1) can be used to calculate this in a cloudy sky with a uniform cloud.

$$DF = \frac{\text{Internal illuminance}}{\text{External illuminance}} 100 \% \tag{1}$$

Prescription of the DF according to the Slovak standards is shown in Figure 2. The rule for the minimum and average daily DF factor for all seven categories of technical light recognition (see Table 1) according to the Slovak and Czech national standards can be seen in Figure 2.



**Figure 2.** The comparison of the Daylight Factor (DF) prescription according to Czech standard CSN 36 00 20 (Integral lighting) [67] and Slovak standard STN 730580 (Daylighting) [68].

The classification of the internal daylighting indoor-environment according to Slovak and Czech technical standards is based on the work, its complexity and the basic requirements that are placed on the complexity of the visual activity.

Artificial lighting is determined with EN 12464-1 2011 'Light and lighting—Lighting of workplaces, Part 1 Indoor work places' for 'night time conditions' only Reference [69]. Namely, the corresponding light levels from the artificial lighting system are calculated without the influence of daylight. Thus, only the combination of daylight and artificial light should be with the use of photosensors. However, this is not the subject of our research.

In Czech standards of ‘Integral lighting in buildings’ [67], interiors are classified into seven groups according to the intensity of the visual activities performed inside a building. This is similar to the Slovak standards [68]. The values of the DF are grouped into seven categories representing human eye recognition for visual detail tasks. The main starting point for determining the requirements for integral lighting is the classification of the visual activities performed in a building according to References [67,68] (Figure 2).

**Table 1.** The classification of human eye recognition of visual detail tasks according to the Slovak national standard STN 730580 [68].

Human Eye Recognition Category		Visual Detail Tasks
I.	Extreme accuracy	The most accurate visual work with limited use of magnification, with the requirement to eliminate errors in definition, stringent control
II.	High accuracy	Very precise production and control activities, high-precision drawing, hand engraving with very small detailing, fine artwork
III.	Precise operation	Precision manufacturing and inspection, regular drawing, technical drawing, consuming laboratory, labour-intensive investigations, fine sewing, embroidery
IV.	Medium accuracy	Medium precision manufacturing and inspection, reading, writing (by hand and machine), routine laboratory work, examinations, treatments, using machines, thicker sewing, knitting, laundry, cooking class, reading room, teaching cabinet, kitchen, doctor's surgery, office, meeting room, conference room
V.	Low accuracy	Approximate works, manipulating objects and materials, food consumption and service, leisure activities, physical education, dining room, living room, lounge, hall, gymnasium, swimming pool, storage room, waiting room
VI.	Very rough work	Maintenance cleaning, showering and washing, changing, walking on public roads open to the public, cloakroom, toilets, corridors
VII.	Only spatial orientation	Walking, material transport, storage of raw material, supervision

The same classification applies to the daily STN standards and the CSN integral lighting. The same applies to the relative observation distance. The difference is in the prescribed minimum DF factors (see Figure 2) as well as differences in the permitted luminance.

Problems related to industrial buildings have not been thoroughly reviewed until such details as another type of buildings. The criteria for residential and civil non-manufacture buildings do not apply to industrial buildings. Therefore, it is necessary to make certain changes in the methods and approaches to assessing the design of buildings in the industrial sectors.

2.3. Daylighting According to European Standards

In the draft of the European standards, the rules are slightly different from national standards. Other factors are taken into account here. This standard evaluates permanently inhabited areas, classifies buildings' premises according to function and work activities, and defines areas with daylighting requirements. The daylight assessment features are applied mainly to industrial areas, offices, civic areas, schools, health-related buildings, business and apartment buildings, and prisons and care homes. The daylight availability is determined by the median of horizontal diffuse illumination at location  $E_{med}$ . Daylight is intended to provide levels of natural light higher than the critical visual daylight lighting level of 300 lx. The daily lighting requirements should be adequate, with an acceptable minimum of 100 lux. The target factor  $D_T$  is the daily lighting factor to be achieved in a certain portion of an area in order to meet the daylighting criterion. On the working plane, the illumination level is 300 lx. The daylighting factor  $D_{TM}$  is the minimum target daylight factor. This is the minimum DF value in a specific location that corresponds to the illuminance level of 100 lx. Basic daylighting requirements according to the draft of the European standards [70] can be seen in Tables 2, 3, and 4:



**Table 2.** The maximum permissible brightness (luminance) of the subject observed and the brightness of the illuminating opening positioned 60° from the normal viewing direction according to European Union (EU) standards.

Class of visual activities	The ratio of the luminance of the observed object to the luminance of the illuminating opening (windows)
I, II, III	1:40
IV	1:100
V, VI, VII	not intended

Note: The usual direction of view is a view of the subject of work or other view related to the activity and the relaxation view in the horizontal direction.

**Table 3.** Recommendation of daylight provision by daylight openings in vertical and inclined surfaces [70].

Level of recommendation for vertical and inclined daylight opening	Target illuminance $E_T$ (lx)	Fraction of space for the target level $F_{plane}$ (%)	Minimum target illuminance $E_{TM}$ (lx)	Fraction of space for Min target level $F_{plane}$ (%)	Fraction of daylight hours $F_{time}$ (%)
Minimum	300	50%	100	95%	50%
Medium	500	50%	300	95%	50%
High	750	50%	500	95%	50%

NOTE: Table A.3 in Reference [70] states that the target daylight factor ( $DT$ ) and the minimum target daylight factor ( $DTM$ ) corresponds to the target illuminance level and the minimum target illuminance, respectively, for the European Committee for Standardization (CEN) capital cities.

**Table 4.** Assessment of the view outwards from a given position [70].

Parameter (a)			
Level of recommendation for view-out	Horizontal sight angle	Outside distance of the view	Number of layers to be seen from at least 75% of the utilized area: - sky - landscape (urban and/or nature) - ground
Minimum	$\geq 14^\circ$	$\geq 6.0$ m	At least the landscape layer is included
Medium	$\geq 28^\circ$	$\geq 20.0$ m	Landscape layer and one additional layer are included in the same view opening
High	$\geq 54^\circ$	$\geq 50.0$ m	All layers are included in the same view opening


(a) For a space with room depth of more than 4 m, it is recommended that the respective sum of the view opening(s) dimensions is at least 1.0 m x 1.25 m (width x height).

The draft of the European Union (EU) standards shows the values of the DF for daylight openings exceeding an illuminance level of 100, 300, 500 or 750 lx for a fraction of the daylight hours  $F_{time}$  (%) = 50% for 33 capitals of Committee for Standardization (CEN) national members. The values of the DF only for horizontal daylight openings with diffusing material exceeds an illuminance level of 100, 300, 500 or 750 lx for a fraction of daylight hours  $F_{time}$  (%) = 50% for 33 capital cities of CEN national members [70].

### 3. A Case Study: Textile Factory

The subject in this case study is a textile factory located in the eastern part of the Slovak Republic in which two knitting halls were observed. It is a three-storey steel-skeleton building surrounded by a lightweight cladding and connected windows (window strip).

There are a lot of spaces in this factory called A, B, C, D, and so on. In Reference [64], we considered hall E and in this paper, we evaluate hall F and hall G, which are illuminated by daylight from two sides.



**Figure 3.** The situation of a textile factory placement, lighting simulation results near windows in the double-side window day illumination.

Figure 3 shows the view of the building from the outside and the internal view as a result of daylight simulation with the Radiance simulation program.

In this article, we want to showcase studies of similar industrial factories that are illuminated by a double-sided daylight system (a strip of windows):

Windows are next to each other in the neighbouring perimeter walls (hall F).

Windows are in perimeter walls against each other (hall G).


In these halls was realised:

- 1) measurement of daylight value,
- 2) determination of the marginal conditions for the calculation of the DF,
- 3) calculation and simulation of the daylight situations using the simulation program,
- 4) confrontation of measured and calculated DF values,
- 5) and the derived simplified formula for the window design depending on the floor area to determine the minimum DF (for integral lighting as a basis).

#### 3.1. Daylight Measurements

Daylight measurements were performed according to Slovak standard 'Measurement of daylighting'. The measuring instruments were borrowed from the STU Faculty of Civil Engineering in Bratislava. The instruments were two 'Hagner EC 1 type' lux meters with the following production numbers: 5532 and 5531, a 'Hagner Universal Photometer type S2, S22065' with an accuracy of 5%, and the 'Hagner Reference calibration sample' with a factor value and a reflection of 0.966. When using a daylight system (according to Slovak valid standard STN 73 0580-1), the minimum standard value  $DF_{min} = 1.5\% - 2\%$ , the average normalized value  $DF_{average} = 5\% - 6\%$ , and the uniformity of the illumination is more than 0.2–0.3 for a given visual task. According to standard measurements of daylighting, the change in the luminance of the sky at a given height to sky luminance in zenith at  $15^\circ$  is 0.3–0.6 and 0.7–0.85 is acceptable at  $45^\circ$  (see Figure 5). Daylight measurements were performed on two different days when the artificial lighting system was switched off. Control points during the measurement were from the floor at 850 mm, because the need for visual power is at a given height. Measurements were performed at 81 control points simultaneously with two lux meters. It was measured in nine rows (direction E–W) labelled A–I at distances of 3, 9, 15, 21, 27, 33, 39, 45, and 51 m from the edge of the peripheral wall. In the longitudinal direction of the hall, it was also measured in

nine rows marked 1–9 at distances of 3, 9, 15, 21, 27, 33, 39, 45, and 51 m from the peripheral wall edge (Figures 4 and 6).



**Figure 4.** The floorplan of halls F and G.

If the device is unable to take a measurement at the specified points, the value is measured at approximately 30 cm–50 cm outside the point. One light measuring device measured illumination at a designated location inside the hall. The second light measurement was external, on a horizontal surface (on the roof). Daylight measurements were performed on the first day twice and the other days three times (see Figure 5). At the level of the roof structure, the measurement of the outdoor horizontal illumination and the external illuminance (see Equation (1)) was measured on a plane that was not shaded.

On the selected days, the value of the outside light in a cloudy sky ranged from 4000 lx–8000 lx on the first day and 5000 lx–8000 lx on the second day, when the light was measured in the direction of the cardinal. The measurements of the luminance distribution in the clouds at the measuring site were performed on both days at the beginning and at the end of the measurement. The comparison of the measured values with the normalized luminance distribution of an evenly cloudy sky on the dark terrain is shown in Figure 5. The final DF values measured at the control points are shown in Figure 7.


From the graphs in Figure 5, it can be seen that the values of the sky luminance at the specified altitude before and after the measurement were done are almost within the allowed range. The results of the measurement values can be seen in Table 5.

**Table 5.** The measured sky conditions rating gradations of sky luminance.


First day					
(a) at the beginning of measurements			(b) at the end of measurements		
Z	Le/Lz	Average value	Z	Le/Lz	Average value
15°	0.4–0.7	0.55	15°	0.35–0.68	0.50
45°	0.75–0.85	0.85	45°	0.80–1.05	0.92
Second day					
(a) at the beginning of measurements			(b) at the end of measurements		
Z	Le/Lz	Average value	Z	Le/Lz	Average value
15°	0.774–0.86	0.80	15°	0.61–0.72	0.68
45°	0.89–1.0	0.95	45°	0.88–0.92	0.90



The measured sky conditions rating gradations of brightness (sky luminance) in the two considered days in December and January can be seen in Figure 5. In Figure 5 x refers to the elevation angle and y to the Le/Lz ratio.




**Figure 5.** The measured sky conditions rating gradations of sky luminance, x refers to the elevation angle, y refers to the Le/Lz ratio, Le refers to the external sky luminance, and Lz refers to the sky luminance at an angle of Z 15° and 45°.




**Figure 6.** Schematic pictures of the predicted lines with the same DF in halls F and G at 81 control points (from A1–I9), indicating sections I–I, II–II, III–III and IV–IV for displaying the measured values.

Daylight measurements were made in December and January when the sky was cloudy. The DF values shown in Figure 7 are calculated from the measurement results as the average value of the five measurements. From these data, the DF evaluation parameters that are shown in Figure 6 were calculated. The spatial distribution of DF, the curves of the same brightness curves, and the DF curve decreases with respect to the depth of the space being considered. This is similar in Figures 8, 9, and 10.


The light reflection factor was determined according to the standards. Luminance was located according to the wall, ceiling, floor, and interior. From the measured luminance values of the individual surfaces and the known reflection factor of the calibration sample, the resulting reflection factor of the measured surfaces was calculated. The values of the calculated reflection factors were used as inputs for assigning the properties of the material surfaces in the hall.



Hall "F" section I-I



Hall "F" section I-I



**Figure 7.** The measured *DF* values at the control points in halls F and G in sections I-I, II-II, III-III and IV-IV.

3.2. Daylight Calculations

The boundary conditions for calculations have been observed in the measurement of daylighting. The following conditions for calculation were considered:


The external illuminance is considered to be 5000 lx; (in the draft EU standards it is considered different for every capital city of the 33 EU members. For Bratislava (Slovakia) it is 16,300 lx). The height of the interior space of hall is 5100 mm. The parapet is at a height of 1200 mm. The dimensions of the windows—the height of the window strip is 2400 mm and the wall thickness varied between 100 mm–300 mm.


The light loss coefficients, normal light transmittance  $\tau_{\text{glazing}} = \tau_1 = 0.92$ . The influence of the frame on light transmittance of windows  $\tau_2 = 0.74$ . The influence of glass cleanliness  $\tau_3 = 0.80$  and the influence of interior and shading elements  $\tau_4 = 1.0$ .


The coefficients of reflections ( $\rho$ ) of the light of individual surfaces: white ceiling  $\rho = 0.75$ , glass areas  $\rho = 0.10$ , walls  $\rho = 0.70$ , external terrane  $\rho = 0.15$  (no snow), light green mop board  $\rho = 0.65$ , light brown floor  $\rho = 0.50$ , and façade  $\rho = 0.45$ . For plants located outside the city, where one hall is above the other, there is no shading.  $Z = 0$ .

The *DF* values in hall F (double-sided daylight system of windows next to each other) and hall G (double-sided daylight system of opposite windows) are measured and computed. The halls reduce the *DF* due to the depth of the track.

The results of the *DF* and lighting calculated in the F and G halls and the luminance ( $\text{cd}/\text{m}^2$ ) in halls F and G calculated without a space device can be seen in Figure 8.









**Figure 8.** Results of the daylight factor  $DF$  (%), illumination  $I$  (lx), and luminance (cd/m<sup>2</sup>) in halls F and G calculated in an unfurnished interior.

In hall E, the daytime lighting was provided on one side only (see Reference [64]). The results are similar to those in halls F and G, except that the symmetry is different. In hall F, the symmetry axis is diagonal across points A9–I1 (Figure 6). In hall G, it is in the centre through points A5, B5, C5, and so on to I5. In hall F, there were no duplications of results at any of the points, despite the fact that the lighting was from two sides. In hall G, the daylight factor can be determined by the superposition of values. It is the sum of the highest value near the windows and the lowest value at the extreme point. At other points, the results are mirrored (Figure 6). When it comes to simulation programs, this is different. The results depend on the program used and the exact specification of the input data. Some programs also take into account the interior and the production process. In the industry, it is quite difficult to simulate a situation that would correspond to reality. We tried to simulate especially the visual perception of the interior, the observed detail, and the view of the windows. The results using simulation programs for the furnished interior can be seen in Figure 9.









**Figure 9.** The results of the daylight factor  $DF$  (%) and illumination  $I$  ( $lx$ ) in hall F and results of luminance ( $cd/m^2$ ) in hall F with the hall equipment calculated by the radiance simulation program.

In Figure 10, the level of  $DF$  factor in space (3D), in the floor plan (2D) and in the section (1D) for alternative calculations with wall thickness variations of 300 mm and 100 mm can be seen. Figure 10 shows the outputs obtained by the same procedure for hall G.





**Figure 10.** The results of the daylight factor  $DF$  (%) and illumination  $I$  (lx) in hall G and the results of the luminance ( $\text{cd/m}^2$ ) in hall G with the hall equipment calculated by the radiance simulation program.

The calculation that tracks the results for hall G was done with the same simulation programs as for hall F. Hall G has a two-sided illumination system with windows facing each other. Alternatively, the daylight factor  $DF$  (%) for a window height of 2400 mm and a wall thickness of 300 mm and 100 mm can be seen in the 3D space, in the plan view, and in the section plane. The luminosity in the furnished interior is interesting.

### 3.3. Evaluation of the Case Study

The values of the selection characteristics of a set are calculated at each measurement point. In the creation of the hall model, the marginal conditions were created based on measurements in the hall. Individual measured material constants (factors of reflection of surfaces, pollution factors, and glazing permeability) were considered. In this study, the results of measurement and calculation data for the control points are also presented. By comparing the calculated and measured data, we can conclude that the course is similar. As far as the level of daylight is concerned, there are differences. The  $DF$  has three components 1-sky  $DF_{\text{sky}}$ , 2-reflective inner components  $DF_i$ , and 3-reflective outer components  $DF_e$  that can be calculated as  $DF_{\text{reflected}}$  (see Reference [64]). This is calculated in most cases together and has the value of  $DF_{\text{reflected}}$ . Relationships 2–4 can be used for  $D_w$  points based on the above analysis. The diameter  $DF_{\text{reflected}}$  can be used as the  $DF$  factor in the centre of the space considered, where the windows are the same (hall F). The  $DF$  measured value (in hall F) is almost twice as high in close proximity to the windows as it is in hall G, where the windows are opposite (Figure 6). The lowest  $DF$  level is in the outermost positions of the windows (point I1 in hall F and in the symmetry axis of hall G—points A5–I5). The noticeable impact of daylight can be seen at points about 9 m away from the windows. Then the level of daylight shifts sharply. The resulting measured value approximates to  $DF_{\text{sky}}$ . The  $DF$  values may be lower due to device shading. This is shown in Figure 8, where the results are obtained using a calculation simulation program.

Changing the level of the reflection component  $DF_{\text{reflected}}$  at the distance from the daylight opening  $D_w$  is expressed by Equation (2) [64]. The reflected component  $DF$  at the distance  $D_w$  from windows changes from  $D_{\rho, \text{min}}$  to  $D_{\rho, \text{max}}$  with an average  $D_{\rho, \text{mean}}$  value. This value is the average in the centre of the space under consideration. The  $DF$  can be expressed by Equation (3).

$$DF = D_{\rho, \text{mean}} K \psi \quad (2)$$

$K$  and  $\psi$  in Equation (2) can be calculated using Equation (3) and Equation(4).

$$K = \frac{D_{\rho, \text{min}}}{D_{\rho, \text{mean}}} (-) \quad (3)$$

$D_{\rho, \text{max}}$  Maximum internal reflected daylight factor (%).

$D_{\rho, \text{mean}}$  Mean (average) internal reflected daylight factor (%).

$D_{\rho, \text{min}}$  Minimum internal reflected daylight factor (%).

$$\psi = \frac{2D_w - T_d}{T_d - 2} (-) \quad (4)$$

$D_w$  Distance from daylight opening (m).

$T_d$  Distance of the outermost point from the windows in the space considered.

The resulting DF also influences the peripheral wall structures. Figures 6 and 7 have documented the results of the DF and illumination for alternative wall thicknesses of 300 mm and 100 mm in the 3D space in the plan view and in the section.

The daylight and DF were measured in several production halls. This article shows two case studies. When analyzing the proportion of the glazed area (windows in the vertical plane) to the floor area, this proportion varies from 3%–6% in halls with a large floor area.

Based on this analysis, we can also calculate the DF relationship in this case, which uses the percentage of glazing  $P$ :

$$P = \frac{A_W}{A_F} (-) \quad (5)$$

We can express daylight factor as:

$$DF = (2.926D_w^{-2.115}) \cdot P^B \quad (6)$$

where

$A_W$  Area of the window structures ( $m^2$ ).

$A_F$  Area of the floor ( $m^2$ ).

$B$  can be calculated by:

$$B = 1.287 + 0.126D_w - 6.6 \times 10^{-3}D_w^2 + 9.8 \times 10^{-5}D_w^3 \quad (7)$$

In this study, we reviewed and analysed the effectiveness and adequacy of daylight that forms the basis for the application of integral light. A case study was conducted in two large industrial buildings to get a picture of the state of the environment and the ability to meet the relevant standards. As mentioned in the accompanying lighting application, there is a prescription—a standard in the Czech Republic that prescribes the minimal indoor climate requirements for minimum daylight (Figure 2). Emphasis has therefore been put on the use of daylight to increase the visual comfort of the industrial hall during the day and thus the possibility of saving energy on artificial light. We have noticed that daylighting in the tested knitting hall of a textile factory does not meet the required conditions throughout the work area. The hall is used during the day, where there are pleated machines that are utilised by the workers. At points and places where the values are lower than the required illumination size, artificial lighting such as electric lights is needed to supplement the daylight to reach the desired levels. The overall situation is particularly interesting in terms of visual perception.

The lights that run during the daytime in hall F are closer to the windows and two times higher than in the hall G. Daily light was measured when artificial light sources were switched off.

#### 4. Conclusions

Our task was to evaluate the daylight lighting in selected areas of the textile factory located in the east part of Slovakia. After performing preliminary calculations, following in situ measurements, and modelling and calculations using simulation programs, the following can be stated. A common parameter for daylight saving is the DF factor (daylight factor) in many countries. The daylight level measurement is relatively complicated because the level of outdoor lighting may change during the day. Finding a suitable day when acceptable conditions are met is difficult. Although the criteria are met and the outdoor lighting is within the allowed range, it may change during the measurement. Especially when there are a lot of control points. In our case study, we wanted to show how this task can be done. In the ordinary interior of the residential buildings, it is easier because the space is relatively small. In industrial buildings, the interiors are large in size. Sometimes the production halls are above and the upper daylight (skylights) can only be applied in the floor under the roof. On the



lower floors, it is possible to modify the structures or use the light pipe. When using windows only (as is this case), there is a significant drop in the DF.

In this case, the hall was an industrially operating hall that measured 54 metres x 54 meters with a height of about 5 meters. This type of 'hall' can also be compared with large spaces in other buildings (not only industrial). Such spaces are also typical for administrative and other buildings where there is a free arrangement without built-in partitions. In this study, a simple relationship to predict the level of daylight was derived, depending on the area of the windows. This relationship can be used to predict the size of glazed parts in the outer wall in the given areas. Since the daylight-protected windows are inadequate, it is necessary to bring light to other distances in a different way. As we know, daylight is at least physiologically and psychologically necessary. The person inside must feel the connection between the enclosed interior and the exterior. This is sometimes only a visual idea that cannot be mathematically described. Therefore, the need for daylight in the conditions we described is necessary if the daily factor DF is a low value.

The calculations that we have performed and confronted with the measurements in a real industrial operation are presented in this case study of large spaces. It should be emphasized that the results are different if we take into account the normative boundary conditions than when calculating using the simulation program. These are also differences when considering a furnished and unfurnished interior. Any situation of preliminary determination of equipment and built-in elements in the interior will be represented by other conditions and only the calculated results will be indicative. They come closer to the values we can expect in a real interior.

The contribution shows the possibility of DF approximation when using windows. In residential buildings, the windows are approximately 10% of the floor area. In an industrial setting, especially in industrial buildings or other large-spaced indoor areas, it is about 3%–6%. For the preliminary determination of DF in such cases, Equation (6) can be used.

When assessing building sustainability based on computational programs, the daylight element becomes just one of the sustainability assessment indicators. At the same time, the need for daylight is essential for sustainability and its emphasis should be highlighted in evaluation programs. Of course, it is not a simple matter to find a compromise between ecology, environment, economics, and energy requirements. However, this is the role for all of us in the future, because getting closer to sustainable development is our goal.

**Acknowledgments:** This paper was elaborated with the financial support of the research project VEGA 1/0674/18 of the Scientific Grant Agency, the Ministry of Education, Science, Research, and Sport of the Slovak Republic and the Slovak Academy of Sciences.

**Author Contributions:** Dušan Katunský coordinated the project, performed the field studies, and wrote the initial draft. Erika Dolníková conducted measurements of illuminations. Bystrík Dolník established a model for simulation and conducted daylight simulations using the simulation computer program. Dušan Katunský, Erika Dolníková, and Bystrík Dolník jointly performed analysis of the data and discussed the issues. Dušan Katunský developed the computational model and wrote the final version of the study.

**Conflicts of Interest:** The authors declare no conflicts of interest.

## References

1. Kontadakis, A.; Tsangrassoulis, A.; Doulos, L.; Topalis, F. An active sunlight redirection system for daylight enhancement beyond the perimeter zone, *Building and Environment* **2017**, *113*,
2. Tsangrassoulis, A.; Doulos, L.; Santamouris, M.; Fontoynt, M.; Maamari, F.; Wilson, M.; Jacobs, A. ; Solomon, J.; Zimmerman, A.; Pohl, W.; Mihalakakou, G. On the energy efficiency of a prototype hybrid daylighting system, *Solar Energy* **2005**, *79*, 1
3. Doulos, L.T.; Tsangrassoulis, A.; Kontaxis, P.A.; Kontadakis, A.; Topalis, F.V. Harvesting daylight with LED or T5 fluorescent lamps? The role of dimming, *Energy and Buildings* **2017**, *140*
4. Doulos, L.; Tsangrassoulis, A.; and Topalis, F. The role of spectral response of photosensors in daylight responsive systems, *Energy and Buildings* **2008**, *40*



- 455 5. Bellia, L., Fragliasso, F., & Stefanizzi, E. Why are daylight-linked controls (DLCs) not so spread? A literature  
456 review. *Building and Environment* **2016**, 106, 301-312.
- 457 6. Bellia, L., Pedace, A., & Fragliasso, F. The impact of the software's choice on dynamic daylight simulations'  
458 results: A comparison between daysim and 3ds max design®. *Solar Energy* **2015**, 122, 249-263.
- 459 7. Shishegar, N.; Boubekri, M. Natural light and productivity: Analyzing the impacts of daylighting on  
460 students' and workers' health and alertness. In Proceedings of the International Conference on "Health,  
461 Biological and Life Science" (HBLS-16), Istanbul, Turkey, 18–19 April **2016**.
- 462 8. Friborg, O.; Rosenvinge, J.; Wynn, R.; Gradisar, M. Sleep timing, phenotype, mood, and behavior at an arctic  
463 latitude (69°N). *Sleep Med.* **2014**, 15, 798–807.
- 464 9. McColl, S. L.; & Wilkinson, F. Visual contrast gain control in migraine: Measures of visual cortical  
465 excitability and inhibition. *Cephalalgia* **2000**, 20(2), 74.
- 466 10. Smolders, K.C.H.J.; De Kort, Y.A.W. & Cluitmans, P.J.M. Higher light intensity induces modulations in brain  
467 activity even during regular daytime working hours. *Lighting Research and Technology* **2015**, 48(4), 433-448.
- 468 11. Yao, J.; Chow, D.H.C.; Chi, Y.-W. Impact of Manually Controlled Solar Shades on Indoor Visual Comfort.  
469 *Sustainability* **2016**, 8, 727.
- 470 12. Fabi, V.; Andersen, R. K.; & Corgnati, S. Verification of stochastic behavioural models of occupants'  
471 interactions with windows in residential buildings. *Building and Environment* **2015**, 94(P1), 371-383.
- 472 13. Gou, Z.; Lau, S.S.; Ye, H. Visual alliesthesia: The gap between comfortable and stimulating illuminance  
473 settings. *Build. Environ.* **2014**, 82, 42–49.
- 474 14. Gou, Z.; Lau, S.S.; Qian, F. Comparison of mood and task performance in naturally-lit and artificially-lit  
475 environments. *Indoor Built Environ.* **2015**, 24, 27–36.
- 476 15. Amundadottir, M. L., Lockley, S. W., & Andersen, M. Unified framework to evaluate non-visual spectral  
477 effectiveness of light for human health. *Lighting Research and Technology* **2017**, 49(6), 673-696.
- 478 16. Lee, J.H.; Moon, J.W.; Kim, S. Analysis of occupants' visual perception to refine indoor lighting environment  
479 for office tasks. *Energies* **2014**, 7, 4116–4139.
- 480 17. Wang, N.; Boubekri, M. Design recommendations based on cognitive, mood and preference assessments in a  
481 sunlit workspace. *Lighting Research and Technology* **2011**, 43, 55–72.
- 482 18. Yokoya, M.; Yamamoto, S.; Yamauchi, Y.; Yamamoto, S.; Ouda, O.; Nakaguchi, T.; & Tsumura, N. Subjective  
483 evaluation of specular appearance for multiple observations using projector-based appearance reproduction  
484 Vol. 6626 LNCS, *3rd International Workshop on Computational Color Imaging, CCIW 2011*; Milan; Italy;
- 485 19. Lee, K.S.; Han, K.J.; Lee, J.W. Feasibility Study on Parametric Optimization of Daylighting in Building  
486 Shading Design. *Sustainability* **2016**, 8, 1220.
- 487 20. Hirning, M.B.; Isoardi, G.L.; & Cowling, I. Discomfort glare in open plan green buildings. *Energy and*  
488 *Buildings* **2014**, 70, 427–440.
- 489 21. Hirning, M.; Coyne, S.; & Cowling, I. The use of luminance mapping in developing discomfort glare  
490 research, *Journal of Light and Visual Environment* **2010**, 34(2), 101-104.
- 491 22. Shen, H.; Tzempelikos, A. Daylight-linked synchronized shading operation using simplified model-based  
492 control; *Energy and Buildings* **2017**, (145), 200-212.
- 493 23. Švajlenka, J.; Kozlovská, M.; Pošiváková, T.; Čonková, E. Indoor Analysis of Environment in Buildings.  
494 *Chemické Listy* **2017**, 111, 398-403.
- 495 24. Švajlenka, J.; Kozlovská, M.; Pošiváková, T. Assessment and biomonitoring indoor environment of  
496 buildings. *International Journal of Environmental Health Research* **2017**, 27, 427-439.
- 497 25. Baker, N. & Steemers, K.; *Daylight Design of Buildings: A Handbook for Architects and Engineers*, Book  
498 Routledge **2014**, ISBN 978-1134-257-348, 260 pgs.
- 499 26. Lyons, L. S. *Handbook of Industrial Lighting*, Elsevier **2013**, ISBN 0-408-00525-4, 224 pgs.
- 500 27. Dolníková, E. & Katunský, D. *Hodnotenie svetelnej pohody pri kombinovanom osvetľovacom systéme v*  
501 *priemyselných halách*, TUKE Košice **2017**, ISBN 978-80-553-2809-6, 151 pgs.
- 502 28. Kalousek, M. & Mohelníková, J. Influence of Window on Solar Gains and Daylight Level, *Advanced Materials*  
503 *Research* **2014**, Vol. 1041, pp. 175-179.
- 504 29. Ferencikova, M. & Darula, S. Availability of daylighting in school operating time; *Light and Engineering* **2017**,  
505 25 (2), 71-78.
- 506 30. Moazzeni, M.H.; Ghiabaklou, Z. Investigating the influence of light shelf geometry parameters on daylight  
507 performance and visual comfort, a case study of educational space in Tehran, Iran. *Buildings* **2016**, 6, 26.

- 508 31. Krüger, E. L., & Fonseca, S. D. Evaluating daylighting potential and energy efficiency in a classroom  
509 building, *Journal of Renewable and Sustainable Energy* **2011**, 3(6).
- 510 32. Piderit Moreno, M.B.; Labarca, C.Y. Methodology for assessing daylighting design strategies in classroom  
511 with a climate-based method. *Sustainability* **2015**, 7, 880–897.
- 512 33. Xue, P.; Mak, C.M.; Huang, Y. Quantification of luminous comfort with dynamic daylight metrics in  
513 residential buildings. *Energy Build.* **2016**, 117, 99–108.
- 514 34. Nebia, B.; Tabet Aoul, K. Overheating and Daylighting; Assessment Tool in Early Design of London's High-  
515 Rise Residential Buildings. *Sustainability* **2017**, 9, 1544.
- 516 35. Iringova, A. Impact of external shading on light comfort and energy efficiency in apartment buildings. *Appl.*  
517 *Mech. Mater.* **2017**, 861, 485–492.
- 518 36. Mohsenin, M.; Hu, J. Assessing daylight performance in atrium buildings by using Climate Based Daylight  
519 Modeling. *Solar Energy* **2015**, 119, 553–560.
- 520 37. Berardi, U.; Anaraki, H.K. The benefits of light shelves over the daylight illuminance in office buildings in  
521 Toronto. *Indoor Built Environ.* **2016**, 1–19.
- 522 38. Gonzalez, J.; Fiorito, F. Daylight design of office buildings: Optimisation of external solar shadings by using  
523 combined simulation methods. *Buildings* **2015**, 5, 560–580.
- 524 39. Pellegrino, A.; Cammarano, S.; Verso, V.R.; Corrado, V. Impact of daylighting on total energy use in offices  
525 of varying architectural features in Italy: Results from a parametric study. *Build. Environ.* **2017**, 113, 151–162.
- 526 40. Costanzo, V.; Donn, M. Thermal and visual comfort assessment of natural ventilated office buildings in  
527 Europe and North America. *Energy Build.* **2017**, 140, 210–223.
- 528 41. Konis, K. Evaluating daylighting effectiveness and occupant visual comfort in a side-lit open-plan office  
529 building in San Francisco, California. *Build. Environ.* **2013**, 59, 662–677.
- 530 42. Mistrick, R.; Casey, C.; Chen, L.; Sarith Subramaniam, S. Computer modeling of daylight-integrated  
531 photocontrol of electric lighting systems. *Buildings* **2015**, 5, 449–466.
- 532 43. Nasrollahi, N.; Shokri, E. Daylight illuminance in urban environments for visual comfort and energy  
533 performance. *Renew. Sustain. Energy Rev.* **2016**, 66, 861–874.
- 534 44. Reinhart, C.F.; Wienold, J. The daylighting dashboard—A simulation-based design analysis for daylit  
535 spaces. *Build. Environ.* **2011**, 46, 386–396.
- 536 45. Amorim, R.; López, J.C.; Molina-Moreno, V.; Peña-García, A. Use of Natural Light vs. Cold LED Lighting in  
537 Installations for the Recovery of Victims of Gender Violence: Impact on Energy Consumption and Victims'  
538 Recovery. *Sustainability* **2017**, 9, 562.
- 539 46. Shen, E.; Hu, J.; Patel, M. Energy and visual comfort analysis of lighting and daylight control strategies.  
540 *Build. Environ.* **2014**, 78, 155–170.
- 541 47. Uriarte, U.; Hernández, R.J.; Zamora, J.L.; Isalgue, A. Side-view atmospheres under outdoor midday high  
542 luminance. *Buildings* **2016**, 6, 53.
- 543 48. Gunay, H.B.; O'Brien, W.; Beausoleil-Morrison, I.; Gilani, S. Development and implementation of an  
544 adaptive lighting and blinds control algorithm. *Build. Environ.* **2017**, 113, 185–199.
- 545 49. Jia, L.; Afshari, S.; Mishra, S.; Radke, R.J. Simulation for pre-visualizing and tuning lighting controller  
546 behavior. *Energy Build.* **2014**, 70, 287–302.
- 547 50. Doulos, L.; Tsangrassoulis, A.; and Topalis, F. Multi-criteria decision analysis to select the optimum position  
548 and proper field of view of a photosensor, *Energy Conversion and Management* **2014**, 86
- 549 51. Doulos, L.; Tsangrassoulis, A.; and Topalis, F. Quantifying energy savings in daylight responsive systems:  
550 The role of dimming electronic ballasts, *Energy and Buildings* **2008**, 40
- 551 52. Veitch, J.A.; Whitehead, L.A.; Mossman, M.; & Pilditch, T.D. Chromaticity-matched but spectrally different  
552 light source effects on simple and complex color judgments *Color Research and Application* **2014**, 39(3).
- 553 53. Perez, R.; Seals, R.; Michalsky, J. All weather model for sky luminance distribution—Preliminary  
554 configuration and validation. *Solar Energy* **1993**, 50, 235–245.
- 555 54. Igawa, N.; Koga, Y.; Matsuzawa, T.; Nakamura, H. Models of sky radiance distribution and sky luminance  
556 distribution. *Solar Energy* **2004**, 77, 137–157.
- 557 55. Katunský, D. Aproximativný výpočet minimálnych činiteľov dennej osvetlenosti vo veľkorozmerových  
558 priemyslových halách. *Building Research Journal* **1992** (40), 299–311.
- 559 56. Van Bommel, W.J.M.; van den Beld, G.J. Lighting for work: A review of visual and biological effects. *Lighting*  
560 *Res. Technol.* **2004**, 36, 255–269.

- 561 57. Yan, B.; Long, E.; Meng, X.; Zhang, Y.; Hou, D.; & Du, X. Influence of user behavior on unsatisfactory indoor  
562 thermal environment. *Energy Convers. Manag.* **2014**, *86*, 1–7.
- 563 58. Sokol, N.; Martyniuk-Peczek, J. *The review of the selected challenges for an incorporation of daylight assessment*  
564 *methods into urban planning in Poland*. Proc. Eng. 2016, 161, 2191–2197.
- 565 59. Chen, K.W.; Norford, L. Evaluating Urban Forms for Comparison Studies in the Massing Design Stage.  
566 *Sustainability* **2017**, (9), 987.
- 567 60. Labat, M.; Attonaty, K. Numerical estimation and sensitivity analysis of the energy demand for six  
568 industrial buildings in France; *Journal of Building Performance Simulation* **2017**, *3*, 1-21.
- 569 61. Gourelis, G.; Ivacic, I. A study on building performance analysis for energy retrofit of existing industrial  
570 facilities. *Applied Energy* **2016**, *184*, 1389-1399.
- 571 62. Pham, K.; Garcia-Hansen, V.; Isoardi G. Appraisal of the Visual Environment in an Industrial Factory: a  
572 Case Study in Subtropical Climates, Solarlits; *Journal of Daylighting* **2016**, Vol. 3, (2), 12-26.
- 573 63. Alarcon, B.; Aguado, A.; Manga, R.; Josa, A.; A value function for assessing sustainability application to  
574 industrial buildings. *Sustainability* **2011**, *3*, 35–50.
- 575 64. Katunsky, D.; Dolnikova, E.; Doroudiani, S. Integrated Lighting Efficiency Analysis in Large Industrial  
576 Buildings to Enhance Indoor Environmental Quality. *Buildings* **2017**, *7*, 47.
- 577 65. Lombera, J.T.; Rojo, J.C. Industrial building design stage based on a system approach to their environmental  
578 sustainability. *Construct. Build. Mater.* **2010**, *24*, 438–447.
- 579 66. Lombera, J-T-S-J; Aprea, I.G. A system approach to the environmental analysis of industrial buildings.  
580 *Building and Environment* **2010**, *45*, 673–683.
- 581 67. *Integral Lighting*, ČSN 360020; CZ Office of Standards, Metrology and Testing Prague, Czech Republic, **2015**.
- 582 68. STN 730580; *Daylighting in buildings, Part–1 Basic requirements*, 1986 *Part–2; Daylighting of residential buildings*,  
583 2000, Slovak Republic Office of Standards, Metrology and Testing; Bratislava, Slovakia; **2000**
- 584 69. EN 12464-1:2012. *Light and Lighting; Lighting of Work Places-Part 1: Indoor Work Places*; Slovak Republic Office  
585 of Standards, Metrology and Testing; Bratislava, Slovakia, **2012**
- 586 70. CEN/TC 169 07/**2017** *Daylight in buildings* (TC 169 WI 00169068), **2017**
- 587 71. International Energy Agency (IEA) *Solar and Heating Cooling Program*, Task 31—*Daylighting Buildings in the*  
588 *21st Century*. Available online: <http://task31.iea-shc.org/> (accessed on 2 May 2017).