

## Article

# Potential for potable water savings due to rainwater use in a precast concrete factory

Giovanna Bertuzzi <sup>1</sup> and EneDir Ghisi <sup>2,\*</sup>

<sup>1</sup> Federal University of Santa Catarina, Department of Civil Engineering, Laboratory of Energy Efficiency in Buildings, Florianópolis-SC, 88040-900, Brazil; giovannakbertuzzi@gmail.com (G.K.B.)

<sup>2</sup> Federal University of Santa Catarina, Department of Civil Engineering, Laboratory of Energy Efficiency in Buildings, Florianópolis-SC, 88040-900, Brazil; enedir.ghisi@ufsc.br (E.G.)

\* Correspondence: enedir.ghisi@ufsc.br (E.G.); Tel.: +55 48 3721 2115; fax: +55 48 3721 5191

**Abstract:** The objective of this paper is to assess the potential for potable water savings due to rainwater use in a precast concrete factory in southern Brazil. The economic feasibility and the rainwater quality were also assessed. The current water consumption, future water demand and rainwater demand in the factory were estimated. The future demand considered was two times higher than the current water consumption since there are plans to increase the production. Three scenarios were then simulated using the computer programme *Netuno*. The ideal rainwater tank capacity, the potential for potable water savings and the economic feasibility analysis for each scenario were estimated. Samples of rainwater were collected in the factory and tested for quality for manufacturing precast concrete. For a rainwater tank capacity equal to 25,000 litres, the potential for potable water savings for the first scenario was 55.4%, but the first scenario was considered economically unfeasible. For the same tank capacity, the second and third scenarios presented viable results regarding potable water savings and payback. As for the rainwater quality, it was proven to be adequate for manufacturing precast concrete. The main conclusion is that rainwater can be used to manufacture precast concrete in the factory studied herein.

**Keywords:** rainwater harvesting, rainwater quality, precast concrete, financial analysis, computer simulation

## 1. Introduction

Rainwater harvesting systems may be installed in different kinds of buildings, such as houses, commercial and residential buildings, factories and many others. The economic benefit of the installation of the system is still a matter of concern among specialists. The economic feasibility varies significantly for each region, being highly dependent on the water tariff charged by the local water company, the rainfall and the adequate sizing of the rainwater tanks [1].

A study performed by Ghisi and Schondermark [2] about the installation of rainwater harvesting systems in houses in the state of Santa Catarina (Brazil) showed that the economic benefits of these systems depend on the water demand. Although there would be environmental benefits due to the installation of rainwater harvesting systems in all houses, there would be economic feasibility only in those with higher water demands or a higher number of occupants.

The use of rainwater can also be applied to situations that demand low volumes of water. Fernandes et al. [3] projected a rainwater harvesting system in a waste treatment installation close to the city of Mirandela (Portugal). Rainwater would be used to wash cars and other equipment, clean outdoor concrete and asphalt floors and irrigate green areas. Fernandes et al. [3] pointed out that for installations that demand small amount of water, the water harvesting systems would be efficient even if the tank capacity did not supply 100% of the demand. The tank capacity supplied 90% of the water demand.

After going through adequate treatment, rainwater can be used in different applications that do not require potable water. The Brazilian standard NBR 15527 [4] presents some possibilities for the utilisation of rainwater, such as toilet flushing, water mirrors, to irrigate lawns or ornamental plants, to wash cars, to clean sidewalks, streets and patios and also for some industrial processes.

Rainwater harvesting systems and other measures that favour the preservation of the environment and natural resources are still rarely used in the field of civil construction. Zhang et al. [5] pointed out that it is likely that one of the main reasons construction companies have a low rate of adoption of environmental measures is because the financial savings are usually enjoyed by the building occupants and not necessarily by the constructor or the client that hired the construction.

A high amount of water is used in constructions, which shows the need for implementing programmes of sustainable use of water resources in construction sites [6]. As pointed out by Santos et al. [7], some studies about water use in buildings have already been performed; however, the water consumption in the stages of construction has been poorly explored yet. Souza and Ghisi [8] analysed ten construction sites in Criciúma, southern Brazil, and observed that the average daily water consumption per worker was 51.25 L/worker.day (ranging from 42.73 to 65.58 L/worker.day), and the average monthly water consumption per built area was 5.06 L/m<sup>2</sup>.month (ranging from 1.76 to 9.79 L/m<sup>2</sup>.month). According to McCormack et al. [9], the efforts for reducing water consumption are mostly related to the operation of the building. Thus, the consumption of water for constructing buildings is usually neglected.

Zhong and Wu [10] performed a study in Singapore to investigate the performance of reinforced concrete and steel structures according to economic sustainability, environmental sustainability and constructability. The results indicated that reinforced concrete structures consume approximately 1468 litres of water per m<sup>2</sup> on average; while, steel structures consume only 1.89 L/m<sup>2</sup>. This difference is due to the differences in the construction process of these two types of structure. It was found that the consumption of water is not a decisive factor for the selection of the material used in the structure of the building.

Concrete is one of the materials largely used in the construction industry. It is necessary to use cement, coarse aggregate, fine aggregate and water to manufacture concrete. Due to the high consumption of water in concrete mixing plants, precast concrete industries and construction sites are concerned with the consumption of this natural resource. In order to reduce the consumption of potable water for manufacturing concrete, there are some alternatives available, such as greywater or rainwater.

According to Arnaldo Forti Battagin (laboratory manager of the Brazilian Association of Portland Cement), rainwater can be used for manufacturing concrete, as long as it presents pH higher than 5 and meets the requirements of the Brazilian standard NBR 15900 [11]. The Brazilian regulation about water for manufacturing concrete – NBR 15900 [12] – defines that rainwater can be used for manufacturing concrete provided that it is tested for some parameters.

Bedoya-Montoya and Medina-Restrepo [13] conducted a study in Colombia to compare the quality of concrete produced using either potable water or rainwater. The authors installed a rainwater collection system on the campus of Institución Universitaria Colegio Mayor de Antioquia. The quality of the rainwater collected was monitored for six months. The water was analysed when the tank was full. The amount of water collected during the first five minutes of each rain was disposed of due to its lower quality. The potable water analysed was collected directly from the aqueduct supplied by the local water company. It was possible to identify that both were adequate to be used for manufacturing concrete. Afterwards, concrete specimens were submitted to compressive strength testing. The results obtained with the compressive strength testing did not indicate that the rainwater reduced the concrete strength in comparison with the samples manufactured using potable water. Bedoya-Montoya and Medina-Restrepo [13] also

pointed out that there were no noticeable differences between the two samples of fresh concrete, regarding the laying process, workability and appearance.

The Brazilian regulation about water for manufacturing concrete, as well as the regulations of other countries, like Colombia, allows the utilisation of rainwater for manufacturing concrete, as long as the water meets the quality criteria established. However, using rainwater for manufacturing concrete is a subject that is still poorly explored globally, and the number of studies is still scarce.

The main objective of this paper is to assess the potential for potable water savings due to rainwater use in a precast concrete factory in southern Brazil. The economic feasibility and the rainwater quality were also assessed.

2. Materials and Methods

2.1. The factory

The factory to be assessed is located in São José, southern Brazil. It currently has 65 employees and produces different kinds of concrete elements, which demands the use of 15,000 litres of water per day on average. The floor-plan areas of the main roofs of the factory sum 15,346.71 m². Such a large roof area could be used to harvest rainwater. The roofs and their corresponding areas are shown in Figure 1.



Figure 1. Layout of the roofs of the factory and their corresponding areas.

Source: Image from Google Earth generated by the authors in 2018

## 2.2. Data collection

In order to perform the analyses, it was necessary to collect some data, such as daily rainfall data. Furthermore, it was necessary to determine the water demand at the factory and to separate this demand into two categories. The first category is the one that requires potable water; the second is the one that does not require potability and therefore can be replaced with rainwater. Besides, other types of data were essential to obtain the potential for potable water savings, such as the roof areas where the rainwater was collected and their runoff coefficients.

### 2.2.1. Rainfall data

The daily rainfall data used in this work were obtained from INMET [14] and are available on BDMEP (Meteorological Database for Teaching and Research). The weather station is located in the district of Praia Comprida in the city of São José (Latitude 27.6025° S and Longitude 48.620278° W). This rainfall station was chosen due to its proximity to the factory (3.5 km) and because it has been operating since 1921.

### 2.2.2. Current water consumption

It was not possible to obtain the total water consumption in the factory with accuracy because currently the water consumed is extracted from an artesian well located in-situ, and therefore there is no control of the amount of water pumped daily or monthly. For this reason, water consumption at the factory was estimated. In order to estimate the water consumption, it was necessary to obtain the number of employees and activities that require water. For each activity, the consumption of water per unit (repetitions, m<sup>3</sup>, etc.) was estimated. The number of repetitions of each process and the volume of concrete manufactured were obtained from the reports kept at the factory.

The amount of concrete elements produced varies throughout the year. It depends on the demand, but mainly on the factory planning since a great number of elements is produced to maintain the stock. Therefore, the total water consumption was estimated for each month of the year. The estimated water consumption was divided among the working days of the year since the factory only operates on those days.

### 2.2.3. Rainwater demand

Currently, the artesian well is being used close to its maximum capacity. Therefore, in case the demand for water increases, it would be necessary to use water from the local water company, which increases costs. Since the company board is planning on doubling the monthly production of concrete elements, demanding a volume of water that is higher than the one available in the artesian well, the future water demand considered herein is twice as much the current consumption.

The volume of water available in the well varies according to rainfall and other environmental factors. Thus, the volume of water available daily varies throughout the year. For this reason, the average water consumption was considered. The average daily water extraction from the well was considered as 14,000 L. This average figure was given by the factory managers, which obtained it throughout the years of the artesian well exploration.

Consequently, the rainwater demand considered was the figure that exceeds the average limit of exploration of the well. This way, on the days in which the future demand was lower than 14,000 L, there was no demand for rainwater. For the days in which the future demand surpasses the average limit of exploration of the well, the rainwater demand will

be the future water demand minus 14,000 L. It was chosen to prioritise the use of water from the artesian well since it does not imply costs for acquisition, only costs with electricity for pumping the water.

#### 2.2.4. Runoff coefficients

The roofs which were considered to be a part of the rainwater harvesting system are made of different materials, such as ceramic, enamelled and metallic tiles. The Brazilian standard NBR 15527 [4] presents runoff coefficients equal to 0.8 as the most commonly used. For this reason, 0.8 was adopted as the runoff coefficient for the factory roofs.

#### 2.3. Potential for potable water savings

The potential for potable water savings due to the installation of the rainwater harvesting system was estimated using the *Netuno* computer programme, version 4 [15]. Such savings refer to the savings of potable water supplied by the local water company since water savings from the artesian well are not desired by the company board. In order to estimate the potential for potable water savings using *Netuno*, it was necessary to have daily rainfall data, and some other data such as first flush, rainwater catchment area, total water demand, number of occupants, rainwater demand and the runoff coefficient of the roofs.

The capacity of the upper rainwater tank is also input data for the simulations. As for the lower rainwater tank, different capacities were simulated. Different roof areas were also simulated. In the first scenario, rainwater was collected from all roofs identified in Figure 1; in the second scenario, all roofs, but sheds 1 and 2, were considered; and in the third scenario, all roofs, but shed 1 and the refectory, were considered.

#### 2.4. Financial analysis

In order to perform the financial analysis for the three different scenarios, some estimations were necessary. The quantity and the diameters necessary for gutters, piping, pipe connections, rainwater tank and other accessories like solenoid valve, float switch, among others, were estimated.

The installation of a lower rainwater tank and an upper tank was considered. The rainwater collected from the roofs would be stored in the lower tank, and then pumped to the upper tank, allowing the rainwater distribution for consumption to be done by gravity.

The financial analysis was performed using *Netuno* 4. The water and sewage tariffs, the monthly inflation, the period in which water and electricity tariffs increase, the period of analysis and the minimum acceptable rate of return are some of the input data. Also, labour costs and the costs of the rainwater tanks, piping and accessories are needed. When an upper water tank is used, the electricity tariffs and the costs of the upper rainwater tank and the motor pump are also necessary. Furthermore, other operational costs may be considered, such as costs with maintenance or water treatment, when applicable.

The inflation considered was the average of the monthly inflation between October 2017 and September 2018, obtained from the National Index of Prices for the Wide Consumer (IPCA) from the Brazilian Institute of Geography and Statistics [16]. The water tariffs for consumption in industries were obtained from the local water company, and the sewage tariffs were considered null since the factory has its sewage treatment systems in-situ. The electricity tariffs were obtained from the local electricity company. As stated in an electricity bill, the factory fits in the green-hour tariff category, subgroup A4. The electricity tariff was considered as off-peak since it was identified in the bills that more than



95% of the consumption fits in this category. Taxes were also considered. The period of readjustment of water and electricity tariffs was considered as 12 months.

The period of analysis considered was 20 years, which is the average lifespan of the motor pump – the equipment of the system that has the shortest lifespan. The minimum acceptable rate of return considered was the average profitability index of the savings account between October 2017 and September 2018.

The net present value, internal rate of return and discounted payback were obtained using *Netuno*. The scenarios were considered economically feasible when the internal rate of return was higher than the minimum acceptable rate of return, and the net present value was positive.

The net present value can be estimated using Eq. 1 [17].

$$NPV = C_0 + \frac{C_1}{1+i} + \frac{C_2}{(1+i)^2} + \dots + \frac{C_n}{(1+i)^n} \quad (1)$$

where NPV is the net present value (R\$),  $C_n$  is the net cash flow at the period  $n$  and  $i$  is the minimum acceptable rate of return. The period considered for the financial analysis ( $n$ ) was 240 months (20 years). All costs were considered as negative figures and the savings as positive figures.  $C_0$  was calculated considering the cost of the lower rainwater tank, the cost of the upper rainwater tank, cost of labour, cost of piping, cost of accessories and cost of the pumps. The costs considered for  $C_1$  to  $C_{20}$  included the electricity tariff and the taxes over the electricity tariff for the operation of the pump.

The payback period represents the time when the invested capital is recovered. It is considered that the investment is recovered when the net present value becomes zero. Therefore, the payback period is the value  $n$  in Equation 1 when NPV is equal to zero.

The discount rate that results in a net present value equal to zero, considering the period for the financial analysis, is the internal rate of return. The internal rate of return represents the profitability of the investment and can be obtained using Eq. 2 (based on Mishan and Quah [18]).

$$0 = \sum_{t=0}^n \frac{C_n}{(1+IRR)^n} \quad (2)$$

where IRR is the internal rate of return (% per month),  $C_n$  is the net cash flow at the period  $n$  and  $n$  is the period considered for the financial analysis, which was 240 months.

## 2.5. Rainwater quality

In this study, rainwater is meant to be used only for manufacturing concrete, cutting pieces and cleaning lanes. Two rainwater samples were collected in two different days from the same location, i.e. the roof of the office. In the first sample, there was no first flush disposal; and in the second, there was first flush disposal. The objective was to compare the quality of the rainwater collected in two different situations. The first sample was collected on the 11th Sep 2018, after six days with no rain. The second sample was collected on the 12th Sep 2018 and there was a first flush disposal equal to 2 mm. The procedure for collecting and storing the samples complied with NBR 15900 [12].

The rainwater quality was assessed according to NBR 15900 [12]. First of all, it was necessary to perform the preliminary tests. After that, if the water met the requirements established for the preliminary tests, the determination of contaminants (sugars, phos-

phates, nitrates, lead and zinc) could be made. In case the water was not approved in the criteria established for the preliminary tests, the tests of concrete setting time and concrete strength would be mandatory. If the water being tested does not meet all the criteria established for the preliminary tests, it can still be approved for use in concrete, as long as it is approved in the tests of concrete setting time and concrete strength, chlorides (or meet the requirements of NBR 12655 [19]), sulfates and alkalis (or meet the requirements of NBR 15577 [20]). Since the carrying out of the tests of concrete setting time and concrete strength excludes the necessity to assess contaminants and allows that one of the criteria of the preliminary tests is not met, one chose to perform these tests and not to assess the contaminants.

Afterwards, it was necessary to perform the tests for chlorides and sulfates. The determination of the level of alkalis was not necessary since aggregates not reactive with alkalis are used in the factory. The factory uses aggregates from a single supplier, obtained from the same mine, and the non-reactivity of the material is verified using periodic tests for the alkali-aggregate reaction.

Therefore, the following tests were performed: (i) Preliminary tests: oils and fat; detergents; colour; solid material; odour; acids (pH); organic matter; (ii) concrete setting time; (iii) concrete strength; (iv) chlorides; (v) sulfates.

The preliminary tests and the tests for the level of chlorides and sulfates were performed in duplicate in the Integrated Laboratory of the Environment (LIMA) in the Department of Sanitary and Environmental Engineering of the Federal University of Santa Catarina (UFSC). The oils and fats, detergents, colour, solid material and odour tests were performed according to the procedures indicated in the NBR 15900 [12].

The test for acid levels (pH) was performed using a piece of pH-meter equipment, which is an instrument used to measure the pH through the potentiometric method. The organic matter tests were performed using the colourimetric method. The concrete setting time test was performed in the Laboratory of Civil Construction Materials (LMCC) in the Civil Engineering Department of the Federal University of Santa Catarina (UFSC) according to the procedure indicated in the NBR 16607 [21]. The standard NBR 15900 [12] defines that for the water sample to be approved in the concrete setting time criteria, the beginning and the end of the concrete setting time must not differ more than 25% from the beginning and the end of the concrete setting time of paste prepared with distilled or deionised water. The beginning and end of the concrete setting time must also meet the criteria established in the Brazilian regulation for the cement used. In this case, the cement used was the CP IV 32.

The strength tests were performed in the laboratory in the factory. In order to perform the concrete strength tests, concrete specimens were moulded according to the criteria established in NBR 5738 [22]. The specimens were ruptured at 7 and 28 days, according to the procedure stated in NBR 5739 [23]. The concrete mix used for all the specimens was the same, which was the standard mix used in the factory. The cement used was the CP V ARI. The test for chlorides in the water samples was performed using the procedure of titulometry. NBR 15900 [12] establishes limits for the chloride levels in the tested water according to the use intended for the concrete. The possible uses are precast concrete or grout, reinforced concrete and standard concrete. Precast concrete elements and reinforced concrete elements are manufactured at the factory. Since the maximum level of chloride for precast concrete is the lowest (stricter), the maximum limit of chloride level considered was defined for this category, which is 500 mg/L.

The sulfate test was performed using a spectrophotometer with a wavelength of 420 nm. The maximum level of acceptance for sulfates in the water is established in NBR 15900 [12] as 2,000 mg/L.

3. Results

3.1. Rainfall data

Daily rainfall data from September 2001 to July 2018 – approximately seventeen years of data – were used in the analysis. The annual rainfall over 2002 and 2017 is shown in Figure 2. The average annual rainfall over that period was 1775 mm. The average monthly rainfall, as well as the minimum and maximum for each month, are shown in Figure 3. The month with the highest rainfall was January (223 mm); the lowest was June (85 mm). Although rainfall distribution is not homogeneous along the year, long dry periods were not observed, which indicates that it is possible to collect rainwater during all seasons of the year.




Figure 2. Annual rainfall in the city of São José over 2002–2017.

Source: Based on INMET [14]




Figure 3. Average, minimum and maximum monthly rainfall in the city of São José over 2002–2017.

Source: Based on INMET [14]

3.2. Current water consumption



The estimates for water consumption in the factory are shown in Table 1. Total water consumption ranged from around 74 kL to 391 kL per month.

**Table 1.** Water consumption at the factory from August 2017 to July 2018.

Month/year	Water for manufacturing concrete (L/month)	Water for cutting and cleaning lanes (L/month)	Water for human consumption (L/month)	Total water consumption (L/month)	Working days in the month (Days)	Daily average consumption on working days (L/day)
August/2017	309,116	34,400	47,840	391,356	23	17,015
September/2017	96,354	800	41,600	138,754	20	6,938
October/2017	101,884	16,250	43,680	161,814	21	7,705
November/2017	186,462	-	41,600	228,062	20	11,403
December/2017	148,686	-	41,600	190,286	20	9,514
January/2018	25,773	2,500	45,760	74,033	22	3,365
February/2018	176,370	24,850	39,520	240,740	19	12,671
March/2018	100,641	9,700	43,680	154,021	21	7,334
April/2018	93,402	17,750	43,680	154,832	21	7,373
May/2018	147,459	2,800	45,760	196,019	22	8,910
June/2018	213,106	20,300	43,680	277,086	21	13,195
July/2018	227,282	18,650	45,760	291,692	22	13,259

### 3.2. Rainwater demand

The water demand considered for the analysis is twice as high as the current water consumption. The total water consumption in the factory can be divided into two categories: potable water and non-potable water. The non-potable water is related to the uses for manufacturing concrete, cutting elements and cleaning lanes since these activities do not require potable water. The potable water is used for human consumption. The non-potable water demand is the one that can be replaced with rainwater. The total water demand is shown in Table 2.

The volume of water available in the artesian well varies according to the time of the year due to various environmental factors. In order to analyse the potential for potable water savings through the implementation of a rainwater harvesting system, an average value provided by the factory managers was used. The amount of water obtained from the artesian well is 14,000 L per day.

The future water demand will be supplied by three different sources: water from the artesian well, water from the water company, and rainwater. It was considered that, for each day, if the demand is equal to or lower than 14,000 L, it is fully met by the water in the artesian well. If the demand is greater than 14,000 L, it is then supplied by the artesian well, which provides 14,000 L, and the exceeding demand is supplied with rainwater; and when the rainwater cannot fully supply the exceeding demand, the

demand is met with water from the water company. Thus, the daily demand for potable purposes (which is 4,160 L/day) is fully supplied by the artesian well.


Table 3 shows the water demand that can be supplied with rainwater, representing the amount that exceeds the 14,000 L of daily consumption. Figure 4 shows the amount of water that can be supplied by the artesian well, and the amount of water that will be supplied with water from the water company and that can be replaced with rainwater.

**Table 2.** Total water demand at the factory.

Month	Water for manufacturing concrete (L/month)	Water for cutting and cleaning lanes (L/month)	Water for human consumption (L/month)	Total water demand (L/month)	Working days in the month (Days)	Daily average demand on working days (L/day)
January	51,547	5,000	91,520	148,067	22	6,730
February	352,740	49,700	79,040	481,480	19	25,341
March	201,283	19,400	87,360	308,043	21	14,669
April	186,805	35,500	87,360	309,665	21	14,746
May	294,918	5,600	91,520	392,038	22	17,820
June	426,211	40,600	87,360	554,171	21	26,389
July	454,564	37,300	91,520	583,384	22	26,517
August	618,232	68,800	95,680	782,712	23	34,031
September	192,708	1,600	83,200	277,508	20	13,875
October	203,768	32,500	87,360	323,628	21	15,411
November	372,925	-	83,200	456,125	20	22,806
December	297,372	-	83,200	380,572	20	19,029

**Table 3.** Water demand that can be replaced with rainwater.

Month	Water demand on working days that can be replaced with rainwater (L/day)
January	-
February	11,341
March	669
April	746
May	3,820
June	12,389
July	12,517
August	20,031
September	-
October	1,411
November	8,806
December	5,029



**Figure 4.** Water demand that can be supplied either by the artesian well and the water company or rainwater.

### 3.2. Potential for potable water savings

After defining the water demand that can be replaced with rainwater, simulations were performed using *Netuno 4* to determine the ideal rainwater tank capacity. Simulations were run for three different scenarios, as explained in section 2. The input data for the three scenarios are shown in Table 4. The daily water demand considered was the average daily demand on working days; the demand considered was null over weekends and holidays.

**Table 4.** Input data used in the *Netuno* computer programme.

Input data		
Initial date	1 <sup>st</sup> Sep 2001	
First flush disposal (mm)	2	
Roof area (m <sup>2</sup> )	First scenario:	15.346,71
	Second scenario:	3.266,71
	Third scenario:	8.767,89
Total water demand	Variable (according to data shown in Table 3)	
Number of occupants	1	
Rainwater demand (% of the total water demand)	100	
Runoff coefficient	0.8	
Capacity of the upper rainwater tank (L)	5000	
Percentage of the upper rainwater tank volume in which there is pumping from the lower to the upper tank (%)	5	
Capacity of the lower rainwater tank	Simulation for various capacities	
Maximum capacity of the lower rainwater tank (L)	50,000	
Interval between capacities (L)	1000	
Difference between potentials for potable water savings through rainwater usage (%/m <sup>3</sup> )	1	

It was considered that the factory had only one occupant because the water demand was considered taking into account the total number of employees and the water demand for all the other uses in the factory. It was considered the installation of an upper rainwater tank of 5000 L so that the rainwater could be pumped from the lower rainwater tank to the upper one and then distributed by gravity. The results obtained from the simulations for the three scenarios are shown in Table 5.

**Table 5.** Results obtained from the computer simulations.

Item	First scenario	Second scenario	Third scenario
Ideal lower rainwater tank capacity (L)	25,000	22,000	25,000
Potential for potable water savings for the ideal tank capacity (%)	55.4	47.4	54.6
Potential for potable water savings considering a lower tank capacity equal to 25,000 L (%)	55.4	50.2	54.6

### 3.5. Financial analysis

The cost of labour was obtained by consulting specialised companies in the region; it was estimated as R\$75,000 for the first scenario, R\$18,000 for the second scenario and R\$25,000 for the third one. The motor pump selected was the centrifugal pump, model BC-91S, 1 HP.

The costs of the rainwater harvesting systems for the three scenarios are shown in Table 6. The cost of accessories refers to equipment such as gutters, piping connections, float switches, solenoid valves and other necessary items for the system.

**Table 6.** Costs for implementing the scenarios.

Component	Cost (R\$)		
	First scenario	Second scenario	Third scenario
Upper water tank	1,799.00	1,799.00	1,799.00
Lower water tank	7,544.72	7,544.72	7,544.72
Labour costs	75,000.00	18,000.00	25,000.00
Piping	116,449.02	29,627.59	33,998.05
Accessories	112,084.86	22,013.36	50,456.06
Pumps	1,659.80	1,659.80	1,659.80
Total	314,537.40	80,644.47	120,457.63

For the financial analysis, the data shown in Table 7 were used as input data to *Netuno*. The results for the financial analysis simulated using *Netuno* are shown in Table 8.

By analysing the results, it can be noticed that the first scenario did not present economic feasibility. This happened because the installation of gutters and pipes was considered in all roofs in this scenario. Thus, the initial costs were much higher than the costs for the two other scenarios. On the other hand, the potential for potable water

savings was not much higher than the two other scenarios. The second and third scenarios were economically feasible. Even though the second scenario presented the lowest payback, it is the scenario that presents the lowest potential for potable water savings.

**Table 7.** Input data for the financial analysis.

Lower rainwater tank capacity (L)	25,000	
Water tariff	Below 10 m³ per month	65.00
	– Fixed tariff (R\$)	
	Above 10 m³ per month	10.7866
	– Variable tariff (R\$/m³)	
Sewage tariff (R\$)	0	
Inflation (% per month)	0.37	
Period of readjustment of the water and electricity tariffs (months)	12	
Period of analysis (years)	20	
Minimum acceptable rate of return (% per month)	0.5	
Cost of the lower rainwater tank (R\$)	7,545.00	
Cost of the upper rainwater tank (R\$)	1,799.00	
Cost of labour (R\$)	First scenario:	75,000.00
	Second scenario:	18,000.00
	Third scenario:	25,000.00
Cost of piping (R\$)	First scenario:	116,449.00
	Second scenario:	29,628.00
	Third scenario:	33,998.00
Cost of accessories (R\$)	First scenario:	112,085.00
	Second scenario:	22,013.00
	Third scenario:	50,456.00
Power of the pump (HP)	1	
Efficiency of the pump (%)	38.8	
Flow rate of the pump (L/h)	6200	
Starting time of the pump (s)	3	
Cost of each pump (R\$)	829.90	
Backup pump	Yes	
Electricity tariff (R\$/kWh)	0.36506	
Taxes over the electricity tariff (%)	25	

Table 8. Results of the financial analysis.

Indicator	First scenario	Second scenario	Third scenario
Net present value (R\$)	-155,247.12	61,207.27	33,740.93
Discounted payback period (months)	-	127	181
Internal rate of return (%/month)	-0.05	1.07	0.73

### 3.6. Rainwater quality

The possibility of using rainwater for the production and cutting concrete pieces and cleaning lanes was considered. In order to consider the use of rainwater to manufacture concrete as viable, it was necessary to perform some analyses in samples of rainwater collected in-situ. The objective of such analyses was to evaluate if the rainwater was adequate for manufacturing concrete and did not affect its strength or durability.

Tests were performed for four samples of rainwater collected at the same place but in different days. The first collection was performed for two samples with no first flush disposal; meanwhile, the second collection was performed for two other samples considering a first flush disposal equal to 2 mm.

The results obtained from the preliminary tests are shown in Table 9. Average results are shown for the quantity analysis. The rainwater from the second collection was approved in all the requirements established in NBR 15900 [12]. However, the first collection did not meet the criteria about the presence of organic matter, even though it was approved according to the other preliminary analysis criteria. If a sample is not approved in these criteria, it does not mean that such rainwater cannot be used for manufacturing concrete. Such rainwater can still be used, as long as it is approved in the concrete setting time test and the concrete strength test.

The results of the concrete setting time and concrete strength tests are shown in Table 10, and the limits for acceptance of the concrete setting time and concrete strength tests are shown in Table 11.

The limits for acceptance were calculated based on the results for concrete manufactured using distilled water. The standard NBR 15900 [12] defines that concrete samples can be approved if the beginning and end of setting times present a maximum variation of 25% when compared to concrete produced using distilled water. As for the strength of the concrete specimens, the Brazilian standard defines that they must present a minimum strength of 90% of the strength of the concrete specimens produced using distilled water. By analysing the results, it is possible to conclude that both rainwater samples were approved in the concrete setting time and concrete strength criteria, since the results meet the limits shown in Table 11. The water collected from the artesian well, which is used in the factory, has its potability assured by tests performed periodically. The standard NBR 15900 [12] considers that if the water potability is assured, it can be considered adequate for manufacturing concrete without the need for further testing. Thus, even though the concrete manufactured using water from the artesian well did not



achieve 90% of the concrete strength of the concrete with distilled water, the water collected from the well can still be considered adequate for manufacturing concrete according to NBR 15900 [12].

The results of the chloride tests are shown in Table 12, and the results of the sulfate tests are shown in Table 13. Two samples from the first rainwater collection were tested, representing the rainwater with no first flush disposal. In order to test the chloride and sulfate levels in the second rainwater collection, which considered a 2 mm first flush disposal, two other samples were tested.

**Table 9.** Results from the preliminary tests.

Test	Requirement	First rainwater collection	Second rainwater collection
Oils and fats	No more than visible traces	Oils and fats were not found	Oils and fats were not found
Detergents	Any visible foam must disappear in 2 minutes	No foam was observed after 2 minutes of rest	No foam was observed after 2 minutes of rest
Colour	Light yellow to colourless	Colourless	Colourless
Solid material (mg/L)	Maximum of 50,000 mg/L	52	56
Odour	The water must be odourless and must not present hydrogen sulphide odour after the addition of hydrochloric acid	Odourless and did not present hydrogen sulphide odour after the addition of hydrochloric acid	Odourless and did not present hydrogen sulphide odour after the addition of hydrochloric acid
Acids (pH)	$\geq 5$	6.44	6.23
Organic matter (mg/L)	The colour of the water must be equal or brighter than the standard solution after the addition of NaOH	8.18	0

**Table 10.** Results of the concrete setting time and concrete strength tests.

Sample	Distilled water	First rainwater collection	Second rainwater collection	Artesian well water
Start of setting (h)	4:00	4:20	4:10	-
End of setting (h)	5:30	5:40	5:40	-
Strength of CPI at 7 days (MPa)	47.23	44.15	50.93	41.51
Strength of CPII at 7 days (MPa)	46.93	47.75	50.51	40.86
Average strength at 7 days (MPa)	47.08	45.95	50.72	41.18
Strength CPI at 28 days (MPa)	57.82	57.80	58.64	51.31
Strength CPII at 28 days (MPa)	57.16	60.06	58.53	54.66
Average strength at 28 days (MPa)	57.49	59.20	58.58	52.98

**Table 11.** Limits for acceptance of the rainwater being tested.

Criteria	Minimum limit	Maximum limit
Start of setting (maximum difference of 25% from the distilled water) (h)	3:00	5:00
End of setting (maximum difference of 25% from the distilled water) (h)	4:08	6:52
Start of setting of CP IV 32 cement (ABNT, 2018b) (h)	1:00	-
Limits for end of setting of CP IV 32 cement (ABNT, 2018b) (h)	-	12:00
Concrete strength at 7 days (90% of the distilled water strength) (MPa)	42.37	-
Concrete strength at 28 days (90% of the distilled water strength) (MPa)	51.74	-

**Table 12.** Results of the levels of chloride.

Source	Level of chloride in sample 1 (mg/L)	Level of chloride in sample 2 (mg/L)	Average level of chloride (mg/L)
First rainwater collection	0	0	0
Second rainwater collection	2.5	2.0	2.25

Table 13. Results of the level of sulfates.

Source	Level of sulfates in sample 1(mg/L)	Level of sulfates in sample 2 (mg/L)	Average level of sulfates (mg/L)
First rainwater collection	2.65	2.25	2.45
Second rainwater collection	2.43	2.55	2.49

The standard NBR 15900 [12] establishes limits for the presence of chloride in the tested water according to the use intended for the concrete. The possible uses for concrete are precast concrete or grout, reinforced concrete and standard concrete. The factory manufactures precast concrete and reinforced concrete elements. Since the maximum chloride level for precast concrete is lower (stricter), the maximum chloride limit adopted was the one defined for this concrete category, which is 500 mg/L. As for the chloride levels, the rainwater from both the first and the second collection was approved.

The maximum level for acceptance of the tested rainwater for the presence of sulfates established in NBR 15900 [12] is 2,000 mg/L. Since the level of sulfates in the rainwater samples from the two collections is lower than the acceptable limit, both samples were approved in this criterion.

#### 4. Conclusions

This paper investigated if rainwater could be used to manufacture precast concrete in a factory located in southern Brazil. The potential for potable water savings due to rainwater use as well as the economic feasibility analysis and the rainwater quality were assessed.

The budgets for the installation of the rainwater harvesting systems were estimated, and the economic feasibility of three scenarios was evaluated. The first scenario did not present economic feasibility; meanwhile, the payback period for the second scenario was 127 months, and for the third scenario it was 181 months (internal rates of return were 1.07 and 0.73% per month, respectively). For the economically feasible scenarios, the potential for potable water savings would range from 50.2% to 54.6%.

The quality of the rainwater was also assessed through tests using rainwater samples collected from the roof of the factory. The samples met the requirements established by Brazilian standards. Thus, the rainwater collected was considered appropriate for manufacturing concrete and for cutting elements and cleaning lanes in the factory studied herein. However, we acknowledge that the rainwater quality should be assessed over a whole year.

In addition to being economically feasible, rainwater harvesting systems can promote the sustainable use of water and also contribute to increasing the impression of clients about the company. Companies which adopt sustainable strategies, such as the use of rainwater, have more visibility and show their clients that the company is concerned with reducing the impact caused to the environment.

**Author Contributions:** Supervision, E.G.; planning the experiments, G.K.B.; carrying out the experiments, G.K.B.; writing—review & editing, E.G. All authors have read and agreed to the published version of the manuscript.

**Funding:** This research received no external funding

**Institutional Review Board Statement:** Not applicable

**Informed Consent Statement:** Not applicable

**Data Availability Statement:** Data are contained within the article

**Conflicts of Interest:** The authors declare no conflict of interest

## References

1. Amos, C. C.; Rahman, A.; Gathenya, J. M. Economic analysis and feasibility of rainwater harvesting systems in urban and peri-urban environments: a review of the global situation with a special focus on Australia and Kenya. *Water*, **2016**, v. 8, n. 4, p. 149.
2. Ghisi, E.; Schondermark, P. N. Investment feasibility analysis of rainwater use in residences. *Water Resources Management*, **2013**, v. 27, n. 7, pp. 2555-2576.
3. Fernandes, L. F. S.; Terêncio, D. P. S.; Pacheco, F. A. L. Rainwater harvesting systems for low demanding applications. *Science of the Total Environment*, **2015**, v. 529, pp. 91-100.
4. ABNT. NBR 15527 Água de chuva – Aproveitamento de coberturas em áreas urbanas para fins não potáveis – Requisitos [Rainwater – Harvesting from roofs in urban areas for non-potable uses – Requirements]. Associação Brasileira de Normas Técnicas, Rio de Janeiro, Brazil, **2019**. [In Portuguese].
5. Zhang, X.; Wu, Y.; Shen, L. Embedding "green" in project-based organisations: the way ahead in the construction industry? *Journal of Cleaner Production*, **2015**, v. 107, pp. 420-427.
6. Pessarelo, R. Estudo exploratório quanto ao consumo de água na produção de obras de edifícios: avaliação e fatores influenciadores [Study on water consumption in the production of building works: evaluation and influencing factors]. Escola Politécnica, Universidade de São Paulo, São Paulo, Brazil, **2008**. [In Portuguese].
7. Santos, C. P.; Silva, S. R.; Cerqueira, C. A. Water consumption in construction sites in the city of Recife/PE. *Electronic Journal of Geotechnical Engineering*, **2015**, v. 20, n. 7, pp. 1711-1726.
8. Souza, T. D.; Ghisi, E. Harvesting rainwater from scaffolding platforms and walls to reduce potable water consumption at buildings construction sites. *Journal of Cleaner Production*, **2020**, v. 258, 120909.
9. McCormack, M.; Treloar, G. J.; Palmowski, L.; Crawford, R. Modelling direct and indirect water requirements of construction. *Building research and information*, **2007**, v. 35, n. 2, pp. 156-162.
10. Zhong, Y.; Wu, P. Economic sustainability, environmental sustainability and constructability indicators related to concrete and steel projects. *Journal of Cleaner Production*, **2015**, v. 108, pp. 748-756.
11. Cimento Itambé, 2015. Água da chuva para produzir concreto. É possível?, **2015** [Rainwater to produce concrete. Is it possible?]. <http://www.cimentoitambe.com.br/agua-da-chuva-para-produzir-concreto/>. Available online 6 March 2018.
12. ABNT. NBR 15900 Água para amassamento do concreto [Water for concrete manufacture]. Associação Brasileira de Normas Técnicas, Rio de Janeiro, Brazil, **2009**. [In Portuguese].
13. Bedoya-Montoya, C. M.; Medina-Restrepo, C. A. El concreto elaborado con aguas lluvia como aporte ambiental desde la construcción [Concrete made with rainwater as an environmental contribution from construction]. *Revista Facultad de Ingeniería*, **2016**, v. 25, n. 41, pp. 31-39. [In Spanish].
14. INMET. Instituto Nacional de Meteorologia, **2018** [National Institute of Meteorology]. <http://www.inmet.gov.br>. Available online 30th Aug 2018. [In Portuguese].
15. Ghisi, E.; Cordova, M. M. Netuno 4. Computer programme. Universidade Federal de Santa Catarina, Departamento de Engenharia Civil, **2014**. <http://www.labee.ufsc.br/>. [In Portuguese].
16. IBGE. Instituto Brasileiro de Geografia e Estatística, **2018** [Brazilian Institute for Geography and Statistics]. <http://www.ibge.gov.br>. Available online 2 October 2018. [In Portuguese].
17. Maravas, A.; Pantouvakis, J. A New Approach to Studying Net Present Value and the Internal Rate of Return of Engineering Projects under Uncertainty with Three-Dimensional Graphs. *Advances in Civil Engineering*, **2018**, v. 2018.
18. Mishan, E. J.; Quah, E. Cost-Benefit Analysis. Routledge, New York, **2007**, 5th edition.
19. ABNT. NBR 12655 Concreto de Cimento Portland – Preparo, controle, recebimento e aceitação – Procedimento [Portland Cement Concrete – Preparation, control, receipt and acceptance – Procedure]. Associação Brasileira de Normas Técnicas, Rio de Janeiro, Brazil, **2015**. [In Portuguese].
20. ABNT. NBR 15577 Agregados – Reatividade álcali-agregado [Alkali-aggregate reaction]. Associação Brasileira de Normas Técnicas, Rio de Janeiro, Brazil, **2018**. [In Portuguese].
21. ABNT. NBR 16607 Cimento Portland – Determinação dos tempos de pega [Portland Cement – Determination of the concrete setting time]. Associação Brasileira de Normas Técnicas, Rio de Janeiro, Brazil, **2017**. [In Portuguese].
22. ABNT. NBR 5738 Concreto – Procedimento para moldagem e cura de corpos de prova [Concrete – Procedure for molding and curing concrete specimens]. Associação Brasileira de Normas Técnicas, Rio de Janeiro, Brazil, **2015**. [In Portuguese].
23. ABNT. NBR 5739 Concreto – Ensaio de compressão de corpos de prova cilíndricos [Concrete – Strength compression test in cylindrical concrete specimens]. Associação Brasileira de Normas Técnicas, Rio de Janeiro, Brazil, **2018**. [In Portuguese].