Design and Applications of Multi-Frequency Holographic Subsurface Radar: Review and Case Histories

Sergey Ivashov[1], Lorenzo Capineri[2], Timothy Bechtel[3], Vladimir Razevig[1], Masaharu Inagaki[4], Nikolay Litchkov[5], and Ahmet Kizilay[6]

1 – Remote Sensing Laboratory, Bauman Moscow State Technical University, Russia
sivashov@rslab.ru , vrazevig@rslab.ru
2 – Department of Information Engineering, University of Florence, Italy,
lorenzo.capineri@unifi.it
3 – Department of Earth & Environment, Franklin & Marshall College, PA, USA,
timothy.bechtel@fandm.edu
4 – Walnut Ltd., Tokyo, Japan, ina_mas@beige.plala.or.jp
5 – Bulgarian Academy of Sciences – IMSET, Bulgaria, niki0611@abv.bg
6 – Electronics and Communications Engineering Department, Yildiz Technical
University, Turkey, akizilay@yildiz.edu.tr

Corresponding author: Lorenzo Capineri lorenzo.capineri@unifi.it

Abstract: Holographic subsurface radar (HSR) is not currently not in widespread usage. This is due to an historical perspective in the ground penetrating radar (GPR) community that the high attenuation of electromagnetic waves in most media of interest, and the inability to apply time-varying gain to the continuous wave (CW) HSR signal precludes sufficient effective penetration depth. While it is true that the fundamental physics of HSR, with its use of a CW signal, does not allow amplification of later (i.e. deeper) arrivals in lossy media (as is possible with impulse subsurface radar — ISR), HSR has distinct advantages. The most important of these is the ability to do shallow subsurface imaging with a resolution that is not possible with ISR. In addition, the design of an HSR system is simpler than for ISR due to the relatively low-tech transmitting and receiving antennae. This paper provides a review of the main principles of HSR through an optical analogy and describes possible algorithms for radar hologram reconstruction. We also present a review of the history of development of systems and applications for HSR of the "RASCAN" type which is possibly the only commercially available holographic subsurface radars. Among the subsurface imaging and remote sensing applications considered are humanitarian demining, construction inspection, nondestructive testing of dielectric aerospace materials, surveys of historic architecture and artworks, paleontology, and security screening. Each application is illustrated with relevant data acquired in laboratory and/or field experiments.

Keywords: Holographic subsurface radar, ground penetrating radar, nondestructive testing, cultural heritage objects, landmine detection, security applications.

1. Introduction

The earliest (1960s/80s) subsurface radars were developed for electromagnetic detection of objects up to several meters below the ground surface [1], [2], [3]. This was dictated by the achievable (at that time) operational frequency range of 100 MHz to 500 MHz for impulse radar. Depth resolution in this band was limited to 0.5 m to 1 m in the common media of soils and fresh water ice [3]. These early applications coined the now widely used phrase Ground Penetrating Radar or GPR. This acronym is still widely used despite the fact that modern subsurface radars have developed much wider applications deserving of the more accurate name of surface-penetrating radar [2] or subsurface interface radar (SIR) [4].

All types of so-called GPR can be divided into three categories by the characteristics of the emitted signal:

- Time-domain impulse radars
- Frequency-modulated continuous-wave radars
- Holographic radars.

This classification, as adapted from [2], is presented in Fig. 1. The last type of subsurface radar — holographic subsurface radar (HSR) is the topic of this review. Note that (contrary to the figure, and as described below) HST can also be multi-frequency.

Fig. 1 Classification of main types of subsurface radar [2].

In optics, the term hologram means an interference pattern between two electromagnetic waves with one of them modulated by diffraction. The etymology of the term hologram comes from ancient Greek with the meaning "whole description" or "whole picture".

The first HSR may be the work of Keigo Iizuka who, with only the rudimentary technology available in the late 1960s, used polaroid film to register holograms from signals in the millimeter range (frequency = 34 GHz) [5], [6].

Due to technological limitations of the time, the first HSRs were continuous wave (CW), but it was immediately evident that for inspection of materials at great depth, signal attenuation was a serious limitation to development of applications for this tool. Also, due to the CW signal, it was not possible to compensate for attenuation with depth or distance by applying a time-varying gain using front-end electronics [2], [7] as is possible for impulse subsurface radar (ISR). After later theoretical and experimental studies, a solution has been found for the realization of an HSR for inspecting low-loss media at shallow depths. The great advantage of this type of HSR is that it can record the amplitude of the interference pattern for each position of an antenna moving across the inspected surface, providing a subsurface image immediately upon completion of the scanning pattern. These images can be considered "real-time" since they do not in principle need any processing; only a device for recording the composite interference pattern (i.e. the sensor plus memory). It will be shown that this type of radar achieves a good compromise in the trade-off between depth of investigation and spatial resolution in the image plane [8]. These characteristics of HSR (i.e. real-time and high-resolution) have, in particular, motivated considerable research on its use for military and humanitarian landmine detection and identification [9], [10], [11].

HSR differs from the two other types of GPR in that it provides (from the raw data) plan-view (as opposed to cross-sectional) radar images [8]. In this sense, HSR is analogous to the optical hologram technology first achieved by D. Gabor in 1948 [12]. Gabor's method is illustrated for a point target hologram as shown in Fig. 2.

Fig. 2 Simple optical hologram of a point target.

In this example, the interference between a plane wave incident perpendicular to the recording plane and the wave diffracted by the point reflector at a distance **h** from the plane, can be recorded as a variation in amplitude by an analog or digital sensor. It is assumed by convention that the reference plane wave has constant phase and amplitude **u_o**.

We denote by **$u(r)$** the distribution of the amplitude of the divergent hemispherical diffracted wave. This wave has an amplitude distribution defined by **$u_1(r)$** on the recording plane. The variation of this amplitude on the plane forms the holographic image.

$$u(r) = u_1(r)\exp(i\varphi(r)) \tag{1}$$

with phase **φ** given by

$$\varphi(r) = \frac{2\pi}{\lambda}\sqrt{r^2 + h^2} \tag{2}$$

where **λ** is wavelength, and **r** is radius or distance on the recording plate from the axis of symmetry directly beneath the target. Interference of these two waves (**u_o** and **u**), the image plane records an intensity distribution **I** [13], [14]

$$I(r) = u_o^2 + u_1^2(r) + u_o u_1(r)[\exp(i\varphi(r)) + \exp(-i\varphi(r))]. \tag{3}$$

which describes a Fresnel zone plate [15] or interference pattern as shown in the lower right corner of Fig. 2.

To reconstruct a hologram, the interference pattern is illuminated by a wave **u_{or}** identical to the reference wave. So, directly behind the interference pattern, the distribution pattern or holographic image looks like

$$u_p(r,0) = u_{or}[u_o^2 + u_1^2(r)] + u_{or}u_o u_1(r)\exp(i\varphi(r)) + u_{or}u_o u_1 \exp(-i\varphi(r)). \tag{4}$$

It is interesting to analyze the composition of the transmitted wave by evaluating the individual terms of equation (4). The first term is the transmitted plane wave or reference, while the second and third terms correspond to the virtual and real images of the object respectively.

Gabor's method [13] had many limitations on the quality of images and presented complexities that make practical application difficult. Thanks to the invention of the laser and its rapid adoption in laboratories worldwide, a solution was proposed by E.N. Leith and J. Upatnieks [16] who solved the limitations of the Gabor system. Their method uses the coherence of incident laser light at a certain angle to the registration plate (or image plane), as shown in Fig. 3. Subsequent innovations in optical holography have similarly involved the use of different combinations of mirrors and beam splitters.

Fig. 3 Schematic optical holography using an inclined beam (e.g. laser).

The inclined reference wave configuration (Fig. 3) is well-suited to modern optical holography, since the attenuation of air in the visible spectrum is negligible for the characteristic size of the system. In aerial or satellite remote sensing, HSR has been successful due to the very low levels of attenuation and dispersion in clear air or a vacuum. However, for subsurface inspection of materials with much higher attenuation(i.e. "lossy media"), using typical operating frequencies below 1 GHz, applications have been limited. One of the areas where HSR has found successful applications is security. In fact, HSR scanners have been designed to detect concealed weapons at airport boarding gates in near-real-time [17], [18].

Systems for optical holography and microwave (MW) or radar holography differ substantially in signal wavelength, and consequently the characteristic dimensions of the recording apparatus. This difference can be estimated by the ratio between the characteristic dimension of the system d and the signal wavelength λ. For an optical system, $d/\lambda \cong 10^6$, while for HSR it is $<10^1$ due to the high attenuation in lossy media requiring larger sources – almost comparable to the wavelength. Furthermore, the laws governing the propagation of electromagnetic waves also differ in the two cases: while the laws of geometric optics are valid for optical systems (see Fig. 2 and Fig. 3), these are not strictly valid for the analysis and development of HSR where attenuation, diffraction and near-field coupling to the medium must be considered. Therefore, only the basic principles are common to optical holography and HSR. Nevertheless, the analogy is critical for understanding the physics of HSR, for interpretation of subsurface radar holograms, and for derivation of hologram reconstruction algorithms [8], [19], [20], [21], [22].

Although there are practical differences, it is interesting to compare optical holograms with HSR holograms. D. Gabor's first published holograms [12], are presented in Fig. 4. In Fig. 4a (top left) is the original photomicrograph. Fig. 4b (top right) is the micrograph directly photographed through the optical system used for reconstruction. The interference pattern is shown in Fig. 4c (lower left). Finally, Fig. 4d (lower right) shows the interference pattern illuminated to reconstruct the original, and the letters have become legible again.

Fig. 4 Gabor's optical hologram [12].

To produce an MW analogy to Gabor's original optical hologram, an HSR experiment devised using a target of metallic letters affixed to a sheet of paper (Fig. 5). The sheet with letters was covered by a 12-mm gypsum board, and scanned with a CW RASCAN model HSR (4 GHz). Additional gypsum boards were added for subsequent scans as shown in Fig. 6.

To obtain an HSR image, it is necessary to perform accurate spatial sampling. Therefore, the holograms in Fig. 6 were recorded as parallel lines with a fixed spacing and fixed sampling step along lines. The radar head was swept manually along these parallel lines with sampling triggered by an optical survey wheel [23]. To avoiding distortions in the HSR image, spatial sampling errors must be much smaller than the signal wavelength in the scanned medium. The time to complete a scan depends on the size of the area and the number (spacing) of raster lines. Typically, for a 4 GHz RASCAN HSR, the distance between the parallel lines is 0.5 cm with this value is also used for the spatial sampling along the lines for a pixel size of 0.5 cm × 0.5 cm. This is a compromise between scan time and image quality, but it is also necessary to consider the spatial resolution of the radar at the depths of investigation, which in turn depends on the type of antenna and signal frequency [24].

Fig. 5 Paper sheet with aluminum foil letters (ruler is 12 inches or 30.48 cm).

In Fig. 6, we show eight MW holograms recorded at 4 GHz frequency [8] and different depth (numbers of covering gypsum plates). The first three images correspond to target depth increasing using 1, 2, and 3 gypsum plates. It can be seen that the word RASCAN remains legible. When the thickness of the gypsum plates goes to 4 and above, the letters become increasingly blurred. This is due to first principles of the propagation of electromagnetic waves: At shallow depth, the reflection to the nadir from the metal surface of the letters has very high amplitude – greater than the level of the reference signal and other oblique reflections (off-nadir).

At greater depth (thickness), the radar antenna, due to its directivity, receives off-nadir reflections from the metal letters and the signal level begins approach the reference level – see equation (4). This phenomenon also explains the non-uniformity of the brightness (amplitude) of the letters which manifests as an undulation. At the maximum depth of about 10 cm obtained by stacking 10 gypsum plates, the image of the hologram obtained with the RASCAN radar resembles the optical hologram of Gabor. The comparison of the images shown in Fig. 4 and

Fig. 6 shows, albeit qualitatively, the differences between holograms in the optical and MW spectra. Due to the different ratios between characteristic dimensions and wavelength for these holograms, the number of visible Fresnel zones varies greatly, from 3 to 4 orders or more for these two types of holograms.

R holograms	Number of plaster sheets over letters
	1
	2
	3
	4
	5
	6
	7
	8

Fig. 6 RASCAN holograms recorded through varying stacks of plaster sheets.

When using HSRs for soil inspection, the medium may have low attenuation when dry and sandy, but may have high dispersion. The variability in the dielectric properties of these natural materials has a great influence on the quality of radar holograms. Experiments have shown that in many cases, this variability makes the interpretation of holograms impossible. These studies, both theoretical and experimental, for the investigation of soils are available in various publications [7], [13], [19], [20], [25]. Since the attenuation and heterogeneity of the medium, and the scale of roughness of the surface limit the maximum effective depth of penetration for HSR, the main advantage of an ISR the ability to investigate greater depths while maintaining a high contrast and signal-to-noise ratio thanks to the time-varying gain in a stroboscopic receiver, which amplifies deeper reflected signals that have a longer time of flight (TOF). In a CW radar system, it is not possible to discriminate reflections by their TOF, so applications for HSR are limited to reduced depths.

At the shallow depths where HSR is applicable, its main advantage is the ability to record images that have higher resolution in plan-view than ISR because of the compactness of the antenna and the easy selection of frequency. High resolution in plan-view at shallow depths is extremely important for many applications, including: diagnostics of composite materials in aerospace and other industries [26], [27], [28], [29], [30], [31], [32], [33], [34]; determination of building details and constructions including cultural heritage monuments [35], [36], [37], [38], [39]; archaeological and paleontological imaging [40], [41], [42]; landmine detection and discrimination [9], [10], [11], [43], [44], [45], [46]; security systems [47], [48], [49], [50], [51], [52], [53]; detection of wood-boring insect damage [54]; and medical imaging [55], [56], [57], [58].

2. HSR design and image reconstruction

The main problem in designing a holographic subsurface radar is selection of the reference

Fig. 7 Design of holographic subsurface radar antenna [59]. The drawing shows the main elements of the design as described in the following: (1) emitting feed antenna, (2) receiver feed antenna for parallel polarization, (3) receiver feed antenna for cross polarization, (4) round waveguide, (5) open end of waveguide. The following dimensional parameters are: D – waveguide diameter, L – waveguide length, *l* – distance between closed end of waveguide and plane of pin antennas 1 and 2.

Fig. 8 Radar image of reinforcing in concrete at 3.9 GHz. Mesh spacing is 20 cm x 20 cm at a depth of 3 cm to 4 cm [39].

signal. Usually, the emitted signal is used, but the simplest way is to produce a coupling signal between the transmitter and receiver antennae. This requires an antenna appliance that can guarantee the independence of the phase and amplitude of this coupling signal from properties of the sounding surface and heterogeneities in the medium. To achieve this, for the RASCAN type radar, the antennae are mounted in a round, open-ended waveguide as in Fig. 7 [8], [59], [60].

Initially, two receivers were used; for parallel and crossed polarizations, with both recorded simultaneously for several frequencies [39]. The recording of cross polarization enhanced detection of elongate targets by reducing the influence of the angle between the long axis of the object and the plane of the receiving antenna feed.

This scheme is simple, but it allows recording of only amplitude radar holograms. This is sufficient when registering holograms in media with a high dielectric constant ε and a high level of attenuation of electromagnetic waves [19], [20] which produces no outer Fresnel zones in the recorded image (see Fig. 8). For such images, digital reconstruction of the radar hologram does not significantly improve the image. The interference pattern alone provides a good approximation of the target shape in plain view.Another feature of images recorded at crossed polarizations is the asymmetry of point targets as in Fig. 9a. In this case, the interference pattern depends on the orientation of the antenna. However, at parallel polarization (Fig. 9b), the symmetrical concentric circles in the interference pattern are directly analogous to the optical image in Fig. 2.

Fig. 9 Cross a) and parallel b) polarization received signals recorded at frequency of 4.0 GHz [39]. These images were recorded for a test wall inside of which small coins and metal wires were placed at different depths.

RASCAN style HSR has been designed with programmable electronics capable of emitting a sequence of discrete frequencies (up to a maximum of 5). This multifrequency operating mode is fundamental for a CW HSR since the phase difference between the sinusoidal reference and object waves for a target at a certain depth can result in zero amplitude in the hologram. In fact, for a given frequency and a medium with a constant propagation speed, there will be cyclically repeating distances (depths) that provide a phase which cancels the sinusoidal function and therefore the detection of the object [62]. The effect of changes in contrast with frequency is demonstrated in an animation in [62]. This animation recorded by RASCAN HSR presents a multi-frequency hologram of a rectangular Soviet PTM-3 antitank (AT) mine buried in sand. Each frame of the animation corresponds to a selected frequency of the radar. Note that there are frequencies at which the mine is clearly visible, and others where it nearly disappears. Recording at discrete frequencies within the antenna band [64] ensures that any reflective target will appear in an image for at least at one frequency.

Mathematically, this phenomenon can be expressed by considering a reflector (target) plane perpendicular to the propagation direction of the incident electromagnetic wave generated by the holographic antenna. The waves emitted by the HSR have a constant frequency ω, but amplitude and phase that are not constant over time. A_r is defined as the amplitude of the reflected wave of constant value, and with phase φ_r depending on the depth of the plane reflector.

$$\varphi_r = 2\sqrt{\varepsilon}\,\frac{l\omega}{c} + \Delta\varphi \ , \tag{5}$$

where $\Delta\varphi$ is the phase shift which arises upon reflection of the electromagnetic wave from the object, ε is the dielectric permittivity of the medium, l is the distance to the object, ω is the angular frequency, and c is the speed of light. Thus, the reflected signal as a function of time t can be written as

$$A_r\cos(\omega t + \varphi_r) \tag{6}$$

Reflected wave (6) mixes with a constant-phase radar reference signal of the form

$$A_o\cos(\omega t + \varphi_o), \tag{7}$$

where A_o and φ_o are the amplitude and phase of the reference signal, respectively. The reflected signal (6) is mixed with the radar reference signal (7) at the receiver. The amplitude of the signal in the mixer output at the difference frequency is given by

$$A_r A_o\cos(\varphi_o - \varphi_r). \tag{8}$$

From this relation one can conclude that, if the phase shift between the reference signal and reflected one is close to

$$\varphi_o - \varphi_r = (k+1/2)\pi \ , \ k = 0,1,2,\ldots \tag{9}$$

the level of recorded signal from the object is low, and at

$$\varphi_o - \varphi_r = k\pi \ , \ k = 0,1,2,\ldots \tag{10}$$

the recorded signal level is maximal. To avoid "blind" depths the original RASCAN type HSR used multiple discrete frequencies across a bandwidth that ensured high target contrast for one or more images [63].

Typical surveyed media (soils, concrete, etc.), often have a relatively high dielectric constant due to moisture content. This also enhances electrical conductivity, and therefore attenuation so that the outer Fresnel zones of the holographic interference pattern are suppressed – sometimes to the point where only reflections in nadir are recorded. In these cases, the interference pattern strongly resembles the footprint of the target, and no image processing is needed [19], [20].

Fig. 10 Holographic Subsurface Radar RASCAN-5 [64].

However, for media with a high degree of transparency for MWs and a low level of ε, reconstruction of the hologram from a relatively complete interference pattern significantly improves the quality and resolution of HSR images [21]. To achieve this, a modification of the HSR (RASCAN-5) with accompanying software was developed (Fig. 10). The general layout of the radar antenna was retained, but the crossed polarized antenna channel was eliminated, and the generator signal was used as a reference signal. This allows recording of complex MW holograms of hidden objects. The radar antenna head containing both transmitter and receiver is connected via cable to a microcontroller unit with a USB link to an ordinary PC. The microcontroller unit drives the transmitter and receiver, digitizes data, and transmits them to the computer.

Fig. 11 Geometry of holographic imaging system.

RASCAN-5 allows the acquisition of complex holograms. In low loss media, where the outer fringes of the interference pattern are retained, the raw image is (somewhat paradoxically) poor. However, in these cases, hologram reconstruction algorithms can be adopted [21], [50], [66], [67], [69]. These make it possible to focus/improve the resolution of the HSR images at selected depths of investigation. For example, Fig. 11 illustrates the data acquisition method for reconstructing the MW hologram of an object that has a two-dimensional shape at a depth z_0.

The target is assumed to be flat, parallel to the scanning plane, lying at a constant depth z_0. The key relationships can be summarized as follows:

$$F(k_x, k_y) = \frac{1}{(2\pi)^2} \iint E(x, y)\, e^{-i(k_x x + k_y y)} dx dy \qquad (11)$$

$$S(k_x, k_y, z_0) = F(k_x, k_y)\, e^{i\sqrt{4(\omega\sqrt{\varepsilon}/c)^2 - k_x^2 - k_y^2} \cdot z_0} \qquad (12)$$

$$E_R(x, y, z_0) = \iint S(k_x, k_y, z)\, e^{i(k_x x + k_y y)} dk_x dk_y \qquad (13)$$

where E (x, y) is the recorded hologram. E (x, y) represents a complex quantity whose values are sampled by the holographic antenna on the scanning surface at z = 0. Applying the Fourier transform to E (x, y) in the space domain (x, y) we obtain the distribution F (k_x, k_y), that is the spectrum of the plane waves of the hologram; k_x and k_y represent the wave numbers

corresponding to x and y respectively. At a different coordinate z_0 or a parallel plane, it is possible to calculate the spectrum of the plane waves of the hologram S (k_x, k_y, z_0). From the latter, by means of the inverse Fourier transform, we can obtain ER (x, y, z_0), which represents the holographic image for $z = z_0$. The mathematical formulation of the calculation process is described by equations (11), (12), (13).

Since HSR is CW, target depths cannot be calculated from known wave propagation speed and TOF. However, depth can be estimated empirically by reconstructing ER (x, y, z_0) for a range of z_0 values, with the best focus occurring at a good approximation for the target depth. In general, the determination of the depth of a buried object through measurements with either ISR or HSR is typically a difficult problem requiring the solution of an inverse and ill-posed problem [70]. Another reconstruction algorithm based on Green's formula was proposed in [70]. Kirchhoff approximation [71] and less strict empirical algorithms used for the reconstruction of MW holograms of landmines was described in [44] and [72].

Often, scanning is performed on an uneven surface, which distorts HSR images. This is especially true when detecting plastic cased landmines that may have low dielectric contrast with soils and are located close to the (potentially uneven) scanned surface. The problem of reconstructing MW holograms for media with an uneven surface was considered in [73], [74] and [75].

3. Main applications of holographic subsurface radars

The greater effective sounding depth of ISR has led to its dominance in the GPR industry [76], [77]. However, HSR is preferred in specialty or niche applications requiring high resolution at only shallow depths. Thus, the early development and testing of HSR focused on application to landmine detection [45], [78], and mapping of plastic and metal pipes in concrete floors [7], [31]. Twenty years of further research has expanded the applications for HSRs, many of which are described in [79] with diverse examples below.

3.1. Landmine detection

In the latter two thirds of the 20[th] Century conflicts all over the world were characterized by widespread use of both antipersonnel (AP) and antitank (AT) mines. From the 1960s on, a significant proportion of deployed mines had plastic casings, and some had almost no metal, making them difficult to detect. Although use has declined since the 1998 Ottawa mine ban treaty an estimated tens of millions remain in over 60 countries worldwide. According to the Landmine Monitor, global mine casualties reached a minimum in 2013, and have risen steadily since [80]. Armed conflicts involving mines continue in places such as Afghanistan, Iraq, Mali, Libya, Myanmar, Nigeria, Syria, Ukraine and Nagorno-Karabakh. According to UN estimates, the average cost for demining is about $0.6/m^2$, with a daily coverage for a single operator of between 10 m^2 and 20 m^2 [82]. Casualties during demining are variable and unfortunately high, approaching 1 to 2 deaths for every 1,000 mines removed.

The widespread introduction of first wood-, then plastic-bodied and minimal metal mines in the second half of the 20[th] Century (starting with the infamous Schu-42 and PMD-6M in WWII) made metal detectors (MDs) ineffective. By the 1980s, significant research began on the use of radio waves to detect mines based on variations in the dielectric constant ε of the soil caused by the installation or presence of a mine [45].

The main problem with using radio-frequency devices for detecting plastic mines with low dielectric contrast with soil is a high level of false alarms caused by soil inhomogeneities and/or an uneven ground surface. Experience shows that with a false alarm rate of 1 to 2 per m^2, a sapper will reject any high-tech device and work with a simple probing spike – which is dangerous because it puts the sapper very close to potential explosive devices, and may trigger sensitive ones. One of the ways to reduce the level of false alarms is to obtain an image of a

target while it is still in the ground — allowing discrimination of actual mines from soil inhomogeneities [46], [78], [82].

Fig. 12 Mock-up of a wide-span system for mine detection.

Fig. 12 depicts a laboratory set-up of a wide-span mine detection system designed in the late 1980s [45], [46] consisting of five standard 600 MHz CW mine detector sensors (not yet called HSRs but quite similar in principal). The advantages of wide-span systems include higher scanning efficiency and the reduction of false alarms through recording of accurate images due to the fixed geometry of the sensors. This system was able to distinguish soil heterogeneities from mines, and could discriminate AT (20-cm to 30-cm diameter) from AP (7-cm to 12-cm diameter) mines [83].

The wide-span mine detector in Fig. 12 has a scanning swath width of 2 m, and is suspended over a 6-m test bed containing 1.5 m of soil. Fig. 13 shows one of the first tests of the radar array; an image of a metal pipe (labelled 1), two AT mines (metal casing TM-62M labelled 2, and plastic casing TC-6 labelled 3). Four is a brick, and five a 30 cm x 30 cm sheet metal plate. The depths of these objects vary from 5 cm to 10 cm.

Fig. 13 Radar images recorded by wide-span mine detector.

The radar images in Fig. 13 show in black-and-white the amplitude of the signals reflected and recorded with the MW antenna array. The image of a mine has two opposing arcs perpendicular to the direction of the array movement reflections from the cylindrical body), with an intense reflection in the center (the raised detonator). The characteristic response for 2 and 3 allows discrimination of the mines from clutter objects 1, 4, and 5., and the estimated diameter of 20 cm to 30 cm is consistent with AT mines. Further testing of such scanning systems has shown that it tolerates well the effects of soil inhomogeneities.

A spatial filtering algorithm has been developed and tested that identifies buried mines by the characteristic shape of their response on MW images. A simple correlation filter is used with a recognition matrix $\mathbf{F}_{j,n}$, which depends on the shape and dimensions of the selected targets [45], [46].

$$\mathbf{F}_{j,n} = \left\| f_{j,n} \right\| = \begin{Vmatrix} 0 & 1 & 1 & 1 & 0 & 0 & 0 & 0 & 1 & 1 & 1 & 0 \\ 1 & 1 & 1 & 0 & 0 & 1 & 1 & 0 & 0 & 1 & 1 & 1 \\ 0 & 1 & 1 & 1 & 0 & 0 & 0 & 0 & 1 & 1 & 1 & 0 \end{Vmatrix}; \quad \begin{matrix} j = 1,2,3; \\ n = 1,2,...12. \end{matrix} \tag{14}$$

The following algorithm then provides target recognition. This describes the relation between each element of the radar image brightness matrix $\left\| m_{i,k} \right\|$ and the element of the matrix $\left\| f_{i,k} \right\|$, which is calculated as follows:

$$l_{i,k} = \Theta \left(\sum_{j=1}^{3} \sum_{n=1}^{12} f_{j,n} \cdot m_{i+j-2,k+n-5} - p \right), \tag{15}$$

where: p is the value of the detection threshold.

The function $\Theta(x)$ in equation (15) is determined as follows:

$$\Theta(x) = \begin{cases} 1; & at \ x > 0. \\ 0; & at \ x \le 0. \end{cases} \quad , \tag{16}$$

Also, it should be noted that the calculated values of the matrix $M = \|m_{i,k}\|$ may go beyond the region where it is defined. In this case, the corresponding values of the matrix are taken to be zero. The proposed algorithm made it possible to recognize both AT and AP mines in this experimental setup. Considering the relative crudeness of computers and displays, and the general novelty of using computers to evaluate image data in the late 1980s, these results were very encouraging.

Development of HSRs of the RASCAN progressed in the mid-1990s [78]. The design of these was quite simple and could be easily adapted to any desired frequency range. The prototype of a wide-span mine detector MiRascan included elements for detecting five frequencies of HSR in two orthogonal polarizations, and a metal detector (MD) [78]. The sensors were installed on a cart, which was driven by a stand-off operator using control box connected by an umbilical cord (Fig. 14a). A block diagram of the MiRascan radar with MD is presented in Fig. 14b.

Fig. 14 a) Two-sensor MiRascan mine detection system; b) block diagram of MiRascan HSR with MD.

The radar operated at five CW frequencies (cycled in sequence) in the range of 1.6 through 2.0 GHz with parallel and cross polarized receivers. and transmitted unmodulated signals at each frequency. Its signals were received in two polarizations. The emitted power was only 10 mW, providing complete safety for the operator. A 2 MHz induction loop MD was located on the 120 mm aperture of the radar, providing coincident HSR and MD images. The cyclical recording of signals at each frequency and both polarizations of HSR and from the MD was realized at a high rate while the sensor head was electromechanically swept side-to-side as the entire system advanced at a rate of 0.17 m/min along a 112 cm wide lane.

Fig. 15 Mines used in experiments; 1)TC-6.1, 2) TC-2.5, 3) TM-62M, 4) TM-62PZ, 5) PTM-3, 6) MS-3, 7) PMN-2.

Inert Soviet TM-62M and PTM-3 and Italian TC-6.1 metal-cased AT mines were used in testing MiRascan. Testing on plastic-cased AT mines used the Italian TC-2.5 and Soviet TM-62PZ. As examples of AP mines, Soviet plastic-cased PMN-2 mines were used, as well as a plastic-body MS-3 booby trap. All these mines are shown in Fig. 15.

The experiments to detect and identify inert plastic- and metal-cased mines were conducted under realistic conditions in a special military test ground near Moscow. The proving ground had sites with several characteristic soils: sand, chernozem, loam, etc. This ensured testing across wide variations in soil dielectric properties. To research the impact of moisture content on the quality of HSR images received by the different

channels, tests were conducted under differing weather conditions: both during hot/dry periods, and following rain events.

Since many mine fields are in populated areas and/or former conflict zones, human debris and shrapnel (clutter) produce false alarms that greatly outnumber actual explosive threats. To test discrimination between mines and clutter, glass and plastic bottles (empty and filled with water) were buried in the test bed. The AT mines and bottles were laid in the ground at a depth of 5 cm to 10 cm, and for the AP mines a depth of 1 cm to 5 cm.

The experimental results are shown in Fig. 16 for two polarizations of HSR and MD. Although HSR images were recorded at five discrete frequencies, only the most distinct image is shown for each polarization. The high MD contrast for the plastic-bodied MS-3 booby trap (top right image) is due to the presence of a metal retaining ring around the casing.

HSR image (cross-polarization)	HSR image (parallel-polarization)	MD image
MS-3 booby trap in chernozem		
Two PMN-2 AP mines in chernozem		
TM-62M AT mine in chernozem		
Glass and plastic bottles filled with water in sand		

Fig. 16 HSR and MD images of mines and clutter.

In the second row of Fig. 16, two PMN-2 AP mines are shown. Both appear clearly in HSR, but only the upper one shows on MD because the metal arming pin has not been pulled as it has for the lower one. The metal-cased TM-62M AT mine in the third row of Fig. 16 display a clear

round footprint in all channels, with the raised pressure plate clearly visible on HSR. The bottom row presents the images of glass (top of each image) and plastic (bottom of each image) bottles filled with water. Since the bottles have no metal, there is no MD image. It is worth noting that in the years after this test, approaches which merge or fuse two sensor outputs were adopted for other dual-sensor mine detectors such as Minehound [84], and ALIS [82].

Later experiments with higher frequency RASCAN radar provided further MW holograms of explosive devices as shown in Fig. 17 [85]. The items were buried horizontally in a sand test bed, and scanned with at a frequency of 3.8 GHz. In general, large explosive objects are buried at varying depths, as in the case, for example, the ends of the object ranged from zero to about 8 cm. In particular, the rocket's fins were almost exposed, while the cylindrical body was about 7 cm deep. The thickest part of the 8-cm shell body was on the surface, with the fins at about 4 cm and the thinnest part of the body at 7 cm or 8 cm. This information is used to understand how the various parts of the body reflect plane waves, and the figures shown show the wave nature of the HSR interference pattern. However, considering the response of the first lobe of the interference pattern, the 2D images faithfully reproduce the shape and size of the real target, even though the 3D reconstruction of the hologram from the recorded interference pattern has not been performed.

Photo	MW hologram
50 mm rocket	
80 mm shell	

Fig. 17 HSR images recorded by RASCAN-4/4000.

It has been shown that HSR images of mines are sufficiently distinct from common clutter items, that they can be discriminated using a machine learning neural network approach. In a study using a cylindrical mine simulant and four clutter objects (rock, crushed can, shell casing and segment of barbed wired), a neural network was trained to identify in any HSR image the mine with 100% detection rate, and zero false alarms [86].

HSRs of other designs intended for mine detection were described in [10], [11], [44]. The operational frequency for these radars is 2 GHz. In most conditions, this seems to be the optimal frequency for land mine detection [78], [87]. The HSR for mine detection using a spiral scanning method [10] is shown in Fig. 18. The device is attached to a rail rotating around the mounting axis as shown in Fig. 18b, and records the MW hologram in polar coordinates.

Fig. 18 HSR for mine detection [10].

The advantage of this scanning method is its relative simplicity and higher productivity in comparison with a rectangular grid, while the disadvantage is the presence of a blind zone in the center of the scan, as well as the necessity to place the central pivot within a potentially mined area. So, it is difficult to imagine how to use this technology in actual field conditions.

The simple and compact design of the RASCAN HSR suggested another approach for alleviating the burden of manual scanning using a robotic scanner (Fig. 19) with simple architecture for sweeping the radar antenna across the path of the robot as it advances incrementally [88].

Fig. 19 HSR on a robotic scanning platform [88].

Further advances cam with integration of a 1 transmitter (Tx) – 4 receiver (Rx) ISR (2 GHz) for rapid detection of buried objects and calculation of their cartesian coordinates; and a

HSR (1.97 GHz similar to that described proposed in [59], used in [78], and depicted in Fig. 7) for object imaging and classification to reduce false alarms. The system (Fig. 20) also has a 3-D video camera that records a digital elevation model (DEM) of the area scanned by the HSR [87], [89]. As shown in Fig. 20, all sensors were mounted on a commercial robotic platform (Clearpath Jackal). Note that all of the radars described above used practically the same CW frequency or impulse center frequency of 2 GHz.

This is based on field testing of the electromagnetic properties of soils near the conflict zone in eastern Ukraine [87] which was the initial focus for the development of this system. For the chernozem soils of this region, 2 GHz provides sufficient resolution to detect and discriminate land mines, while maintaining sufficient sounding depth of 5 cm to 20 cm.

Fig. 20 Robotic platform "Ugo 1st" [89]; 1)ISR antenna array, 2) ISR controller, 3) HSR, 4) 3-D camera.annerR antenna array, 2) ISR controller, 3) HSR, 4) 3-D camera.

Demining is complicated by the widespread occurrence of small, plastic-cased AP mines, which, due to their sometimes insignificant signature on both radars and MDs are easily indistinguishable from reflections from soil irregularities. Scientific experiments, as a rule, are carried out in controlled conditions with more or less homogeneous soil and a relatively flat ground surface. Fig. 21 shows conditions of real minefields. These circumstances need to be comprehended in further design of MW devices and algorithms for mine detection and discrimination.

Fig. 21 a) Riverbank minefield in the Republic of Serbska, b) minefield with clearance lane in southern Lebanon.

There are several methods for filtering out false reflections from surface relief. For ultrawide band (UWB) ISR, this can be done by gating the reflected signal by range or by other methods using the high spatial resolution of UWB radars [73], [90]. For HSR, this cannot be used since the signal is CW; either monochromatic [10], [87] or multi-frequency [31] which is insufficient to obtain the required range resolution. One of the possible ways to solve this problem for HSR is using an additional video sensor [91], [92].

In the first case [91], it was proposed to suppress uneven surface influence using a reconstruction method (modified back propagation) that incorporates a DEM collected by a video sensor. The utility of this approach was illustrated experimentally by comparing MW images reconstructed with the DEM against the same images realized using traditional back propagation methods assuming a homogeneous ground with a planar surface. Accurate positioning of HSR sensor was obtained using a webcam video and a graphic contrast augmented reality (AR) marker; this solution [93] allows the acquisition of interference pattern samples at a great number of arbitrary positions to investigate a volume. To calculate the radar position, the physical coordinates of the AR marker angles are corrected with their geometric projections on the webcam image. With the information on the 3-D coordinates of each sample, it was possible to adopt a rear projection algorithm for the reconstruction of the MW image. By introducing the concept of AR, it is possible to superimpose the visual image of the scanned area onto the MW image, eliminating the need to georeference the radar image (although this is still possible and often desirable.

This method for incorporating surface relief is important for demining, but also lends itself to other applications such as detection of objects hidden under clothing, or scanning of non-flat surfaces (arched ceilings, columns, statues, etc.). It should be noted that the high sensitivity of HSR to reflections from surface irregularities can also useful in applications where surface defects themselves are to be detected. As, for example, when detecting surface defects on metals [93], [94], [95].

3.2. Non-destructive testing of building structures and composite materials

Despite the fact that the first HSRs of RASCAN type were designed with the rather narrow goal of detecting landmines, particularly those with plastic cases, later work shows that they have a much wider field of applications. One of these areas is the examination of building structures in order to detect defects, embedded elements and other inhomogeneities [39], [96]. Building elements are an easier subject for scanning and interpretation since, in general, they have a relatively flat surfaces and more or less homogeneous and predictable composition. A trained user easily learns to recognize the internal elements of a structure from a recorded MW image, and to identify anomalous targets or conditions.

The need for detecting concealed details (such as e.g. reinforcing or voids) in different structures frequently arises during repair and renovation of old buildings. MDs are traditionally used to detect metallic details such as rebar, mesh, conduits or post-tensioning cables. However, the need to detect dielectric objects (e.g. plastic conduits or pipes, voids, etc.) is also of great interest and importance.

The most sensitive and still widely used method for inspecting structures uses X-rays. However, traditional X-rays do not use backscattered signal, and therefore require a two-sided approach with the source and receiver placed on opposite sides of the structure. In some important cases, both sides of a structure under investigation cannot be accessed; for example, in the sounding of roadways and airstrips. In addition, there are significant health concerns when storing, transporting and using X-ray sources.

The first experiments in the field of MW imaging of structures involved concrete floor inspection using the Mine-detecting MiRascan system as depicted in Fig. 22 [97]. MW images were recorded to map plastic heating tubes in a floor to prevent driven nail damage during installation of a parquet floor. More details on this use of HSR are given in the later section on cultural heritage investigations [98].

Fig. 22 a) MiRascan radar at work, b) sample of plastic tubing.

Another application for HSR after the catastrophic crash of the USA Space Shuttle Columbia in 2003 [100]. There was a need for non-destructive testing (NDT) of the dielectric foam thermal insulation on the large propellant tanks, and the adhesion of the thermal tiles to the aluminum body of the craft. These and other composite materials used in the aeronautical and aerospace sector are semi-transparent in the MW range [28] and [101]. For example, the Shuttle's external liquid hydrogen and oxygen tanks store these propellant components at –183 °C and –253 °C respectively. To prevent fuel vaporization and exterior condensation and icing, the tank is covered with insulating polyurethane foam. This layer has a thickness ranging from 25 mm to 50 mm. NASA investigators determined that damage to the left wing of the spacecraft during the launch of the 28th mission was caused by the sudden boiling (at high altitude) of condensation in or under the thermal insulation. On re-entry, the damage to the thermal protection allowed plasma to penetrate and destroy the aluminum wing. After previous Space Shuttle launches, similar damage had been found, but of much smaller magnitude, and it was considered an acceptable level of risk [102], [103], [104]. Another type of damage was associated with the coating of thermal protection tiles. During re-entry they are subjected to high thermal and mechanical stresses. A case reported in the literature [100] concerns the first flight (April 12, 1981) of the Space Shuttle Columbia where 16 thermal protection tiles were lost and 148 were damaged [100]. After the first and only flight of the Soviet Shuttle Buran (November 15, 1988) similar defects with serious side effects were found [100].

Tests of MW and millimeter wave technologies for NDT of the Space Shuttle thermal shielding were undertaken following the Columbia disaster [22], [28], [104]. Although the shuttle program was soon cancelled, the success of these tests led to development of devices specifically designed for NDT of the composite materials that are used in aerospace engineering.

Initially, RASCAN-5 with its ability to record both amplitude and phase (therefore allowing reconstruction of complex MW holograms [19], [20], [21]) was tested for NDT of composite details [66], [67], [105]. However, these experiments showed insufficient sensitivity to small and low-contrast defects due to low operating frequency and imprecise positioning during manual scanning. This prompted the creation of an automated stand system (Fig. 23) that would achieve the required sensitivity and precision [106], [107].

The experimental set-up mainly consists of a ZVA 24 vector network analyzer (VNA) with 10 MHz to 24 GHz frequency band and a 2-D electromechanical scanning bed. An antenna with T_x and R_x function is connected by two flexible stable phase feeders to the VNA. The distance between the antenna and the scanning plane of the investigated object is adjusted by means of a

tripod with adjustable height on which the antenna is fixed. This set-up also allowed us to experiment with different styles of antenna. The measurements were carried out by moving the sample with the 2D scanner bed, while the antenna remains fixed on the tripod. The movement system synchronized with the VNA allows acquisition on a programmable grid of points.

Fig. 23 Experimental high precision HSR system; 1) test sample, 2) antenna, 3) cables, 4) electromechanical scanning bed, 5) VNA (ZVA 24).

The capabilities of the MW NDT investigation system to detect defects of interest to the aerospace industry were evaluated using a thermal insulation sample with purposely created internal defects. This sample was produced by a Russian aerospace company, and its specifications (not shown to the researchers until experiments were complete) are shown in Fig. 24. (in mm). A foam disk with diameter 270 mm and thickness 40 mm is glued to a 5-mm aluminum plate. But, prior to gluing, three circles with a diameter of 50 mm and a height of 1 mm were cut from the lower surface of the foam disk. Therefore, in the sample there is no adhesion to the aluminum plate on the surfaces of the three buried circular defects ("blind defects) while the deposition of the glue on the circular surfaces of the cuts has been preserved to simulate the effect of delamination at the interface between the foam and metal. The thickness of the glue is about 200 µm. Finally, the entire 400 mm by 500 mm frame was filled with insulating foam to conceal all interior details.

Fig. 24 Mechanical drawing of composite mock insulation with three artificial defects.

When this "blind" sample arrived at the lab, scans were carried out with the HSR at three frequencies; 7 GHz, 15 GHz and 22.5 GHz. The HSR images are shown in Fig. 25 [109]. As expected from theory, the spatial resolution improves with increasing frequency (while attenuation also increases). At 7 GHz, it is not possible to detect the three intentional defects. Instead, a geometric pattern of reflections from the edges of the sample dominate the image. But, the flaws are readily detectable in the 15 GHz and 22.5 GHz MW images. Also in the higher frequencies, a weld bead in the aluminum substrate is visible. In the 22.5 GHz image, the reconstruction algorithm provides strong suppression of the edge effects, and while the intentional defects and internal structure of the sample is clear, there is also a surprise. Targets 1 and 2 on Fig. 25 are imaged by the 22.5 GHz HSR, but are not intentional anomalies. These are defects in the foam that were not intended by, nor known to, the fabricator. This experiment highlights that manufacturing procedures, even if carried out by qualified personnel and in specialized laboratories, are not free from unintentional defects that can be detected by HSR scans with sufficiently high frequency and precision.

| 7 GHz (λ≅4.3 cm) | 15 GHz (λ≅2 cm) | 22.5 GHz (λ≅1.3 cm) |

Fig. 25 HSR images of the aerospace materials test sample with intentional (and unintentional) defects.

This system was also successfully used in similar blind experiments on a sample submitted by the Vikram Sarabhai Space Center, India [109]. Other NDT applications have included detection of water intrusion in honeycomb composite products [30], [110], and examination of tube coverings [111], [112], [113] among others.

MW technology is not yet in wide use for NDT of dielectric components, but there are now blind tests that show clear advantages of HSR for the aerospace industry. Comparing HSRs with ISRs, we can affirm that the former is less expensive and more easily adaptable to specific geometries and test conditions. HSR can also be compared with traditional ultrasonic NDT techniques applied to dielectric materials such as thermal insulating foams with high porosity, thermal tiles made with sintered quartz fibers, and composite materials based on fiber glass or carbon with a honeycomb structure: all of these materials or components exhibit high attenuation for acoustic waves [27] at frequencies that would provide spatial resolution comparable to MW HSR systems, [115]. Furthermore, ultrasonic systems are efficient only when the transducers are placed in contact with the tested surface to ensure a good mechanical coupling (often requiring coupling gels). HSR NDT can be done in complete stand-off fashion.

3.3. Cultural heritage inspection and diagnostics

This section is a largely a continuation of the previous, but considers the specific requirements and precautions required for examination of important artworks, architecture, and other cultural heritage objects. This is where the advantages of all NDT methods are most manifest. Traditionally, several NDT methods have been applied to these studies, with the selection and effectiveness of a particular technology dependent upon the properties of medium under investigation. A comparison of HSR with other NDT methods for cultural heritage studies is in [115].

Fig. 26 Historical Russian Senate Building during the time of restoration.

One of the first examples of the use of HSR in an historical building was during the reconstruction of the early 19th Century Senate building in Saint-Petersburg, Russia [37]. The building was being refitted for using it by the Constitutional Court of Russian Federation (Fig. 26). The building was built by the Russian-Italian outstanding architect Carlo di Giovanni Rossi in 1829–1834 and has great value for Russian culture. An in-floor radiant heating system had been installed previously, but with no water piping plan. In addition, there are electrical and communications cables in the concrete floor. Workers wished to avoid damaging pipes and cables with driven nails during the installation of a parquet (as in the early use of MiRascan described above). In this construction, first, metal mesh with 150 mm spacing had been laid on the concrete subfloor. Then, pipes were fastened to the mesh using plastic clips. Various types of pipes had been used including cross-linked polyethylene (PEX), multi-layer (a composite of aluminum and PEX) and polybutylene (PB). The spacing between pipes was about 30 cm. The pipes were then covered by a cement screed with thickness above the pipes of about 3 cm.

There was concern that the plastic pipes would be invisible against the background of the highly MW reflective metal mesh. However, there are several effects that worked in favor. Recall that the contrast of an object on an HSR image depends on its reflectivity and the phase shift which is a function of the distance from the antenna aperture to the target. For elongate objects polarization also has strong influence on the recorded contrast. In this case, the pipes are above the mesh and quite elongate.

The survey was carried out with the aid of a RASCAN-4/2000 holographic subsurface radar with discrete CW operating frequencies in the range of 1.6 GHz to 2.0 GHz (Fig. 27a). Fig. 27b depicts a portion of the scanned floor (16.7 m^2 total area) with imaged pipes and cable marked in chalk. As expected, there was no contrast between pipes and metal mesh in the parallel polarization radar images. However, in cross-polarization images, the plastic pipes were clearly visible. A detailed radar image showing pipes draping across a cable is shown on Fig. 27c.

Fig. 27 a) HSR antenna, b) pipes and cables marked on floor, c) pipes (light) draping over cable (dark).

As the survey progressed, the operator analyzed the image and drew the results in chalk on the floor; blue for heating tubes, red for electrical cables. The composite MW image of the total scanned area is presented in Fig. 28a, and the interpreted layout in Fig. 28b.

Fig. 28 a) Composite HSR image
b) Layout of pipes and cables.

Another application was the scanning of a marble medallion in the floor of the church of San Biagio in Montepulciano, Italy (see Fig. 29) [36]. From information on the typical thicknesses of such marble medallions, a 4 GHz HSR was employed. In Fig. 29b, there is good correlation between the optical image and the HSR image. With reasonable certainty, we could conclude that the objects highlighted by the contrast patterns are dielectric and non-metallic materials. Below are the interpretations for the three contrasting patterns shown in the yellow squares in Fig. 29b. The yellow highlighting labelled 1 and 2 may at first represent either brick or wooden supports, or maybe a symmetrical change in contrast due to reflection depth from an arched opening beneath the medallion. In fact, it is possible to view the images at different frequencies, and the positions of these dark contrast bands shift systematically, confirming the arch hypothesis.

The dark feature labelled 3 matches a barely visible hairline crack in the marble. Since the dimensions of the crack are much smaller than the wavelength of the HSR signal, this response is interpreted as arising from moisture that has intruded the marble along this crack. Later laboratory experiments comparing MW images of perfectly mated cracks in marble with and without moisture confirm this effect [36].

Historical research in the church archive indicates that the medallion was placed around 1590 during the funeral ceremony of a Prelatio of the Casata Cervini family. The current burial place of the Prelatio is not registered. However, the hypothesized supports and the arched vault suggest the possibility that under the medallion there could be the remains or relics of the Prelatio.

Fig. 29 a) The church of San Biaggio, b) side-by-side optical and MW images of the medallion.

An example of non-destructive investigation with HSR concerns the Croce di San Marco which dates to the mid-fourteenth century and is attributed to Puccio di Simone [118]. It is considered one of the masterpieces and greatest examples of Florentine painting: the dimensions of the cross

are imposing reaching a height of 6.3 meters. The cross was assembled by the masters of the time by composing perpendicular axes with a retractable joint. The thickness of each poplar board is 7 cm and the entire structure, including the crossbars, reaches a thickness of about 25 cm with an estimated total weight of around 500 kg (see Fig. 30). A test of RASCAN HSR was performed on the area highlighted by the yellow box on Fig. 31. During scanning, the artwork was protected by a green cloth supporting a plexiglass sheet marked with parallel and numbered scan lines.

Fig. 30 Croce di San Marco.

In the images, metal nails securing the wooden planks are clearly visible as very dark spots. The image at a frequency of 3.7 GHz clearly shows the contrast between areas laminated with gold leaf (white areas in Fig. 31) versus those where the wood is painted (shades of grey in Fig. 31).

In the painted area, streaks consistent with the wood grain are visible, as are very dark spots that may represent knots in the wood. These features highlight the sensitivity of HSR. In addition, especially in cross polarization, there is a dark curved shape associated with blood emanating from the wound on the side of the Christ figure (see Fig. 30).

This contrast pattern was not expected as it is painted on the gold leaf that surrounds the figure. It is not plausible that a dielectric layer less than a tenth of a millimeter thick could modify the amplitude or phase of the reflected wave, so an explanation was sought by designing a dedicated experiment in the laboratory of the Opificio delle Pietre Dure in Florence. To recreate this phenomenon, a specimen was made with gold foil partially covered with a layer of red paint.

Fig. 31 HSR images of Croce di San Marco recorded at 3.7 GHz; a) parallel polarization, b) cross polarization.

As expected, the area covered by the layer of paint is indistinguishable from that on gold foil without paint. A plausible hypothesis is that the paint used for the blood contains a metal component, and therefore can be modelled as a non-perfect conductor. In this case the electric field would be cancelled only partially, thus determining a phase variation different from 180°, resulting in the image in Fig. 31. This hypothesis was confirmed by a chemical analysis carried-out previously by the Opificio delle Pietre Dure of Florence, which detected high levels of lead in the paint used to depict the blood. Somewhat surprisingly, lead was used at the time of creation of this piece to make the colour white. Here it may have been used to create the appearance of the flow of blood by making striations of red and lighter red to white.

In the USA, termites and other wood boring organisms inflict $4.5 billion worth of damage on homes and other buildings each year. While professional inspections, trained dogs, and CO_2 detectors can spot active colonies, the old damage from previous infestations is often not visible at the surface of wooden structures and may be hidden behind plaster or other floor, wall, or ceiling coverings (which in historic structures cannot be removed). HSR of the RASCAN type has been shown to be effective in detecting hidden tunnels and other damage [54]. Fig. 32 shows a wooden beam in a structure on the former estate of US President James Buchanan (1791–1868). On the left is a photo of the surface of the old beam. The center is an HSR image at

parallel polarization and 3.7 GHz signal frequency. The dark contrast highlights its joint with an adjacent beam to the right, as well as an area with no obvious surface manifestation. The photo on the right shows termite damage exposed by peeling away the surface of the wood.

| Beam in historic structure | HSR image at 3.7 GHz | Insect damage revealed |

Fig. 32 Wooden beam in historic structure with insect damage detected and revealed.

Perhaps the most exotic application of holographic radar has been for the detection and imaging of hidden dinosaur tracks [117], [118]. The study of dinosaur tracks provides important information about these prehistoric animals, in particular behavior, which is often not revealed by the fossil remains. If the sediment fills a series of footprints before they are eroded by the elements (wind, water, etc.), then the track could be fossilized and preserved for millions of years as a mold and cast that can be separated to reveal the print. Until now, dinosaur tracks have been studied when they are found during exposure by erosion or quarrying. Where they are exposed, it is reasonable to assume that other tracks may exist, but remain covered and hidden from direct observation. Following partially successful laboratory and field experiments, it was proposed to use the high precision experimental installation shown in Fig. 23. These experiments were conducted in three frequency ranges: 6.4 GHz to 7.0 GHz, 12.8 GHz to 15.2 GHz and 18.0 GHz to 21.5 GHz. A cast and modeled dinosaur trace model was created by making a plaster cast of a real dinosaur trace (var. Anamoepus [119] from Dinosaur State Park in Connecticut, USA) and reproducing the well-fitting mold from this cast as shown in Fig. 34. The half of the specimen with the impression mold has an area of 255 mm x 225 mm and a height of 27 mm. The cast sample has the same area, but 22 mm high. The footprint is located in the center of the samples and has dimensions of 11 cm in length by 7.5 cm in width.

a   b

Fig. 33 Cast (a) and mold (b) of Anamoepus dinosaur footprint.

Fig. 34 a) Cast and mold cleanly mated, b) separated by < 1 mm slip of sand.

Experiments with only the cast or mold with clean plaster surfaces conducted in all frequency bands showed clear radar images that gave better results at higher frequencies. From this experimental investigation and from the support of the simulations of digital fingerprint models, we can believe that the MW holographic radar is suitable for performing non-contact scans of areas in which the traces are even partially exposed. The ability to scan without contact is an important advantage considering the fragility of the thin layers that covers the sequences of the impressions, and the difficulty of recording and reproducing them digitally when they have very low relief. To highlight the ability to discover hidden footprints, the mold of the implant was coupled with the plaster cast to reproduce the situation in nature. This imaging (Fig. 34) was most successful when the mold and cast were separated by a very thin (less than 1 mm) slip of clay or sand (as is common for real tracks).

Fig. 35 Summed modulus of parallel and cross polarization scans at 6.7 GHz (top); summed modulus of scans 6.4 GHz, 6.5 GHz, 6.6 GHz and 6.7 GHz parallel and cross polarizations (middle); photograph of the lower side of the limestone slab aligned to correspond with the scanned area (bottom).

Other experiments that used HSR on paleontological samples include a partially exposed rostrum of an Upper Jurassic to Lower Cretaceous fossil crocodylomorph in a 21-mm thick limestone slab from the Maiolica Formation. The specimen, recovered in the Altopiano di Asiago (Vicenza Province, Italy), is presently housed in the paleontological collections of the Rovereto Civic Museum (Trento Province, Italy). The holographic radar response recorded on the surface where the fossil cannot be observed correlates well with the actual fossil shape revealed on the reverse side of the slab. This study was done using a RASCAN-4/7000 HSR radar with discrete signals at frequencies between 6.4 GHz and 6.8 GHz.

The results of these paleontological experiments are not fully developed (Fig. 35), but this is a very new field of application for HSR. Therefore, further field trials are needed to understand the relevance of the MW holographic technique for the remote detection of characteristic shapes in areas of paleontological interest. For example, the high dielectric contrast sensitivity of the proposed method has been exploited for imaging hidden invertebrate fossils that have been pyritized or otherwise replaced by secondary minerals with very different dielectric constants from the rock in which they were fossilized.

3.4. Security

Modern security systems that use active MW technology generally record the complex amplitude of reflected waves from an area under surveillance and process these signals to produce images that may reveal concealed objects. These security systems are classified into two categories. The first includes mechanical scanning systems while the second includes electronic scanning systems [50]. For both categories, during scanning and data acquisition, the electromagnetic field is the same. For the second category, it can be estimated that electronic scanning can be completed in about one tenth the time for systems with mechanical scanning [120]. The high acquisition rate in electronically scanned radar systems enables MW video streaming at frame rates of dozens per second. There are already several systems on the market and therefore much research; among these are the ProVision [121] system produced by L-3 Communications which uses mechanical scanning by means of a series of vertically distributed elements, and the Eqo [122] radar system produced by Smiths Detection which uses the electronic control of a 2-D matrix of distributed elements. Through the electronic programming of the relative delays between the transmitting elements, it is possible to define the point of focus within the investigated volume to provide a high-resolution radar image [123]. The performance of the ProVision system, as stated in the data sheet [121], is between 200 and 300 people per hour at a data acquisition time of 1.5 seconds. The performance of Eqo should not exceed that of ProVision because it is based on the cooperative self-rotation of the subject, which is difficult to obtain in less than 1.5 seconds. The performance of both systems is further limited by the fact that subjects must often remove outer clothing before scanning. System performance limitations and high cost (approximately $ 170,000) limit use outside of airports.

Fig. 36 Schematic system for inverse aperture synthesis using radar and video camera.

To increase the throughput of active radar systems while decreasing system cost, a system architecture based on the principle of inverse aperture synthesis has been proposed. This concept is different from the systems with mechanical scanning in that it uses the motion of subjects through an array of stationary transmitters to form a synthetic aperture. Systems that use such aperture synthesis are currently used in radar systems for tracking aerial or marine targets. In these systems, one of the difficulties arises from not knowing target parameters that would allow calculation of matched filter coefficients for signal processing. These difficulties can be overcome for a moving person by recording a synchronous video that captures the motion parameters of the subject as in Fig. 36 [52], [120]. These parameters will enable coherent radar processing and inverse aperture synthesis leading to a synthesized radar image, which can be calculated for every instantaneous pose of the walking person.

The proposed principle has been tested in laboratory conditions and shown to be practical. Using an experimental setup with a mannequin subject (Fig. 37a), it was shown that the proposed method can significantly reduce the dimensions of a prospective screening system and the number of channels in the antenna system and at the same time obtain detailed radar images of hidden objects.

Fig. 37 a) Mannequin with concealed weapons; b) real part of a portion of the holographic interference pattern; c) reconstructed image at distance of 45 cm.

The data obtained in an experiment with the mannequin are shown in Fig. 37 [51]. The data acquisition was done with the following parameters:

- the distance from the mannequin to the scan plane was about 45 cm
- the frequency of VNA sweeps was 18.0 GHz to 26.5 GHz
- the height and width of the scanned aperture were 100 cm and 90 cm, respectively.

In the reconstructed MW hologram (Fig. 37), the silhouette of the plastic mannequin is visible, as well as the metal belt buckle, and especially the highly reflective metal weapons. Further development of the proposed method and evaluation of its performance are underway using an electronically switched antenna array. This allows more rapid and representative data collection.

4. CONCLUSIONS

This review provides a summary of the theory, technology and applications of HSR including humanitarian demining, NDT, cultural heritage investigations, and security. While HSR is not a universally applicable method for sounding of optically opaque media, there are many (and growing) practical and important cases. With selection of appropriate probing signal frequency to balance the trade-off between scanning depth and plan-view resolution, it is possible to reconstruct MW holograms of shallow targets that allow accurate determination of the shape and dimensions, and provide images suitable for human or machine classification. The case histories summarized here indicate promising prospects for even better subsurface imaging based on combining HSR with other sensors (e.g. optical, magnetic, acoustic) and with manual spatial sampling replaced by more precise robotic and/or electromechanical scanners.

ACKNOWLEDGEMENT

This review was prepared by international team of authors from Russia, USA, Italy, Bulgaria and Turkey, and supported by a few founds including the Russian Science Foundation under project # 21-19-00043, the Russian Foundation for Basic Research under projects # 19-57-18001 and # 20-57-46004, and Bulgarian National Science Fund under administrative contract # KP-06-RUSSIA /22-28.09.2019.

References

[1] M. I. Finkelstein, "Subsurface radar," *Telecomm. Radio Eng.* Part 2, vol. 32, 1977, pp. 18-26 (English translation).

[2] D. J. Daniels, *Surface-penetrating radar*. Pub. by IEE. London, 1996.

[3] M.I. Finkelstein, V.A. Kutev, and V.P. Zolotarev, *Applications of subsurface radar in geology*, Nedra, Moscow, 1986 (in Russian).

[4] Doolittle, J.A., 1987. Using ground penetrating radar to increase the quality and efficiency of soil surveys. *Soil survey techniques*, *20*, pp.11-32.

[5] K. Iizuka, "Microwave hologram by photoengraving," in *Proceedings of the IEEE*, vol. 57, no. 5, pp. 813-814, May 1969, DOI: 10.1109/PROC.1969.7090.

[6] Iizuka, K. and Gregoris, L.G. (1970). Application of microwave holography in the study of the field from a radiating source. Appl. Phys. Lett. 17: 509–512.

[7] G. Junkin; and A. P. Anderson, "Limitations in microwave holographic synthetic aperture imaging over a lossy half-space," *Communications, Radar and Signal Processing, IEE Proceedings F*, Volume 135, Issue 4, August 1988, pp. 321 – 329. DOI: 10.1049/ip-f-1.1988.0039

[8] Sergey I. Ivashov, Vladimir V. Razevig, Igor A. Vasiliev, Andrey V. Zhuravlev, Timothy D. Bechtel, and Lorenzo Capineri, Holographic Subsurface Radar of RASCAN Type: Development and Applications, IEEE Journal of Selected Topics in Earth Observations and Remote Sensing, Volume 4, Issue 4, December 2011. pp. 763-778. DOI: 10.1109/JSTARS.2011.2161755

[9] S.I. Ivashov, V.V. Razevig, A.P. Sheyko, I.A. Vasilyev, A Review of the Remote Sensing Laboratory's Techniques for Humanitarian Demining, Proceedings of International Conference on Requirements and Technologies for the Detection, Removal and Neutralization of Landmines and UXO, EUDEM2-SCOT-2003, 15-18 September 2003, Vrije Universiteit Brussel, Brussels, Belgium, 2003, Vol. 1, pp 3-8.

[10] X. J. Song, Y. Su, C. L. Huang, M. Lu, S. P. Zhu, "Landmine Detection with Holographic Radar," *16th International Conference of Ground Penetrating Radar* (GPR 2016), Hong Kong, 13–16 June 2016, pp. 1–4. DOI: 10.1109/ICGPR.2016.7572660

[11] G. Pochanin, L. Capineri, T. Bechtel, V. Ruban, P. Falorni, F. Crawford, T. Ogurtsova, L. Bossi, "Radar Systems for Landmine Detection: Invited Paper," *2020 IEEE Ukrainian Microwave Week (UkrMW)*, Kharkiv, Ukraine, 2020, pp. 1118-1122, doi: 10.1109/UkrMW49653.2020.9252789

[12] D. Gabor, "A new microscopic principle," *Nature*, 161, 1948, pp. 777-778, DOI: 10.1038/161777a0

[13] N. P. Chubinsky, "Possibilities of holographic methods at sounding of lossy media", *Proceedings of 4th Russian conference Radio-Physics Methods in Remote Sensing*, Murom, 30 June – 3 July 2009, pp. 47-60 (in Russian).

[14] R.J. Collier, C.B Burckhardt, L.H. Lin, *Optical Holography*, Academic Press, New York and London, 1971.

[15] Wood, Robert Williams, *Physical Optics*, New York: The MacMillan Company, 1911, pp. 37–39.

[16] E.N. Leith, and J. Upatnieks, "Reconstructed wave fronts and communication theory," J. Opt. Soc. America, 52, No. 4. XIV Advertisement, 1962, Available: http://www.opticsinfobase.org/viewmedia.cfm?uri=josa-52-10-1123&seq=0 .

[17] D. L. McMakin, D .M. Sheen, J. W. Griffin, and W. M. Lechelt. "Extremely high-frequency holographic radar imaging of personnel and mail," Sensors, and Command, Control, Communications, and Intelligence (C31) Technologies for Homeland Security and Homeland Defense V, edited by Edward M. Carapezza, Proc. of SPIE Vol. 6201, 62011W, 2006. DOI: 10.1117/12.668509

[18] Andrey Zhuravlev, Vladimir Razevig, Margarita Chizh, and Sergey Ivashov, Imaging of concealed objects on moving persons by creating synthetic aperture due to their natural motion, Proceedings of the IEEE International Conference on Microwaves, Communications, Antennas and Electronic Systems (COMCAS 2017), Tel-Aviv, Israel, 13-15 November 2017, Pages: 1–4, DOI: 10.1109/COMCAS.2017.8244743

[19] V.V. Razevig, S.I. Ivashov, I.A. Vasiliev, A.V. Zhuravlev, T. Bechtel, L. Capineri, Advantages and Restrictions of Holographic Subsurface Radars. Experimental evaluation, Proceedings of the XIII International Conference on Ground Penetrating Radar, Lecce, Italy, 21-25 June 2010, pp. 657-662. DOI:10.1109/ICGPR.2010.5550241

[20] V. Razevig, S. Ivashov, M. Chizh, A. Zhuravlev and L. Capineri, "Influence of Electrical Properties of Media on Reconstruction of Microwave Holograms Recorded by Subsurface Radar," 2019 IEEE International Conference on Microwaves, Antennas, Communications and Electronic Systems (COMCAS), Tel-Aviv, Israel, 2019, pp. 1-5. DOI: 10.1109/COMCAS44984.2019.8958377

[21] V. Razevig, S. Ivashov, I. Vasiliev, A. Zhuravlev, Comparison of Different Methods for Reconstruction of Microwave Holograms Recorded by the Subsurface Radar, Proceeding of the 14th International Conference on Ground Penetrating Radar, 4-8 June 2012, Shanghai, China, pp. 335-339. DOI: 10.1109/ICGPR.2012.6254884

[22] Kolandasami A.P., Makhmanazarov R.M., Kuz`menko I.Y., Muksunov T.R., Yakubov V.P. Phase as the basis for wave vision //IOP Conf. Ser.: Mater. Sci. Eng. 2019. Vol. 516. P. 1-5. URL: https://iopscience.iop.org/article/10.1088/1757-899X/516/1/012058

[23] http://www.rslab.ru/downloads/scan.avi

[24] E. Bechtel, S. Ivashov, T. Bechtel, E. Arsenyeva, A. Zhuravlev, I. Vasiliev, V. Razevig, and A. Sheyko, "Experimental determination of the resolution of the Rascan-4/4000 holographic radar system," 12th International Conference on Ground Penetrating Radar, June 16-19, 2008, Birmingham, UK. http://www.rslab.ru/downloads/bechtel_et_al.pdf

[25] C. Liu, M. T. Al Qaseer and R. Zoughi, "Influence of Antenna Pattern on Synthetic Aperture Radar Resolution for NDE Applications," in *IEEE Transactions on Instrumentation and Measurement*, DOI: 10.1109/TIM.2020.3026122.

[26] T. Lu, C. Snapp, T.-H. Chao, A. Thakoor, T. Bechtel, S. Ivashov, I. Vasiliev, "Evaluation of holographic subsurface radar for NDE of space shuttle thermal protection tiles," *Sensors and Systems for Space Applications. Proceedings of SPIE*, Volume 6555, 2007. DOI: 10.1117/12.719911

[27] S. I. Ivashov, V. V. Razevig, A. V. Zhuravlev, T. Bechtel and M. A. Chizh, "Comparison of Different NDT Methods in Diagnostics of Rocket Cryogenic Tanks Thermal Protection Coating," 2019 IEEE International Conference on Microwaves, Antennas, Communications and Electronic Systems (COMCAS), Tel-Aviv, Israel, 2019, pp. 1-5. DOI: 10.1109/COMCAS44984.2019.89581577

[28] S. Kharkovsky and R. Zoughi, "Microwave and millimeter wave nondestructive testing and evaluation," *IEEE Instrum. Meas. Mag.,* April 2007, 10(2), pp. 26–38. DOI: 10.1109/MIM.2007.364985

[29] J. T. Case, F.L. Hepburn, R. Zoughi, Inspection of Spray on Foam Insulation (SOFI) Using Microwave and Millimeter Wave Synthetic Aperture Focusing and Holography, 2006 IEEE Instrumentation and Measurement Technology Conference Proceedings, Sorrento, Italy, 24-27 April 2006. DOI: 10.1109/IMTC.2006.328527

[30] L. Capineri, P. Falorni , T. Becthel, S. Ivashov , V. Razevig and A. Zhuravlev, Water detection in thermal insulating materials by high resolution imaging with holographic radar, Measurement Science and Technology, Special Issue, Vol. 28, No. 1, 2017, pp. 1-6. DOI:10.1088/1361-6501/28/1/014008

[31] X. Zhang, J. Liang, N. Wang, T. Chang, Q. Guo and H. Cui, "Broadband Millimeter-Wave Imaging Radar-Based 3-D Holographic Reconstruction for Nondestructive Testing," in *IEEE*

Transactions on Microwave Theory and Techniques, vol. 68, no. 3, pp. 1074-1085, March 2020, DOI: 10.1109/TMTT.2019.2948349.

[32] R. K. Amineh, M. Ravan and R. Sharma, "Nondestructive Testing of Nonmetallic Pipes Using Wideband Microwave Measurements," in *IEEE Transactions on Microwave Theory and Techniques*, vol. 68, no. 5, pp. 1763-1772, May 2020, DOI: 10.1109/TMTT.2020.2969382.

[33] Chao Liu, Al Qaseer Mohammad Tayeb, Forrest Sheng Bao, Reza Zoughi, Target depth-based adaptive scanning in microwave synthetic aperture radar imaging for NDE applications, Proceedings SPIE, Volume 11745, Passive and Active Millimeter-Wave Imaging XXIV; 1174509 (2021), https://doi.org/10.1117/12.2585930.

[34] Andreas Och , Patrick A. Hölzl, Stefan Schuster, Stefan Scheiblhofer, Dominik Zankl, Venkata Pathuri-Bhuvana, and Robert Weigel, "High-Resolution Millimeter-Wave Tomography System for Nondestructive Testing of Low-Permittivity Materials," in IEEE Transactions on Microwave Theory and Techniques, vol. 69, no. 1, pp. 1105-1113, Jan. 2021, doi: 10.1109/TMTT.2020.3030662

[35] S. I. Ivashov, V. I. Makarenkov, V. V. Razevig, V. N. Sablin, A. P. Sheyko, I. A. Vasiliev, "Concrete floor inspection with help of subsurface radar," *Eight International Conference on Ground-Penetrating Radar*, GPR'2000, May 23-26, 2000, University of Queensland, Gold Coast, Queensland, Australia, pp. 552-555. DOI: 10.1117/12.383629.

[36] L. Capineri, P. Falorni, G. Borgioli, A. Bulletti, S. Valentini, S. Ivashov, A. Zhuravlev, V. Razevig, I. Vasiliev, M. Paradiso, M. Inagaki, C. Windsor, T. Bechtel, "Application of the RASCAN holographic radar to cultural heritage inspections," Archaeological Prospection, 16, pp. 218-230, 2009. DOI: 10.1002/arp.360

[37] V. V. Razevig, S. I. Ivashov, A. P. Sheyko, I. A. Vasilyev and A. V. Zhuravlev, An example of holographic radar using at restoration works of historical building, Progress In Electromagnetics Research Letters, Vol. 1, pp. 173–179, 2008. DOI: 10.2528/PIERL07120603

[38] Sergey Ivashov, Timothy Bechtel, Vladimir Razevig, Lorenzo Capineri, and Masaharu Inagaki, A proposed radar method for non-destructive investigation of Egyptian pyramids, Insight, January 2021, Vol 63, No 1, pp. 12-19. DOI: DOI: 10.1784/insi.2021.63.1.12.

[39] Vasiliev I.A., Ivashov S.I., Makarenkov V.I., Sablin V.N., Sheyko A.P. RF Band High Resolution Sounding of Building Structures and Works. IEEE Aerospace & Electronic Systems Magazine. May 1999, Vol. 14, No. 5, pp. 25-28. DOI: 10.1109/62.765776

[40] Luca Bossi, Pierluigi Falorni, Colin Windsor, Fabiana Zandonai, Fabrizio Bizzarini, Massimo Delfino, Luca Giusberti, Timothy Bechtel, Margarita Chizh, Sergey Ivashov, Lorenzo Capineri, The imaging of subsurface crocodile remains in a limestone slab using holographic radar, GPR 2020 — 18th International Conference on Ground Penetrating Radar, Golden, Colorado USA, June 14–19, 2020, pp. 6-9. DOI: 10.1190/gpr2020-003.1

[41] S. Ivashov, V. Razevig, A. Zhuravlev, M. Chizh, T. Bechtel, L. Capineri, M. Inagaki, MW Holographic Imaging System for Detection of Hidden Dinosaur Tracks, The 38th PIERS in St. Petersburg, Russia, 22–25 May, 2017, Pages: 3241-3246, DOI: 10.1109/PIERS.2017.8262316

[42] Vohra, D., Bechtel, T., Thomas, R.D.K., Windsor, C., Ivashov, S., Capineri, L., Inagaki, M. and Van Scyoc, R., 2015, July. A test of holographic radar for detection of hidden vertebrate tracks and trackways. In 2015 8th International Workshop on Advanced Ground Penetrating Radar (IWAGPR) (pp. 1-4). IEEE

[43] T. Bechtel, L. Capineri, C. Windsor, M. Inagaki, S. Ivashov, Comparison of ROC curves for landmine detection by holographic radar with ROC data from other methods, 2015 8th International Workshop on Advanced Ground Penetrating Radar (IWAGPR), 2015, p. 1-4, DOI: 10.1109/IWAGPR.2015.7292645

[44] G. Borgioli, L. Bossi, L. Capineri, P. Falorni, T. Bechtel, F. Crawford, M. Inagaki, G. Pochanin, V. Ruban, L. Varyanitza-Roschupkina, and T. Ogurtsova, "A Hologram

Reconstruction Algorithm for Landmine Recognition and Classification Based on Microwave Holographic Radar Data," *2018 Progress in Electromagnetics Research Symposium (PIERS-Toyama)*, Toyama, 2018, pp. 1938-1944, doi: 10.23919/PIERS.2018.8597707.

[45] S.I. Ivashov, V.N. Sablin and I.A. Vasilyev, "Wide-span systems of mine detection," in *IEEE Aerospace and Electronic Systems Magazine*, vol. 14, no. 5, pp. 6-8, May 1999, DOI: 10.1109/62.765772.

[46] S. I. Ivashov, V. N. Sablin, I. A. Vasilyev, N. V. Nikiforov and V. E. Minkov, "Wide-span systems of mine detection," 1998 Second International Conference on the Detection of Abandoned Land Mines (IEE Conf. Publ. No. 458), Edinburgh, UK, 1998, pp. 78-80, DOI: 10.1049/cp:19980693.

[47] A. Zhuravlev, A. Bugaev, S. Ivashov, V. Razevig and I. Vasiliev, "Microwave holography in detection of hidden objects under the surface and beneath clothes," 2011 XXXth URSI General Assembly and Scientific Symposium, Istanbul, 2011, pp. 1-4, DOI: 10.1109/URSIGASS.2011.6050429

[48] A. Zhuravlev, V. Razevig, M. Chizh, and S. Ivashov, Imaging of concealed objects on moving persons by creating synthetic aperture due to their natural motion, Proceedings of the IEEE International Conference on Microwaves, Communications, Antennas and Electronic Systems (COMCAS 2017), Tel-Aviv, Israel, 13-15 November 2017, pp. 1–4, DOI: 10.1109/COMCAS.2017.8244743

[49] Meng, Y.; Lin, C.; Zang, J.; Qing, A.; Nikolova, N.K. Ka Band Holographic Imaging System Based on Linear Frequency Modulation Radar. *Sensors* 2020, *20*, 6527. DOI: 10.3390/s20226527

[50] Sheen D.M., McMakin D.L., Hall T.E., Three-dimensional millimeter-wave imaging for concealed weapon detection, IEEE Trans. Microwave Theory Tech., vol. 49, no. 9, pp. 1581–1592, Sep. 2001. DOI: 10.1109/22.942570

[51] Zhuravlev, A., Razevig, V., Chizh, M., Dong, G., Hu, B. (2020). A New Method for Obtaining Radar Images of Concealed Objects in Microwave Personnel Screening Systems. IEEE Transactions on Microwave Theory and Techniques, *1–1*. DOI:10.1109/tmtt.2020.3023443

[52] David M. Sheen, R. Trevor Clark, J. Tedeschi, A. Mark Jones, Thomas E. Hall, "High-resolution 3D microwave imaging of a moving target using optical motion capture," Proc. SPIE 10994, Passive and Active Millimeter-Wave Imaging XXII, 109940D (13 May 2019); doi: 10.1117/12.2519892

[53] J. Gao, Y. Qin, B. Deng, H. Wang and X. Li, "A Novel Method for 3-D Millimeter-Wave Holographic Reconstruction Based on Frequency Interferometry Techniques," in IEEE Transactions on Microwave Theory and Techniques, vol. 66, no. 3, pp. 1579-1596, March 2018, doi: 10.1109/TMTT.2017.2772862.

[54] Bechtel, T., Capineri, L., Falorni, P., Inagaki, M., Zhuravlev, A., Razevig, V., Ivashov, S. and Windsor, C., 2011, March. Detection of Latent Damage from Insect Activity in Wooden Structures through the Use of Holographic Subsurface Radar. In PIERS Proceedings, Marrakesh, Morocco, March 2011, p. 95.

[55] L. N. Anishchenko, I. L. Alborova, M. A. Chizh and A. V. Zhuravlev, "Microwave imaging of biological tissue phantom in different frequency ranges," *2016 Progress in Electromagnetic Research Symposium (PIERS)*, Shanghai, 2016, pp. 4639-4643, doi: 10.1109/PIERS.2016.7735712

[56] C. Huang, T. Liu, M. Lu and Y. Su, "Holographic subsurface imaging for medical detection," *Proceedings of the 15th International Conference on Ground Penetrating Radar*, Brussels, 2014, pp. 651-654, DOI: 10.1109/ICGPR.2014.6970506.

[57] D. Flores-Tapia, O. Maizlish, C. M. Alabaster and S. Pistorius, "A holographic reconstruction method for circular multistatic subsurface radar," *2012 International*

Waveform Diversity & Design Conference (WDD), Kauai, HI, 2012, pp. 142-145, DOI: 10.1109/WDD.2012.7311268.

[58] H. Wu, M. Ravan and R. K. Amineh, "Holographic Near-Field Microwave Imaging With Antenna Arrays in a Cylindrical Setup," in *IEEE Transactions on Microwave Theory and Techniques*, DOI: 10.1109/TMTT.2020.3031897.

[59] I.A. Vasiliev, A.I. Ivashov, S.I. Ivashov, V.I. Makarenkov, V.N. Sablin, A.P. Sheiko, Subsurface radar, Russian patent # 2158015, 20.10.2000, RU 2 158 015 C2. Reference in WoS:
http://apps.webofknowledge.com/full_record.do?colName=DIIDW&recordID=2001101210
&log_event=no&search_mode=GeneralSearch&qid=2&log_event=yes&product=UA&SID=
C6FUAJCOAHXc12dYwqC&viewType=fullRecord&doc=3&page=1

[60] Luca Bossi, Pierluigi Falorni, Alessandro Bartolini, Lorenzo Capineri, Characterization of a 2 GHz holographic radar antenna for detection of subsurface targets, 18th International Conference on Ground Penetrating Radar, Golden, Colorado, 14–19 June 2020, pp. 324-327. DOI: 10.1190/gpr2020-085.1

[61] S.I. Ivashov, L. Capineri, and T.D. Bechtel, Holographic Subsurface Radar Technology and Applications, in book UWB Radar. Applications and Design, edited by James J. Taylor, CRC Press, Taylor & Francis Group, 2012, pp. 421-444. ISBN 978-1-4200-8986-8.

[62] http://www.rslab.ru/downloads/ptm3.avi

[63] V.V. Razevig, I.A. Vasil'ev, A.I. Ivashov, S.I. Ivashov, V.I. Makarenkov, Method of Obtaining Radio Holograms of Subsurface Objects, Russian patent #2482518, 01.11.2011.
http://apps.webofknowledge.com/full_record.do?colName=DIIDW&recordID=2013H61403
&log_event=no&search_mode=GeneralSearch&qid=9&log_event=yes&product=UA&SID=
F1YM3JgCMcXP2VTvp7o&viewType=fullRecord&doc=2&page=1

[64] http://www.rslab.ru/english/product

[65] Andrey Zhuravlev, Sergey Ivashov, Igor Vasiliev, Vladimir Razevig, Processing of Holographic Subsurface Radar Data, Proceeding of the 14th International Conference on Ground Penetrating Radar. 4-8 June 2012, Shanghai, China, pp. 68-71. DOI:10.1109/icgpr.2012.6254833

[66] S. Ivashov, V. Razevig, I. Vasiliev, T. Bechtel, L. Capineri, Holographic subsurface radar for diagnostics of cryogenic fuel tank thermal insulation of space vehicles, NDT & E International, Vol. 69, January 2015, Pages 48-54, DOI: 10.1016/j.ndteint.2014.10.002

[67] A. V. Zhuravlev, S. I. Ivashov, V. V. Razevig, I. A. Vasiliev and A. S. Bugaev, "Holographic subsurface radar RASCAN-5," 2013 7th International Workshop on Advanced Ground Penetrating Radar, Nantes, 2013, pp. 1-6. DOI: 10.1109/IWAGPR.2013.6601548

[68] J.V. Goodman, Introduction to Fourier Optics. New York: McGraw-Hill, 2005.

[69] Tikhonov A. N. Solutions of Ill-Posed Problems, New York, Winston, 1977.

[70] A. V. Popov, V. V. Kopeikyn, V. A. Vinogradov and S. A. Zapunidi, "Reconstruction algorithms and experiments with a prototype of holographic subsurface radar," *4th International Conference on Antenna Theory and Techniques (Cat. No.03EX699)*, Sevastopol, Ukraine, 2003, pp. 561-563 vol.2, doi: 10.1109/ICATT.2003.1238803.

[71] A. Popov, I. Prokopovich and D. Edemskii, "Experimental implementation of microwave subsurface holography," *2016 Days on Diffraction (DD)*, St. Petersburg, 2016, pp. 340-345, DOI: 10.1109/DD.2016.7756870

[72] Y. Zhang, Z. Xiao, L. Wu, X. Lu and Y. Wang, "Deep learning for subsurface penetrating super-resolution imaging," *2017 10th UK-Europe-China Workshop on Millimetre Waves and Terahertz Technologies (UCMMT)*, Liverpool, 2017, pp. 1-4, DOI: 10.1109/UCMMT.2017.8068492.

[73] D. Sukhanov and K. Zavyalova, "Three-dimensional non-contact subsurface radiotomography through a non-planar interface between media," *Proceedings of the 15th*

International Conference on Ground Penetrating Radar, Brussels, 2014, pp. 663-667, DOI: 10.1109/ICGPR.2014.6970509

[74] V.V. Razevig, A.V. Zhuravlev, A.S. Bugaev, M.A. Chizh and S.I. Ivashov, "Imaging under irregular surface using microwave holography," 2017 Progress in Electromagnetics Research Symposium - Fall (PIERS - FALL), Singapore, 2017, pp. 172-177. DOI: 10.1109/PIERS-FALL.2017.8293132

[75] Qin, T., Bossi, L., Bartolini, A., Falorni, P., Giannelli, P., Zhao, Y., & Capineri, L. (2018). Influence Analysis of Uneven Surface on Landmine Detection Using Holographic Radar. 2018 Progress in Electromagnetics Research Symposium (PIERS-Toyama). doi:10.23919/piers.2018.8597927

[76] https://www.geophysical.com/about-gssi

[77] https://www.guidelinegeo.com/

[78] Ivashov S.I., Makarenkov V.I., Razevig V.V., Sablin V.N., Sheyko A.P., Vasiliev I.A. Remote Control Mine Detection System with GPR and Metal Detector. Eight International Conference on Ground-Penetrating Radar, GPR'2000, May 23-26, 2000, University of Queensland, Gold Coast, Queensland, Australia, pp. 36-39. DOI: 10.1117/12.383598

[79] Reza K. Amineh, Natalia K. Nikolova, Maryam Ravan, Real Time Three Dimensional Imaging of Dielectric Bodies Using Microwave/Millimeter Wave Holography, Publisher: IEEE Press Series on RF and Microwave Technology, IEEE press, Wiley, June 2019, ISBN: 978-1-119-53886-8. DOI: 10.1002/9781119538875

[80] Landmine Monitor 2020, 12 Nov 2020, the-monitor.org/en-gb/reports/2020/landmine-monitor-2020.aspx

[81] V.P. Joynt, "Mobile metal detection: a field perspective," Proceedings of the Second International Conference on the Detection of Abandoned Land Mines, MD'98. Edinburgh, UK, 12-16 October 1998, pp. 14,15.

[82] M. Sato, "Dual Sensor ALIS for Humanitarian Demining and its Evaluation Test in Mine Fields in Croatia," IGARSS 2008 - 2008 IEEE International Geoscience and Remote Sensing Symposium, Boston, MA, 2008, pp. II-181-II-184, DOI: 10.1109/IGARSS.2008.4778957.

[83] Jane's Mines and Mine Clearance Edition by Colin King, December 1, 1996.

[84] David Daniels; Jurgen Braunstein; and Michael Nevard, (2014) "Using MINEHOUND in Cambodia and Afghanistan," The Journal of ERW and Mine Action: Vol. 18: Issue 2, Article 14.

[85] S. Ivashov, V. Razevig, I. Vasilyev, A. Zhuravlev, T. Bechtel, L. Capineri, The Holographic Principle in Subsurface Radar Technology, International Symposium to Commemorate the 60th Anniversary of the Invention of Holography, Springfield, Massachusetts USA, October 27-29, 2008, pp. 183-197.

[86] Windsor, C., Capineri, L., & Bechtel, T. D. (2012). Buried object classification using holographic radar. Insight-Non-Destructive Testing and Condition Monitoring, 54(6), 331-339.

[87] T. Bechtel, G. Pochanin, S. Truskavetsky, M. Dimitri, V. Ruban, O. Orlenko, T. Byndych, A. Sherstyuk, K. Viatkin, F. Crawford, P. Falorni, A. Bulletti, L. Capineri, "Terrain Analysis in Eastern Ukraine and the Design of a Robotic Platform Carrying GPR Sensors for Landmine Detection," 2018 17th International Conference on Ground Penetrating Radar (GPR), Rapperswil, 2018, pp. 1-4, doi: 10.1109/ICGPR.2018.8441556.

[88] Capineri, L., Arezzini, I., Calzolai, M., Windsor, C., Inagaki, M., Bechtel, T., & Ivashov, S. (2013). High resolution imaging with a holographic radar mounted on a robotic scanner. Session 4A5 SC5: High Resolution Imaging with Penetrating Radar Scanners for Detection of Small or Low Contrast Objects, 1378.

[89] L Bossi, P Falorni, G Pochanin, V Ruban, T Ogurtsova, F Crawford, T. Bechtel, L. Capineri, Detection of targets from radar tracks of the UWB-GPR" 1Tx+ 4Rx" on the mobile platform" 18th International Conference on Ground Penetrating Radar, June 14-19, 2020, 448-451. DOI: 10.1190/gpr2020-116.1

[90] Jonard, F., Weihermüller, L., Vereecken, H., & Lambot, S. (2012). *Accounting for soil surface roughness in the inversion of ultrawideband off-ground GPR signal for soil moisture retrieval. GEOPHYSICS, 77(1), H1–H7.* doi:10.1190/geo2011-0054.1

[91] V. V. Razevig, A. V. Zhuravlev, A. S. Bugaev, M. A. Chizh and S. I. Ivashov, "Imaging under irregular surface using microwave holography," 2017 Progress in Electromagnetics Research Symposium - Fall (PIERS - FALL), Singapore, 2017, pp. 172-177. DOI: 10.1109/PIERS-FALL.2017.8293132

[92] Vladimir Razevig, Andrey Zhuravlev, Margarita Chizh, Sergey Ivashov, Alexander Bugaev, Hand-held Radar with Video Positioning System for Microwave Imaging, The 38th PIERS in St Petersburg, Russia, 22–25 May, 2017, Pages: 3052-3055, DOI: 10.1109/PIERS.2017.8262279

[93] A. Zhuravlev, V. Razevig, S. Ivashov, A. Skrebkov, V. Alekseev, On the Use of Microwave Holography to Detect Surface Defects of Rails and Measure the Rail Profile, Sensors 2019, 19, 1376, pp. 1–11. DOI: 10.3390/s19061376

[94] R. Zoughi *et al*., "Real-time and on-line near-field microwave inspection of surface defects in rolled steel," *Proceedings of 1997 Asia-Pacific Microwave Conference*, Hong Kong, 1997, pp. 1081-1084 vol.3, doi: 10.1109/APMC.1997.656406

[95] Y. Gao *et al*., "Millimeter Wave Differential Probe System for Surface Crack Detection in Painted Aircraft Fuselage," *2019 IEEE International Instrumentation and Measurement Technology Conference (I2MTC)*, Auckland, New Zealand, 2019, pp. 1-6, doi: 10.1109/I2MTC.2019.8826970

[96] M.T. Ghasr, Y. LePape, D.B. Scott, and R. Zoughi, "Holographical Microwave Imaging of Corroded Steel Bars in Concrete," American Concrete Institute (ACI) Materials Journal, vol. 112, no. 1, pp. 115-124, January 2015. doi:10.14359/51686981.

[97] Ivashov S.I., Makarenkov V.I., Razevig V.V., Sablin V.N., Sheyko A.P., Vasiliev I.A. Concrete Floor Inspection with Help of Subsurface Radar. Eight International Conference on Ground-Penetrating Radar, GPR'2000, May 23-26, 2000, University of Queensland, Gold Coast, Queensland, Australia, pp. 552-555. DOI: 10.1117/12.383629

[98] S. Ivashov, V. Razevig, A. Sheyko, I. Vasilyev, T. Bechtel, Holographic Radar as a Tool for Non-Destructive Evaluation of Structural Materials, Proceedings of the 2005 SEM Annual Conference & Exposition on Experimental and Applied Mechanics, Portland, Oregon, USA, Tuesday, June 7 - Thursday, June 9, 2005.

[99] Columbia Accident Investigation Board Report (2003), NASA, August.

[100] Gofin MYa. Heat resisting and thermal protecting systems of reusable space ships. Moscow: Mir; 2003. p. 672 (in Russian).

[101] Aviation Week & Space Technology. April 7, 2003, p. 31.

[102] Aviation Week & Space Technology. February 17, 2003, p. 27, 28.

[103] Aviation Week & Space Technology. October 4, 2004, p. 58.

[104] Ivashov S.I., Vasiliev I.A., Bechtel T.D., Snapp C., Comparison between impulse and holographic subsurface radar for NDT of space vehicle structural materials, Progress in electromagnetics research symposium. 2007, Beijing, China, March 26–30, 2007, p. 1816–1819.

[105] Sergey I. Ivashov, Vladimir V. Razevig, Timothy D. Bechtel, Igor A. Vasiliev, Lorenzo Capineri, and Andrey V. Zhuravlev, Microwave Holography for NDT of Dielectric Structures, Proceedings of the IEEE International Conference on Microwaves, Communications, Antennas and Electronic Systems (COMCAS 2015), Tel-Aviv, Israel, 2-4 November 2015, 978-1-4799-7473-3/15/$31.00 ©2015 IEEE, DOI: 10.1109/COMCAS.2015.7360372

[106] Ivashov, S., Zhuravlev, A., Chizh, M., & Razevig, V. (2016). *High resolution MW holographic system for NDT of dielectric materials and details. 2016 16th International Conference on Ground Penetrating Radar (GPR).* DOI:10.1109/icgpr.2016.7572595

[107] Margarita A. Chizh, Andrey V. Zhuravlev, Vladimir V. Razevig, and Sergey I. Ivashov, Experimental Validation of Sparse Sensing Technique in Subsurface Microwave Holography, PIERS in Shanghai, 8 — 11 August, 2016, pp. 1734-1738. DOI: 10.1109/PIERS.2016.7734775

[108] Sergey Ivashov, Andrey Zhuravlev, Vladimir Razevig, Margarita Chizh, Timothy Bechtel, Lorenzo Capineri, Binu Thomas, "Frequency Influence in Microwave Subsurface Holography for Composite Materials Testing," Proceedings of the 17th International Conference on Ground Penetrating Radar, GPR 2018, Rapperswil, Switzerland, June 18–21, 2018, pp. 98-103. DOI: 10.1109/ICGPR.2018.8441592

[109] Ivashov, S. I., Bugaev, A. S., Zhuravlev, A. V., Razevig, V. V., Chizh, M. A., & Ivashov, A. I. (2018). *Holographic Subsurface Radar Technique for Nondestructive Testing of Dielectric Structures. Technical Physics, 63(2), 260–267.* doi:10.1134/s1063784218020184

[110] M. Chizh, A. Zhuravlev, V. Razevig and S. Ivashov, "Detection of Water Inclusions in Honeycomb Composite Products by a Holographic Radar," 2019 IEEE International Conference on Microwaves, Antennas, Communications and Electronic Systems (COMCAS), Tel-Aviv, Israel, 2019, pp. 1-5. DOI: 10.1109/COMCAS44984.2019.8958114

[111] Reza K. Amineh, Maryam Ravan, and Raveena Sharma, Nondestructive Testing of Nonmetallic Pipes Using Wideband Microwave Measurements, IEEE Transactions on Microwave Theory and Techniques, accepted for publishing, DOI: sci-hub.do/10.1109/tmtt.2020.2969382

[112] A. Mazzinghi, A. Freni, L. Capineri, A microwave non-destructive testing method for controlling polymeric coating of metal layers in industrial products, NDT and E International, Vol. 102, March 2019, pp. 207–217 DOI: 10.1016/j.ndteint.2018.12.003

[113] Ur Rahman, M. S., Haryono, A., & Abou-Khousa, M. A. (2020). *Microwave Non-destructive Evaluation of Glass Reinforced Epoxy and High Density Polyethylene Pipes. Journal of Nondestructive Evaluation, 39(1).* doi:10.1007/s10921-020-00669-2

[114] M. A. Abou-Khousa, A. Ryley, S. Kharkovsky, R. Zoughi, D. Daniels, N. Kreitinger, and G. Steffes, Comparison of X-Ray, Millimeter Wave, Shearography and Through-Transmission Ultrasonic Methods for Inspection of Honeycomb Composites, AIP Conference Proceedings 894, 999 (2007); DOI: 10.1063/1.2718076

[115] L. Capineri, P. Falorni, S. Ivashov, A. Zhuravlev, I. Vasiliev, V. Razevig, T. Bechtel and G. Stankiewicz, Combined holographic subsurface radar and infrared thermography for diagnosis of the conditions of historical structures and artworks, Near Surface Geophysics, 2010, 8, pp. 355-364. DOI: 10.3997/1873-0604.2010005

[116] S. Ivashov, L. Capineri, T. Bechtel, V. Razevig, A. Zhuravlev, and P. Falorni, Use of holographic subsurface radar analysis in the preservation and restoration of cultural heritage objects, Surface Topography: Metrology and Properties, 2019, v. 7, No. 4, 045017, pp. 1-11. DOI: 10.1088/2051-672X/ab4fa2

[117] L. Capineri, F. Zandonai, M. Inagaki, V. Razevig, S. Ivashov, C. Windsor, and T. Bechtel, RASCAN holographic radar for detecting and characterizing dinosaur tracks, Proceedings of the 2013 7th International Workshop on Advanced Ground-Penetrating Radar, July 02-05, 2013, Nantes, France, pp. 71-76. DOI: 10.1109/IWAGPR.2013.6601553

[118] Inagaki, M., Bechtel, T., Capineri, L., Ivashov, S., Windsor, C., A small difference of permittivity observed in a holographic radar image of dinosaur footprints, Conference: Society of Exploration Geophysics Japan, Tokyo, Lapan, Volume: 128th Conference, Spring 2013, June 2013, pp. 117-120, in Japanes. https://jglobal.jst.go.jp/detail?JGLOBAL_ID=201302261927363642

[119] Galton, P. M. and J. O. Farlow, "Dinosaur State Park, Connecticut, USA: History, footprints, trackways exhibits," *Zubia*, Nr. 21, 129–174, 2003.

[120] Andrey Zhuravlev, Sergey Ivashov, Vladimir Razevig, Igor Vasiliev, Inverse synthetic aperture radar imaging for concealed object detection on a naturally walking person, Proc. of SPIE Symposium on Defense and Security, Radar Sensor Technology XVIII Conference.

Baltimore, Maryland, USA, May 5–7, 2014, Vol. 9074, pp. 907402-1…11. DOI: 10.1117/12.2051615

[121] "ProVision® Imaging," 26 March 2014, https://www.leidos.com/sites/g/files/zoouby166/files/2020-07/FS-Leidos-Provision2.pdf

[122] "eqo," 3 June 2013, http://www.smithsdetection.com/index.php/en/products-solutions/people-screening-systems/60-people-screening-systems/eqo.html, (15 January 2015).

[123] Ahmed, S. S. *Personnel screening with advanced multistatic imaging technology. Passive and Active Millimeter-Wave Imaging XVI,* Proc. of SPIE 8715, 2013. DOI:10.1117/12.2018054