

## Article

# Specification and Classification of Pelletised Dried Sewage Sludge: Identifying its Key Properties as a Renewable Material for Enabling Environmentally Non-harmful Energy Utilisation

Vesna Mislej<sup>1\*</sup> and Barbara Novosel<sup>2</sup>

<sup>1</sup> JP Vodovod Kanalizacija Snaga d.o.o., Vodovodna c. 90, Ljubljana, 1000-SI

<sup>2</sup> Faculty of Chemistry and Chemical Technology University of Ljubljana, Slovenia

\* Correspondence author: vesna.mislej@vokasnaga.si

**Abstract:** Renewable active sludge is a smart material for wastewater treatment and the protection of surface water bodies. The generated pellets (dried and pelletised dehydrated anaerobically stabilised excess sludge) are produced in a quantity of  $31.4 \text{ g} \pm 5.6 \text{ g}$  dry matter (DM) per one Population equivalent calculated to COD (PE<sub>COD</sub>) in one day. They are the appropriate tools for reaching sustainable development goals (SDGs) in renewable energy production. The specification and classification of pellets as non-hazardous alternative solid recovered fuel (SRF) create a bridge between »treated sewage sludge as the tool to remove pollutants and nutrients from wastewater« and »preparation of the valuable material as an SRF that meets customer-specific requirements«. In the last eleven years, pellets' net calorific value (NCV) is  $13.0 \pm 0.7 \text{ MJ kg}^{-1}$  as received (ar). In 2021, the 80<sup>th</sup> percentile of the Hg/NCV ratio was  $0.079 \text{ mg Hg MJ}^{-1}$ . The halogen contents of the pellets do not threaten corrosion to the incineration facility. Stable pellets' energy potential, perspective ash composition for critical raw materials recovery, and reduction of the annual amount of Hg transferred to stakeholders by 64.3 % m/m - from 10.1 kg in 2010 to 3.67 kg in 2021 - qualify pellets as a specific waste stream and a renewable material for SRF production.

**Keywords:** alternative solid recovered fuel; classification; pelletised sewage sludge; pollution prevention; renewable material; sustainable energy production

## Highlights

Water is an essential societal need of great value in the EU economy.

Municipal wastewater treatment and environmentally friendly use of treated sludge (pellets) are the appropriate tools for reaching the SDGs.

Higher pellets amounts are a bonus to the environment and the circular economy (CE).

Pellets are a renewable material for energy recovery and some raw materials.

Pellets' characterisation over eleven years allows adaptation to seasonal conditions, reveals the stability of their properties, and creates the bridge between wastewater treatment and save energy recovery – which represents sewage sludge's footprint as a smart material for SRF production.

Data on the content of transferred pollutants to final stakeholders are essential for controlling their mass flow to prevent circulation in the environment.

## 1. Introduction

Achieving the Sustainable development goals (SDGs) [1] of Clean water and sanitation, Affordable and clean energy, Responsible consumption and production with the urban wastewater treatment plants (UWWTPs), and their by-product sewage sludge will be possible only with efficient facility operations. The Fitness Check of EU – Water Regulation [2, 3] as a comprehensive policy evaluation of the Water Frame Directive (WFD) [4]


and its components the Environmental Quality Standards Directive (EQSD) [5], the Groundwater Directive (GWD) [6], and the Flood Directive [FD] [7] assesses whether the Directives are fit for performing the five criteria set out in the Commission's Better Regulation agenda [8]: i) effectiveness, ii) efficiency, iii) coherence, iv) relevance and v) EU added value. Evaluation's key findings are i) the Directives are broadly fit for purpose, ii) water is an essential societal need of great value in the EU economy, and the Directives contribute to achieving a range of SDGs [1]. In addition, the conclusions are as follows: i) on the one hand, the WFD [4] has been successful in setting up a governance framework for integrated water management for the more than 110,000 water bodies in the EU [9], slowing down the deterioration of water status and reducing chemical pollution, ii) on the other hand, the Directive's implementation has been significantly delayed, and less than half of the EU's water bodies are in good status, even though the deadline for achieving this was 2015, and finally iii) good status of water bodies also critically depends on the full implementation of other pieces of EU legislation, such as the Nitrate Directive (ND) [10] and the Urban wastewater treatment Directive (UWWTD) [11], as well as better integration of water objectives in other policy areas such as agriculture, energy or transport, which has not happened yet at the scale necessary. Chemicals are an important key area where there is room to improve and achieve better results on good water status [2]. The Wilkinson et al. [12] study concerning pharmaceutical pollution of the world's rivers presents the findings of a global survey of pharmaceutical pollution in waterways. The study monitored 1,052 sampling sites along 258 rivers in 104 countries on all continents, thus representing the pharmaceutical fingerprint of 471.4 million people. It shows that the presence of these contaminants in surface waters poses a threat to environmental and human health in more than a quarter of the studied locations. The study also included the Ljubljanica river, with measurements upstream and downstream of the Central wastewater treatment plant Ljubljana (CWWTPL) [13]. Regarding the level of cumulative active ingredients, the Ljubljanica river has 124<sup>th</sup> place out of 137 rivers that were quantified in the study. This means that the sewer system of Ljubljana, along with the CWWTPL, greatly contributes to the good status of the Ljubljanica river, a clean environment, and good public health. The CWWTPL generates the pellets, which are the subject of the present study.

Additional requirements to protect receiving waters may positively or negatively affect the UWWTP's capacity to recycle sludge. Any cost-benefit analyses conducted to increase provisions for water treatment should also consider the impact on the quality of sludge, so the decision is taken with a global picture of the consequences [14]. Sewage sludge does not automatically fit into existing definitions of waste. It may be re-used and not discarded [14]. The total amount of sludge produced in Europe in 2018 was 8.67 million tonnes of dry matter [15]. The data show a slight trend towards reducing landfills, land reclamation, and agricultural uses. In contrast, incineration and, in particular, other uses of sewage sludge like phosphorus recovery increased [15].

The energy-intensive industries are looking for alternative solid fuels to reduce primary fuel consumption and enforce the sustainable utilisation of treated, non-hazardous renewable combustible waste [16, 17, 18]. In 2018 revised EU Renewable Energy Directive (RED) [19, Part A of Annex IX] made a significant shift in the evaluation of sewage sludge by placing it among advanced biofuels as a renewable energy source for the production of fuels for transport (biogas utilisation) and electricity production to accelerate the take-up of renewables in the EU. Further, to achieve the EU's objective of climate neutrality by 2050 [20], in May 2022, the proposed new revision of RED [21] and the REPowerEU Plan[22] suggest increasing the target amount of renewable energy – currently set at 32 % by 2030 – to 45 %. Advanced biofuels/SRFs must be adequately prepared to achieve this goal [19, 21].

The treated and properly mixed combustible waste must have reliable quality and be utilised successfully regarding economic and environmental aspects. The Technical Report [16] gives background information on critical properties used for establishing a classification system for the SRF and a proposal for the quality classes of SRF. Specifications

in that document concern key information about potential risks for different combustion technologies and plants. The SRF is used only by combustion facilities complying with the emission limit values set by the EU Industry Emission Directive (IED) [23]. Following the IED and required BAT's reference documents [24, 25], the SRF must also fulfil the technical request of the installations. The proposed classification system, the classes, and the specifications should help the authorities in i) writing the permits, ii) be a help for the final user to understand better what has to be taken into account when dealing with an SRF, and iii) should increase the positive perception of the public on the use of SRF by saving of natural resources. Currently, the main stakeholders of SRFs [15, 16] are cement kilns [26], pulverised coal-fired power plants, fluidised bed combustion plants, and cogeneration plants. The primary sources of SRFs are municipal solid waste, sewage sludge, and commercial and industrial process-related waste [16]. In order to increase the energy efficiency of the incineration plant, the best available technique (BAT) [27] is used, and drying sewage sludge is an appropriate technique to increase energy efficiency if alternative energy is used for the drying process [28, BAT 20]. Regarding the energy efficiency levels associated with the best available techniques (BAT-AEELs) for sewage sludge incineration, the boiler's energy efficiency is 60 – 70 % [28]. Own biogas produced at the site of sewage sludge origin could be the source of low-grade heat for treated sludge drying. Suppose waste collect from different sources of input material for the production of SRF. In this case, the treated sewage sludge must not be dried. The operator of the incineration facility determines the ratio of input material. The Technical Standard [18] states the different origins code by specifying a source of waste. Figure 1 illustrates the waste hierarchy, waste-to-energy (WtE) processes according to the role of WtE in the CE [29], and the mission of an urban wastewater treatment plant, where SRF is produced [30].



**Figure 1.** a) The waste hierarchy and the role of WtE in the CE [29]. b) The mission of an urban wastewater treatment plant, where SRF is produced [30].

Energy recovery of waste with a high energy efficiency factor (waste recovery operation, R 1) has an advantage over waste incineration, where the purpose is only to reduce its amount. The energy efficiency factor must be  $\geq 0,60$  for installations in operation before 1 January 2009 and  $\geq 0,65$  for installations in operation after 31 December 2008 [31] (Figure 1a). Only treated sludge can achieve the relevant energy efficiency factor. The term »treated sludge« is set by the SSFD [32] as sludge that has undergone biological, chemical, or heat treatment, long-term storage, or any other appropriate process so as significantly to reduce its fermentability and the health hazards resulting from its use. Following the Technical Standard [18], the term "sludge from the treatment of urban wastewater" in mono-stream SRF means dried anaerobically stabilised excess sludge, which has undergone classification and specification.

In terms of the waste hierarchy and the basic approach to waste prevention, the view of sewage sludge is much more complex (Figure 1b). Sewage sludge is a by-product of municipal wastewater treatment, and its larger quantities are conditioned by the growth of an agglomeration infrastructure [33]. Its larger quantities mean more treated municipal

wastewater, cleaner surface waters, better-protected groundwater, and larger quantities of renewable bioresources for sustainable CE (Figure 1b).

Waste that should be utilised as an alternative to fossil fuels has to be sustainable, of renewable source, with known properties and appropriate quality, which are the feature of smart materials. A regulatory framework is needed to support sustainable and resilient sewage sludge management, incorporating a broader scope for risk assessment and strict sludge quality control [14]. To achieve the objectives of the WtE, it is necessary to consider all possible uses in the direction of energy and material use while following the protection of the environment and human health [34]. The latter is possible only with a thorough knowledge of all relevant sludge properties and the elimination components that limit this particular use. The emphasis is on substances removed from municipal wastewater using sewage sludge as a smart biogen material. Not managed adequately during recovery procedures, they can re-enter the environment. Alternatively, producing green energy from the incineration that biogen material can also be considered carbon capture. The period until 2050 should consider a transition phase to reach carbon neutrality according to the local constraints to trial new technologies and solutions.

With the efficient operation of UWWTPs, the SDGs [1] of Clean water and sanitation, Affordable and clean energy, and Responsible consumption and production can be achieved. The present paper is an addition to the two previous studies about sludge generation and characterisation at the CWWTPL [35]. They comprehensively addressed the wastewater treatment quality system and sewage sludge preparation for sustainable energy use [30] and the basis of morphological, physicochemical, and thermal properties of pellets as raw material for the CE [36]. By wastewater treatment, it is ensured the preservation of natural water resources and the generation of renewable material that can be used for energy production. According to the UWWTP's mission, a bridge between "treated sewage sludge as a tool to remove pollutants from wastewater" and "a valuable material useful for SRF that fulfils customer-specific requirements" must be created. The reference investigations and present study evaluate the critical properties of pellets for their use as a fossil fuel alternative to accelerate the renewable energy technologies in the transition period to clean energy transformation [37]. With a comprehensive review and assessment of their key properties, essential to the functioning of energy production plants, the pellets could be evaluated as a smart material for SRF preparation. The crucial and characteristical data on sludge's SRF between 2010 and 2021 are listed, which enables the safe energy use of pellets and adequate cleaning of flue gases by preventing the circulation of pollutants in the environment.

## 2. Material and methods

### 2.1. Material

The quality of the pre-treated sludge produced at the CWWTPL is discussed. The CWWTPL is a single-stage mechanical-biological wastewater treatment plant designed for conventional secondary treatment of municipal wastewater in the capital city of Slovenia (SM: Figure 1) [30, 35, 38, 39].

### 2.2. Methods and techniques

By Technical Standards [17, 18] is obligatory to specify the following SRF's properties: class code, origin, traded form, particle diameter, ash and moisture content, NCV (expressed as arithmetic mean on both dry and as received basis), and chemicals content. The latter represents chlorine (as the arithmetic means on a dry basis) and heavy metals (antimony, arsenic, cadmium, chromium, cobalt, copper, lead, manganese, mercury, nickel, thallium, and vanadium - each specified as median on dry basis). In 2021, tin (Sn) was also included among the mandatory analytes [18]. Zinc was additionally tested throughout the entire pellet quality control period. Also, sulphur was additionally analysed (in monthly and annual representative samples). The considered study also specifies some SRF's physical (bulk density, macro-impurities) and chemical properties (total organic carbon (TOC),

hydrogen, nitrogen, some halogens, and major and trace elements), labelled as non-obligatory, and analysed on the annual representative samples.

### 2.2.1. Wastewater monitoring

According to legislation, at the UWWTPs with a higher organic load than 10.000 PE, the flow of wastewater measures continuously with the Khafagi-type venturi meter and an in-line flow meter. The treatment efficiency results are verified only with representative inflow and outflow samples, characterised by standardised physicochemical tests (SM: from Table 2 to Table 8) [40]. The chemical oxygen demand (COD) in raw and treated wastewater is monitored by measurements of daily representative 24-hour time-proportional composite water samples using the accredited method from the group of standards ISO/TC 14/SC 2 - Physical, chemical, and biochemical methods. A sampling of wastewater, steps in evaluating the treatment efficiency of heavy metals (HMs) removal, and determining methods are described in detail in Supplementary material (SM).


### 2.2.2. The efficiency of pollutants removal in the raw wastewater

At the CWWTPL [13], the treatment efficiency calculation is based on i) 24-hour continuous measurement of raw wastewater flow at the inlet ( $Q_{inlet}$ ) and outlet ( $Q_{outlet}$ ), and ii) testing of 24-hour representative wastewater sample  $c_{inlet}$  (the concentration of an analyte in the raw wastewater) and sample  $c_{outlet}$  (the concentration of an analyte in the treated wastewater). The treatment efficiency of the selected analytes is presented in SM.

### 2.2.3. Pellet's monitoring – Sampling Plan, Specification and Classification

At the CWWTPL, the concept of the Sampling pattern for the SRF specification and classification is provided according to the Technical Standards [17, 18]. Figure 2 presents the sampling pattern from the hourly grab samples (Level 1) to one annual representative sample (Level 5). A quality system has been established for the pellets sampling procedure, which includes the Pellets sampling plan according to i) EN 14899:2005, Characterization of waste, Sampling of waste materials, the framework for the preparation and application of a sampling plan, and ii) the manual time-proportional daily sampling, Technical Standard ISO 5667-13:2011, Water quality, Sampling, Part 13: Guidance on the sampling of sludge from sewage and water treatment works, and iii) EN 15002:2015, Characterization of waste, Preparation of test portions from the laboratory sample, as well as routine inspection of the pellets before shipment to the stakeholder. The pellets Sampling plan takes into account the relevant Technical Standards: i) CEN/TS 15442:2006, Solid recovered fuels, Methods for sampling, and ii) CEN/TR 15310-3:2006, Characterization of waste, Sampling of waste materials, Part 3: Guidance on procedures for sub-sampling in the field.

One month of pellets production is chosen for the lot size of the SRF production (Figure 2). Pellets' classification as the SRF is based on the representative monthly samples in one calendar year (Figure 2, Level 3, and Level 4). Continual monitoring of the pellets' dry matter with moisture analysers with a halogen heater (on an hourly and daily basis) ensures the pellets' stable moisture content.



**Figure 2.** Schematic presentation of the Pellets Sampling Plan at the CWWTPL [17, 18, 36].

Periodically, every three hours, 200 mL samples of granules were manually collected from the conveyor belt (Figure 2, Level 1) [36]. Preparation of the representative composite daily sample for each shipment is provided by homogenising and quartering the three-hour sub-samples (Figure 2, Level 2). Daily samples are stored in plastic bottles of 1 L at 5 °C ± 1 °C. At the end of each calendar month, a monthly composite sample (sample increment of 400 mL) from each daily sample is provided (Figure 2, Level 3). Prepared are four composite samples (4x1 L) by homogenising and quartering the daily sub-samples. The monthly samples are stored in brown glass bottles at 5 °C ± 1 °C. The sampling period runs from 1 January to 31 December, and each year at least ten monthly samples are delivered to the authorised contractors to conduct specification and classification (Figure 2, Level 4). Similarly, mass-proportional representative annual composite samples were prepared from the refrigerated (5 ± 1 °C) monthly samples according to the quantity delivered each month. Four annual composite samples (4 x 1 L) are obtained by homogenising and quartering the monthly sub-samples. Storage is done at 5 °C ± 1 °C in brown glass bottles (Figure 2, Level 5). Parallel to monthly samples, at the end of each batch of the drying process, preparation of the composite batch sample (sample increment of 400 mL in volume from each daily sample) is executed by homogenising and quartering sub-samples (Figure 2, Level 3). Representative batch samples are stored in glass bottles of 0.75 L at 5 °C ± 1 °C [36].

The Technical report [40] and the Technical Standards [17, 18] source the concept of performing the standardised physicochemical and thermal tests - depending on the validity of the relevant standard - to characterise the quality of the representative monthly and annual samples: i) the oven dry method for moisture content at 105 °C (CEN/TC 444 - Environmental characterisation, Sludge, treated biowaste, soil and waste, EN 15934:2012, Calculation of dry matter fraction after determination of dry residue or water content), ii) laboratory furnace for loss on ignition (LOI) at 450 °C (CEN/TC 223, EN 13039:2011, Determination of organic matter content and ash) and LOI at 550 °C (CEN/TC 292, EN 15169:2017, Determination of loss on ignition in waste, sludge and sediments), iii) laboratory furnace for ash content at 900 °C (CEN/TS 343, EN 15403:2011, Determination of ash content at 550 °C, modified), and iv) standard laboratory equipment for bulk density (as received) according to CEN/TS 343, CEN/TS 15401:2010, Determination of bulk density (modified). Standard chemical analytical methods for pellets characterisation as an SRF were applied as specified by Technical Committee ISO/TC 147/SC 2, Physical, chemical and biochemical methods, Technical Committee ISO/TC 190, Soil quality, Subcommittee

SC 3, Chemical methods and soil characteristics, CEN/TC 223 "Soil improvers and growing media, CEN/TC 292 - Characterization of waste, CEN/TC 308 - Characterization of sludge, and CEN/TS 343/WG 5 – Chemical Tests, Solid recovered fuels. The NCV was performed on an air-dried sample (drying at < 40 °C with disintegrated granules < 1 mm using the Retsch SK1 hammer mill) according to CEN/TS 15400:2006, EN 15400:2011, and CEN/TS 16023:2013. The ultimate analysis was performed with Technical Standards ISO 609:1996 (TOC and H), EN 13137:2001 (TOC), EN 15936:2012 (TOC), EN 15407:2011 (H and N), ISO 11261:1995 (N), EN 13654-1:2001 (N), ISO 351:1996 (S), EN 15408:2011 (S, N, Cl, F and Br), ISO 6878:2004 (P). Decomposition of the sample due to the determination of metals, alkaline earth metals and heavy metals was performed on an air-dried sample (drying at < 40 °C, with sample size < 0.2 mm, ground in the Retsch ZM 200 mill) according to EN 13656:2004, Characterization of waste, Microwave-assisted digestion with hydrofluoric (HF), nitric (HNO<sub>3</sub>) and hydrochloric (HCl) acid mixture for subsequent determination of elements. Metals content was determined using of inductively coupled plasma mass spectrometry with optical or mass detection (ISO 17294-2 - relevant edition and EN 15411:2011). Mercury content is determined with the method EN ISO 12846:2012, Water quality - Determination of mercury - Method using AAS with and without enrichment.

Macro-impurities »Solid particles from glass, rocks, plastics, or metal > 2 mm«, expressed in % m/m<sub>DM</sub> are determined according to the Technical Specification CEN/TS 16202:2013, Sludge, treated biowaste and soil – Determination of impurities and stones. It specifies a method to assess the physical impurities > 2 mm in sludge, treated biowaste and soil and is covered by Technical Committee CEN/TC 223 - Soil improvers and growing media.

The methods used for wastewater and most of the pellets characterisation are accredited according to the Technical Standard SIST EN ISO/IEC 17025:2017, General requirements for the competence of testing and calibration laboratories and performed by authorised contractors [42, 43].

### 3. Results and Discussion

Since treated sludge represents the fingerprint of a UWWTP catchment area, treatment efficiency, and excess sludge management system, a holistic approach to its evaluation as an SRF must be done. An integral part of the processed excess sludge is mechanically-biologically removed and anaerobically stabilised organic substances with energy potential, and in contrast, the removed heavy metals from wastewater represent the stakeholder's heavy metals' environmental footprint. First, to resolve this point of view, it was taken into account the amount of treated wastewater, and the effect of removing organic substances (expressed as COD) and HMs from raw municipal wastewater, which are prescribed for controlling the quality of treated flue gases and released wastewater of combustion facility [23]. In addition, molybdenum (Mo) was analysed as an essential analyte in assessing receiving surface water quality [44] and the inertness of the resulting ash [45]. Second, the environmental footprint of the combustion plant must be linked to the quality of the treated sludge as input material, with the aim of preventing the further circulation of pollutants.

In terms of "sewage sludge footprint assessment in the WtE", the pre-treated excess sludge must be considered from several points of view, namely whether the quality of this material is predictable, comparable with other combustible materials, stable, regularly controlled and harmless for use in the environment and for human health.

The use of sewage sludge for energy production has advantages and disadvantages. It can be assessed from different engineering aspects: i) UWWTP capacity, ii) stage of wastewater treatment, iii) aerobic- or anaerobic stabilisation, iv) dehydration equipment, v) thermal treatment or drying and vi) natural and economic conditions (the location of the UWWTP, the arrangement of the transport route, and the available facilities for the final treatment of sludge). The national and local level of public awareness of the usefulness of sludge as a material for the WtE is also essential, which is also important for achieving the global SDGs.

To have confidence in the sewage sludge quality, it is necessary to have a suitable sampling procedure, a targeted end user and a list of required specified characteristics. The assessment of the usability of sewage sludge must be made in terms of several options, dynamism, reliability and feasibility. The final utilisation of sewage sludge must be adaptable to local seasonal conditions.

Additionally, in terms of "sewage sludge footprint assessment in the WtE", it is necessary to look at the economic benefits and environmental consequences of its use in the WtE in terms of the quality of treated polluted air, newly generated industrial wastewater and the quality of its recipients, soil and consequently drinking water and human health [23].


First, it is necessary to take a holistic approach to formulate the frame legislation and a global strategy in sewage sludge management regarding the WtE. Alternatively, producing green energy from incineration can also be considered carbon capture. The period until 2050 should consider a transition phase toward carbon neutrality when it is possible to trial new technologies and solutions to reach carbon neutrality according to local constraints [14].

Combustion plant operators must have a comprehensive quality control system to effectively manage the incineration process to prevent the circulation of pollutants into nature and obtain useful residues. Its crucial part must be: i) monitoring the mass balance of pollutants in flue gases and newly generated wastewater, and economic management of residues (bottom ash and fly ash). An essential part of such a holistic quality control system is the control of input raw materials, especially the input control of sewage sludge, which is recognised as a specific waste stream.


Thorough knowledge of the physicochemical properties of the SRF input is the basis for the holistic prevention of pollutant recycling in nature.

### *3.1. The Mission of the CWWTPL to achieve SDGs in Clean water and sanitation, and Responsible consumption and production*

To estimate the treatment efficiency of organic pollution, nutrients, and potentially toxic metals (PTMs), and predict their concentration level in the pellets, it is necessary to monitor the quantity and quality of inlet and outlet of a UWWTP. The quantity, flow rate of municipal wastewater, and the organic load expressed as COD in tonnes of oxygen are the most critical parameters for determining the treatment efficiency of a UWWTP. The total annual amount of treated wastewater at the CWWTPL varies between (in million m<sup>3</sup>) 32.59 (2010, a rainy year), 24.10 (2011), 28.02 (2012), 30.00 (2014), and 27.09 (2021) (Figure 3a). The monthly amount of treated wastewater at the CWWTPL ranges from 1.5 million m<sup>3</sup> in the dry summer of 2016 to 4.05 million m<sup>3</sup> during the rainfalls in the spring of 2013 (Figure 3b). The CWWTPL's geographical area characterises a pronounced rainy season in early spring and late autumn. On the contrary, compared to the apparent seasonal changes in the amount of treated wastewater, the monthly amounts of COD removed are only slightly increased in the spring period (Figure 4a). On average, in 2010 – 2021 the treatment efficiency of COD was 92.5 %, while the annual amount of removed COD fluctuated between (in tonnes of oxygen) 15.51 (2012), 14.04 (2014), 12.94 (2021), and 11.96 (2010).



**Figure 3.** Review of the operational dynamics of the CWWTPL from 2010 to 2021: a) the trend of fluctuations in the annual amount of treated wastewater, and b) seasonal fluctuation of treated wastewater's quantity.



**Figure 4.** Key dynamics of the CWWTPL efficiency potential from 2010 to 2021: a) seasonal COD removal fluctuation, and b) the average annual removal efficiency of heavy metals from raw municipal wastewater (SM: Table 2 – Table 8) [46].

Heavy metals most often characterise the environmental quality of generated sewage sludge. The scope and content of the list of heavy metals as limit parameters differ in EU Directives. EU Directives EQSD [5] and PSD [40] prescribe the list of pollutants, which is the basis for the chemical and ecological status assessment of the receiving water body. The following heavy metals and their compounds are on the list i) the Priority Hazardous Substances Cd (in  $\mu\text{g L}^{-1}$  for surface water body) and Hg (in  $\mu\text{g L}^{-1}$  for a surface water body and  $\mu\text{g kg}^{-1}$  wet weight for biota), ii) the Priority Substances Ni and Pb (in  $\mu\text{g L}^{-1}$  for surface water body), and iii) the non-synthetic Special Pollutants - the list with their limit values is in the domain of each EU Member State separately (in  $\mu\text{g L}^{-1}$  for surface water body) B, Sb, As, Co, Cr, Cu, Mo, Se and Zn [44]. By the E-PRTR Regulation [47], a register is kept about the released and transferred pollutants from large UWWTPs (organic load  $\geq 100,000$  PE). Among other parameters, the following metals' content and their compounds are monitored (in  $\text{kg year}^{-1}$ ): As, Cd, Cr, Cu, Hg, Ni, Pb and Zn. According to the IED [23], the following metals and their compounds are monitored for emissions of substances into i) the air (in  $\text{mg Nm}^{-3}$ ) Sb, As, Cd, Co, Cr, Cu, Hg, Mn, Ni, Pb, Tl and V, and ii) into the receiving water body (in  $\text{mg L}^{-1}$ ) As, Cd, Cr, Cu, Hg, Ni, Pb, Tl and Zn. Following the SSFD [32], the quality of treated sewage sludge for agricultural use is judged on the content of (in  $\text{mg kg}^{-1\text{DM}}$ ) Cd, Cr, Cu, Hg, Ni, Pb, and Zn. The parameters determining the treated sludge quality differ from its intended final utilisation. For example, the requirement for determining tin (Sn) is given only in Technical Standard [18]. In nature, the pollutants circulating in the environment and the EU Commission should unify the parameters to establish a holistic approach to environmental protection and human health.

Figure 4b shows heavy metals' average annual removal efficiencies from raw waste water between 2010-2022. The treatment efficiency was monitored twice a year only for A s, Cd, Co, Cr, Cu, Hg, Ni, Pb, and Hg (SM: Table 2 - Table 5, Table 7). For Sb, Tl, V, and M n, the treatment efficiency has been monitored since 2013 (SM: Table 3, Table 6, and Tabl

e 8), and for Mo only in the last two years (SM: Table 8). In June 2022, the concentrations of heavy metals in raw wastewater follow in the order (in mg L<sup>-1</sup>) Zn(0.28)>Mn(0.25)>Pb(0.024) >Cr(0.019)>Ni(0.017)>Cu(0.015)>V(0.0031)>Co(0.0029)> Tl(0.0025=LOD/2)>As(0.00093)>Mo(0.00054)>Sb(0.00035)>Cd=Hg(0.00019) (SM: Table 2 to Table 8). On average, the order of treatment efficiency in 2010 – 2022 is (in %) Pb(86.8)>Cu(83.4)>V(77.6)> Mn(76.6)> Hg(71.5)>Zn(71.0)>Cr(63.5)>Cd(54.6)>Ni(52.5)>Mo(49.1)>As(32.5) (Figure 4b, SM: Table 2 to Table 8). From the data on the removal efficiency of PTMs, no distinct trend can be observed. The mixture of large amounts of precipitation and municipal wastewater in 2010 (Figure 3b) reflects poorer removal efficiency only for Cr and Hg (Figure 4b). Active sludge is undoubtedly a suitable tool for removing such pollutants based on adsorption [48], absorption, and biological processes. Only one measurement was quantified for Sb at inflow (2.1 µg L<sup>-1</sup>; 75.5 % treatment efficiency). Other results were below LOD = 0.001 mg L<sup>-1</sup> at inflow and outflow (SM: Table 3). Also for Tl, it was possible to estimate the treatment efficiency with only one measurement (90.8 % removal efficiency), which was higher than LOD at inflow and outflow (SM: Table 5). In the mentioned time period, only two measurements were performed for Mo (1.8 µg L<sup>-1</sup> at inflow with 45.3 % removal efficiency and 0.54 µg L<sup>-1</sup> at inflow with 53.0 % removal efficiency).


Certainly, UWWTP treatment technology is essential for achieving some SDGs. Still, the entire municipal infrastructure in the contributing area is vital to improving its pollutant removal efficiency - the careful use of drinking and underground water, the effective separation of precipitation wastewater from municipal wastewater, and the effective pre-treatment of industrial wastewater.

### 3.2. *The CWWTPL as a point of acceptance of non-hazardous waste to produce the SRF*


Advanced treatment of generated sludge must achieve high efficiency in water removal from the excess sludge and enhance biogas production to achieve optimal consumption of external energy. The quality of generated pellets represents the fingerprint of the UWWTP on the area of the excess sludge pre-treatment. They are non-hazardous waste (SM: Table 9) [49, 50, 51, 52, 53, 54], which is also a precondition for using waste to prepare an SRF.

The SRF flow chain concept – from the input of non-hazardous waste to the SRF production as the point of acceptance and its final utilisation as a point of delivery – is adapted to the mission of the UWWTPs operation and treated sewage sludge as a specific mono-waste stream. A bridge must be made from “Agreed acceptance criteria” to “Customer specific requirements” [17, 18]. According to the UWWTP’s mission, this means that a bridge between “treated sludge as a tool to remove pollutants from wastewater” and “a valuable material useful for SRF that fulfils customer-specific requirements” must be created.

At the CWWTPL [35], the digestate drying process is performed in batch mode [36]. In 2021, there were 34 single batches (Figure 5a), and the quality of representative samples of single batch series fluctuates markedly seasonally (Figure 5b). The period of a single batch is of different lengths, so the mass of pelletised digestate during one batch varies between 38 tonnes to 175 tonnes (Figure 5b).



**Figure 5.** Quality and quantity dynamics of batch series in 2021: a) bulk density and moisture of batch representative samples, and b) seasonally fluctuation of pellets production, their organic matter content at 450 °C, and LOI at 550 °C and 900 °C.



**Figure 6.** Seasonal dynamics in pellets' production and quality in 2010 - 2021: a) seasonal production in  $\text{g}_{\text{DM}}$  per PE in one day, and b) seasonal fluctuation of their volatile matter.

The moisture content fluctuates from 7.5 % m/m to 9.5 % m/m, and the bulk density from 635 kg m<sup>-3</sup> to 711 kg m<sup>-3</sup> (Figure 5a). The pellets' biomass content (LOI at 450 °C as an organic matter content) is characterized by the lowest over the summer. In contrast, the mineral content, determined as the difference between LOI at 550 °C and LOI at 450 °C, is the highest (Figure 5b). The latter mass loss is probably due to the thermal decomposition of MgCO<sub>3</sub> or minerals containing magnesium, phosphorus and carbonates [36]. The CaCO<sub>3</sub> content, evaluated as the difference between LOI at 900 °C and LOI at 550 °C, is stable over the year (Figure 5b). Knowing the naturally occurring source of inorganic CO<sub>2</sub> in the SRF is very important in evaluating emission coupons.

On average, the pellets production from 2010 – 2021 was i)  $31.4 \text{ g}_{\text{DM}} \pm 5.6 \text{ g}_{\text{DM}}$  per 1 PE<sub>COD</sub> in one day (Figure 6a), ii)  $10.6 \pm 0.6$  (in tonnes<sub>DM</sub> per day), iii)  $322.0 \pm 55.9$  (in tonnes<sub>DM</sub> per month), and iv)  $3,864 \pm 1$  (in tonnes<sub>DM</sub> per year). In the summer months, the production of pellets is higher (Figure 6a), while their volatile fraction is lower (Figure 6b), namely 65.5% m/m<sub>DM</sub> on average, while the average of the other months is 68.1% m/m<sub>DM</sub>. As received quantity at stakeholders fluctuates between (in tonnes) 3,915 (2014), 3,930 (2010), 4,012 (2021), and 4,158 (2012).

### 3.3. The pellets' specification

Technical standards [17, 18] are the source of the SRF sampling concept and characterisation procedure. The samples and subsamples preparation and their storage take place in 5 levels (Figure 2): i) Level 1 – one sample increment (grab sample) every three hours of pellets production, ii) Level 2 – daily representative samples, iii) Level 3 and Level 4 – batch/ monthly samples, and iv) Level 5 – annual representative sample.

Due to the mechanical treatment of raw wastewater, no visible particles are detected in the pellets as macroscopic impurities (MI) as the glass, metal, and plastics are. Results of content tests are MI = < 0.5 % m/m<sub>DM</sub>.

According to the SRF characterisation procedure, the volatile matter determined at 550 °C presents the combustible share of SRF in question. The share of volatile matter in annual representative samples, expressed as LOI at 550 °C, ranges from 61.1 % m/m<sub>DM</sub> (in 2010) to 70.9 % m/m<sub>DM</sub> (in 2020), which contributes to the NCV and economically favourable energy use (Table 1). Ash content presents the mass of inorganic residue after fuel ignition under specific temperature conditions.

**Table 1.** Proximate analysis of annual pellets samples.

Parameter/ annual sample	Unit	Y2010	Y2012	Y2013	Y2014	Y2016	Y2018	M2019*	M2020*	Y2021
Bulk density	kg m <sup>-3</sup>	704	641	676	683	646	648	637	633	668
DM, 105 °C	% m/m	91.3	91.5	90.7	91.5	91.0	90.4	91.1	91.7	91.9
LOI, 550 °C		61.1	67.6	66.3	67.4	66.3	68.6	70.5	70.9	66.9
Ash, 550 °C	% m/m <sub>DM</sub>	38.9	32.4	33.7	32.6	33.7	31.4	29.5	29.1	33.1
Ash, 900 °C**		33.2	28.5	29.6	29.4	29.8	28.1	24.0	25.9	29.6
NCV	MJ kg <sup>-1</sup> ar	11.8	13.3	11.9	13.2	12.8	13.1	13.7	14.0	13.3
	MJ kg <sup>-1</sup> DM	12.9	14.9	13.3	14.4	14.2	14.5	15.0	15.0	14.5

\* Average values of 10 consecutive monthly subsamples of pellets. \*\*Modified standard method for the ash determination at 550 °C.

The sources of carbon (organic and inorganic), nitrogen, hydrogen, and sulfur in pellets are biological macromolecules (proteins, carbohydrates, lipids, and some coenzymes) and the mineralogic structure of microorganisms (as a carbonate content). The latter are carriers of biological processes of municipal wastewater treatment. Because pellets are a biogen material, they contain i) vital elements (C, H, N, S, O), ii) nutrients and macroelements (N, P, Si, Ca, Mg, K and Na), and iii) essential PTMs (Fe, Mn, Co, Zn, Cu, Cr and Mo), (iv) non-essential PTM (Al), and (v) highly toxic PTMs (Hg, Cd, Pb, and metalloid As) [55, 56]. Table 2 shows that from 2010 to 2021 the content (in % m/m<sub>DM</sub>) of nitrogen (2010 - 2021; c (N) =  $5.35 \pm 1.05$ ), hydrogen (2010 - 2014, 2021; c (H) =  $4.65 \pm 0.38$ ) and sulfur (c (S) =  $1.01 \pm 0.21$ ) repeated in pellets. Pellet's ultimate analysis from 2010 to 2021 shows significant deviations in organic carbon content (c (TOC) =  $35.1 \pm 3.7$  % C m/m<sub>DM</sub>). 2010 was extreme in rainfall, so TOC is the lowest. After 2014, there is a slight downward trend (Table 2). Changes in the anaerobic stabilisation of excess sludge and biogas production contribute to the lower value for TOC in 2021.

The pellets' content and composition of the main mineral elements are essential in predicting the properties of the resulting residue and its impact on the optimal operation

of the facility (Table 3). Na, K and Al could influence the appearance of sintering of the residue and the formation of melt, which is disturbing for the device.

**Table 2.** Ultimate analysis of annual pellets samples.

Analyte	Unit	Y2010	Y2012	Y2013	Y2014	Y2016	Y2018	Y2021
TOC	% C m/m <sub>DM</sub>	29.0	38.4	37.6	39.5	33.1	35.7	32.7
TIC		no a.	2.0	3.6	1.5	9.9	6.9	3.9
N		4.90	6.15	5.89	5.58	5.75	6.01	3.15
H	% m/m <sub>DM</sub>	4.57	4.40	4.21	5.08	no a.	4.99	
S		0.69	1.15	0.93	1.26	1.06	0.80	1.2
O*		21.9	15.5	14.3	15.1	no a.		21.2

\* Calculated.

From the point of view of material use and the CE, the residue contains many critical raw materials (phosphorus and other nutrients), as well as elements that contribute to the usefulness of the residue for geotechnical composites and construction products, and this is a great advantage. The content of macroelements (P, Si and Ca) in pellets is regularly monitored (Table 3). The content of phosphorus as an essential critical raw material for the CE [57] was reproducible from 2010-2021 (till the summer of 2022, the chemical removal of phosphorus at the CWWTPL was not yet underway) due to stable biological processes. There is a decreasing trend for potassium content and TOC as nutrients. The content of Si and Ca in the pellets fluctuates (Table 3), which means that they are subject to the impact of stormwater discharges into the public sewerage system. The content of Mg, Fe, Al, Ti and Na are not monitored regularly, but it can be estimated that they have repeatable values.

**Table 3.** Ultimate analysis of annual pellets samples to macroelements in % m/m<sub>DM</sub>.

Analyte	2010	Y2012	Y2013	Y2014	Y2016	Y2018	Y2021
Si	no a.	3.3	5.6	6.1	9.4	7.6	3.4
Ca	5.2	4.6*	4.8	4.7	3.7*	6.4*	3.2*
P	1.07	2.22*	1.92	1.77	1.62*	1.45*	1.67
Mg	1.0	0.96*	0.42		no a.		0.67
Fe	1.2	0.92	1.1	1.2		no a.	
Al	1.0	0.88	0.78	0.88		no a.	
K	0.22	0.30*	0.36	0.39	0.28*	0.32*	0.20
Ti		0.14	0.15				
Na	no a.	0.12	0.14			no a.	

\* Digestion for subsequent determination of aqua regia soluble portion of elements.

Table 4 shows an overview of micronutrients and trace elements. Their increasing content in pellets presents their order in 2021 (Table 4, sample Y2021). The IED [23] sets the emission limit values for Tl, Cd, Hg, As, Ni, Pb, Cr, Cu, and Zn for wastewater discharges from waste gas treatment. The pellets' chlorine content in 2010-2021, which can potentially cause corrosion in the incinerator, is low ( $c(\text{Cl}) = 0.079 \pm 0.034 \text{ % m/m}_{\text{DM}}$ ) and results from edible salt in municipal wastewater (Table 4). Besides chlorine, zinc has the highest content in pellets among the elements listed in Table 4 (according to the removal efficiency is in 6<sup>th</sup> place, Figure 4b). Zinc is relevant for emission limit values for discharges of newly generated wastewater at the combustion plant. As a heavy metal, Zn also has the highest concentration in raw wastewater (SM: Table 4). Co, Mn and V are elements for which EU Directives determine only the emission limit values into the air [23]. According to the Slovenian legislation, Sb, As, Co, Cr, Cu, Mo, and Zn are also non-

synthetic Special Pollutants of surface water bodies [44]. As a pollutant, Tl is mentioned only on the List for the emission limit values into the air and newly generated wastewater. The concentration of Tl in SRF is practically zero [18], which was also confirmed for pellets (Table 4). Among the elements in Table 4, a decreasing trend in their content in pellets is observed only for Cd and Hg. Hg is an atmospheric deposit and poses a global threat to the environment and human health. Due to human activity, Hg levels in the atmosphere were 450 % above natural values, representing a 20 % increase in Hg in the environment between 2010 and 2015 [58].

**Table 4.** Ultimate analysis of annual pellets samples to microelements and trace elements in mg kg<sup>-1</sup>DM.

Analyte	Y2010	Y2012	Y2013	Y2014	Y2016	Y2018	Y2021
Tl	<10	<0.5	<0.5	<0.5	no a.	0.13	<0.16
Cd	1.0	1.2	1.2	1.1	1.1**	0.80	0.90
Hg	2.8	1.8	1.7	2.3	1.7**	1.14	1.0
Se	<20	3.4	3.1	4.4		no a.	
As	<20	3.5	3.9	3.8	3.6**	3.3	4.1
Sb	<20	4.3	3.7	2.6	3.5**	2.7	4.2
Mo	<50	8.3*	11	9.0		no a.	
Co	9.0	17	8.4	6.7	9.7**	6.8	9.3
V	<20	17	18	19	no a.	20	29
Br	<50	<21	<37	62		no a.	
Pb	84	93	80	78	85**	66	71
Sn				no a.***			79
Ni	54	86	82	80	73**	75	98
F	98	120	114	139	no a.	86	no a.
Cr	84	120	110	110	130**	100	100
Mn	270	310	270	300	no a.	250	270
Cu	310	350	410	540	230*	350	540
Zn	920	1000*	930	920	720*	790*	850
Cl	100	810	770	1120	1070	750	940


\*Digestion for subsequent determination of aqua regia soluble portion of elements. \*\* Average of ten representative monthly samples (Jan.– Oct.). \*\*\* In 2021, Sn was included among the mandatory analytes [18].

The obtained data (from Table 2 to Table 4) are essential from the point of view of wastewater treatment, protection of natural water sources, and further procedures for the final use of pellets. The purpose of the multi-year data is to assess the pellets' quality and their end users' supply dynamics. It should not only look at the basic parameters for pellets classification as a solid alternative fuel. If the goal is the sustainable consumption of pellets, it is also necessary to know the dynamics of macro-, micro-, and trace elements. These data enable careful consideration of the transfer of pollutants to the final stakeholders, with the aim of efficient and safe management of combustion plants, flue gas cleaning, and optimal ash management, which are essential aspects of the sustainability of energy use. In 2010 – 2021, the prescribed sum of concentrations of analytes Sb, As, Pb, Cr, Co, Mn, Ni, and V [23] fluctuated between (in mg kg<sup>-1</sup>) 841 (2010), 1,001 (2012), 1,126 (2021), and 1,140 (2014). Figure 7a presents the annual amount (except for the years 2015 and 2017, when the basis for the calculation was the average value for monthly representative samples) in the order of magnitude from 65 kg (V in 2012) to 3,839 kg (Zn in 2012) of HMs transferred to stakeholders. Figure 7b presents the transferred amount up to 65 kg. Regarding the amount of heavy metals transferred to stakeholders in 2010 – 2021 (Figure 7), the order is as follows (in average mass (kg) ± relative standard deviation (RSD) in %) Zn(3,35 ±9.81)>Cu(1,543±25.6)>Mn(1,071±6.93)>Cr(460±28.2)>Ni(325±14.6)>Pb(303±11.6)>Sn (290,


$\text{Ni}=1$ ) > V ( $78.7 \pm 21.6$ ) > Co ( $35.9 \pm 35.1$ ) > Mo ( $35.6 \pm 16.8$ ) > As ( $18.8 \pm 8.45$ ) > Sn ( $13.4 \pm 17.0$ ) > Hg ( $6.06 \pm 2.4.8$ ) > Cd ( $4.02 \pm 13.5$ ). According to one measurable measurement of thallium in 2016, its annual amount transferred was 550 g. The obtained data show us the difference in the quality of the pellets, which depends on the characteristics of the catchment area (organic load of wastewater expressed as PE, number of inhabitants, industrial activity, mixed or separate sewage system) and the influence of atmospheric deposits, for example, Hg. The latter accumulates in the waste rainwater that flows to the municipal treatment plant. The trend of the annual transferred amounts of Hg shows a significant decrease, while the shares of other pollutants do not offer a marked tendency (Figure 7).

Knowing micro-elements content is essential when it is necessary to immobilise PTMs in cases where the appropriate leachate quality is a condition for specific product use. Data on the range of micro-elements are also crucial for extraction procedures of phosphorus recovery because they can predict the quality of the extract with the soluble form of phosphorus. Based on the quality of the treated sludge in question, a technologist can prepare an appropriate plan for the most optimal phosphorus recovery process. In addition to phosphorus, when there is a shortage of raw materials, pellets will become interesting for obtaining other elements, for example, copper, nickel and cobalt.

Data on the content of transferred pollutants are essential for controlling the mass flow of pollutants to prevent their circulation in the environment (Figure 7).



**Figure 7.** The transferred HM<sub>s</sub> to stakeholders in 2010 – 2021: a) the annual amount of HM<sub>s</sub> in the order of magnitude from 65 kg to 3,839 kg, and b) the annual amount of HM<sub>s</sub> up to 65 kg.



**Figure 8.** Hierarchy of the mission of the CWWTPL.


The fundamental mission of CWWTPL operation is to treat municipal wastewater, the contents of septic tanks, and sewage sludge produced at small UWWTPs. Figure 8 schematic presents the priority route. The results of wastewater and sewage sludge management at the CWWTPL for 2019 show the basic concept of the UWWTP's mission. In 2019, 27.2 million  $m^3$  of treated wastewater was released into the Ljubljanica river. The

pellets' production was  $6,980 \text{ m}^3$  in volume. This means that 4,443.78 tonnes of pellets were delivered to the stakeholder, and  $0.00039 \text{ m}^3$  of mercury was transferred with them (Figure 8).

It is necessary to have a holistic approach to evaluate the municipal wastewater from the extensive contribution area and, consequently, to the generated sewage sludge, to solve the problems due to its inadequate quality. Without improving the control and the quality of the pre-treated industrial wastewater, the quality of the treated sludge will not significantly enhance either [14].

### 3.4. Point of an SRF delivery

The point of pellets' delivery is the turning point at the CWWTPL when pellets become a renewable fuel source [19]. The point of delivery is an important point where pellets change ownership and category - they become a combustible material. The stakeholder assumes environmental responsibility for their economic use. As the accompanying documentation is comprehensive and indicates all characteristics, it enables the stakeholder to manage produced ash and minimise the environmental impact. The point of SRF delivery is the turning point at which the quality of treated sewage sludge starts to assess from the SRF stakeholders' point of view. Necessary is knowledge of i) pellets classification, ii) transport dynamics and average daily delivered quantity, iii) optimal energy use and mixing with other combustible materials and waste, iv) potential environmental impact due to pellets combustion, and v) process of the incineration (combustion behaviour, prevention of corrosion on the device, and ash production).



**Figure 9.** Dynamics in pellets' delivery to stakeholders from 2010 to 2021: a) seasonal pellets delivery (in tonnes as received), and b) seasonal organic matter delivery (in g per PE in one day).

Figure 6 presents the seasonal dynamics in pellets' production (on average,  $31.4 \text{ g}_{\text{DM}} \pm 5.6 \text{ g}_{\text{DM}}$  per 1 PE<sub>COD</sub> in one day) and their volatile matter as LOI in % m/m<sub>DM</sub>. In contrast, Figure 9 presents the dynamics in the delivered monthly amount of pellets in tonnes and their monthly average organic content expressed in g PE<sup>-1</sup> day<sup>-1</sup>. The dynamics in Figure 4a (COD removal), Figure 6a, Figure 9a, and Figure 9b are comparable. On average, in terms of delivered combustible material, the transferred organic matter to stakeholders in 2010 – 2021 was i)  $21.2 \pm 3.9$  (in g per 1 PE<sub>COD</sub> in one day), ii)  $7.1 \pm 0.6$  (in tonnes per day), iii)  $217.4 \pm 40.8$  (in tonnes per month), and iv)  $2,609 \pm 1$  (in tonnes per year).

#### 3.4.1. Pellets classification as an SRF

Dried treated sewage sludge is a biogen material and a specific non-hazardous waste stream (SM: Table 9). The studies by [59, 30, 36] reveal that to achieve adequate traceability of pellets, and their quality and classification for use as an SRF, it is necessary to establish an appropriate quality management system.

Only fuels derived from non-hazardous waste [17, 18, 31] can be classified as SRF. Five quality classes divide each classification characteristic (SM: Table 10). Each classification characteristic should be considered equally important. The Class code combines all three key properties and shall be included in the specification. Fuel outside the ranges of

the classes shall not be defined as SRF [18]. The SRF preparation proceeds with pellets' characterisation and categorisation according to quality class criteria, focusing on the key parameters NCV, Cl, and Hg [16, 17, 18]. The results of the chemical analysis of representative samples of each SRF production lot obtained over one calendar year must be statistically processed. At first, the authority contractor must determine the production lot size. The statistical distribution pattern of the characteristics parameters (average, median, and 80<sup>th</sup> percentile) evaluates the quality class of SRF. When the 12-month production is less than 15,000 tonnes, the lot size for classification shall be one-tenth of the amount produced in a 12-month rolling period. From 2010 – 2021, the annual pellets production at the CWWTPL is approximately 4,200 tonnes<sub>ar</sub>, and the monthly output varies by season, precipitation, and maintenance work (Figure 6a). After the statistical distribution pattern of the obligatory characteristics, the pellets' Quality Class codes for 2021 were NCV 4; Cl 1; Hg 3, as was also determined in previous years [30].

The specification of the SRF gives the relevant fuel properties. Still, it is also important to the character of the input material and the technology used either in production or end use of the SRF. The classification is not enough for an intending user or other stakeholders [18], but it is a tool for identifying and pre-selecting SRF. Not all kinds of SRFs are suited for all energy recovery installations [16]. From the stakeholder across Europe, there is no consistent level for the scope of information regarding the SRF quality. The performance of the combustion facility depends on the design and operating conditions and limit values set by the competent authority in an environmental permit. The plant must comply with national legislation and BAT, and report its updates to the relevant authorities. By selecting the appropriate SRFs, the facility operation is optimal, successfully prevents unwanted emissions of substances into the air and water, and prolongs its lifetime.

The national legislation of each EU Member State determines the manner of application of the SRF. Slovenian legislation prohibits SRF produced from contaminated biomass and combustible waste, with Class code 5 for NCV and Class code 2, 3, 4, or 5 for the Hg/NCV ratio [60, 61]. At the existing combustion facilities in Slovenia, pellets cannot be utilised as a single SRF but only as waste with classification number 19 08 05 at the industrial co-incineration plants. The use of pellets as SRF is only allowed in Slovenia if mixed with other combustible waste, and the proportion of pellets is at least 3% m/m [61].

### 3.4.2. Dynamics of pellets' transport


The pellets must be properly stored until they are taken over by the stakeholder. Long-term storage of pellets is not possible at the CWWTPL. They must have appropriate storage conditions. The storage decision relates to the appropriate technical options for preventing NCV deterioration because of the economic value of the pellets, and storage is also a safety category. During the pellets production cycle, it is necessary to daily empty the silo to temporarily pellets storage. Delivery must be carried out regardless of the hour or day of the week. Holidays and non-working days are included. Pellets are shipped between 70 % v/v and 73 % v/v filling of the collection silo at the latest (SM: Figure 1). The hourly production of pellets is approximately 700 kg, or 2 % v/v of the silo. The filling of the collection silo with more than 75 % v/v does not provide the prescribed explosion protection and is not allowed during continuous pelleting. Pellets transport is carried out with standard trucks or tank trucks. Between 2017 and 2021, an average of 170 pellet shipments per year were sent to stakeholders. On average, on the operating days, the mass of one shipment is 25.4 tonnes (as received) or a volume of 38.9 m<sup>3</sup> with an average bulk density of 653 kg m<sup>-3</sup>.

The dryness of pellets results not only in lower transportation costs but in drastically decreasing disposal costs. To mitigate climate change, the energy recovery facilities should be as close as possible to the place of origin of combustible waste. In the study [62], possible alternative scenarios for pellets' final utilisation and the impact on Carbon Footprint (CFP) were determined. It was founded that CFP of various approaches i) pellets' thermal and material utilisation in a cement plant (distance from the place of origin 120 km), ii) pellets' thermal utilisation in a thermal power plant (distance from the place of

origin 7 km), and iii) mono-incineration in own plant are more or less similar but smaller than conventional sewage sludge treatment.

### 3.4.3. Energy use and mixing with other combustible waste

The NCV sources from the organic matter (Table 2, LOI), the content of TOC and H (Table 3), and presents the economic value of SRF in question. According to Technical Standard [18], the NCV values must be expressed as an arithmetic mean on a dry (DM) and received basis (ar).




**Figure 10.** Monthly energy value's dynamism of pellets in 2010 - 2021: a) pellets' calorific value (NCV), and b) delivered renewable energy in GJ<sub>ar</sub>.

Figure 10a presents an overview of the values for NCV<sub>ar</sub> for representative monthly samples from 2010 - 2021. Seasonal fluctuation characterises NCV. It is similar to seasonal changes in LOI at 550 °C (Figure 6b). Pellets have a Class code of 4 for NCV. On average, the value for NCV in the spring is approaching that of Class code 3 (one level better Quality Class), but this value did not reach throughout the investigation period. In summer, the NCV is mostly below 13 MJ kg<sup>-1</sup>ar. The trend for the amount of renewable energy in GJ that pellets provide (Figure 10b) in one month of production is even more markedly similar to the dynamism of pellets production in g PE<sub>COD</sub><sup>-1</sup> in one day (Figure 6a). Those parameters represent the fingerprint of the CWWTPL's efficiency. From 2010-2021, the amount of renewable energy delivered to stakeholders ranged from 2,800 GJ in October 2010 to 6,750 GJ in March 2019 (Figure 10b). On average, the annual supply of potential energy to the stakeholders in 2010 – 2021 is 55,488 GJ<sub>ar</sub> ± 7.6% (46,575 GJ<sub>ar</sub> in 2010; 55,610 GJ<sub>ar</sub> in 2012; 54,545 GJ<sub>ar</sub> in 2014, and 52,488 GJ<sub>ar</sub> in 2021).

### 3.4.4. Emission potential assessment -Environment footprint of the combustion plant: SRF - emissions potential assessment to ensure non-harmful utilisation


The content of heavy metals Sb, As, Cd, Cr, Co, Cu, Pb, Mn, Hg, Ni, Tl, Sn and V presents the chemical properties of SRF, which are the obligatory properties to specify the SRF (Technical Standard, Appendix A, 2021). The content of Cd in pellets' monthly representative samples has been monitored regularly since 2010 due to the requirements of Slovenian legislation [60, 61]. Since 2014, the content of Sb, As, Co, Cr, Pb, and Ni has been determined only occasionally (Figure 11) due to Austrian legislation [63] and pellets' exportation to Austria. In 2022, Cu, Mn, Tl and Sn have also been monitored according to the new Technical Standard [18]. Figure 11a presents the pellets' heavy metal concentration, each <12 mg kg<sup>-1</sup><sub>DM</sub>, and Figure 11b presents the heavy metal concentration, each <200 mg kg<sup>-1</sup><sub>DM</sub> and >50 mg kg<sup>-1</sup><sub>DM</sub>. As, Cd, Sb, and Co are characterised by a very low content in raw wastewater, at the level of  $\mu$ g L<sup>-1</sup> or <LOQ (SM: Table 2 and Table 3), while the concentration in pellets c(median, As) = <4.6 mg kg<sup>-1</sup><sub>DM</sub>, c(median, Cd) = <1.25 mg kg<sup>-1</sup><sub>DM</sub>, c(median, Sb) = <3.75 mg kg<sup>-1</sup><sub>DM</sub>, and c(median, Co) = <11 mg kg<sup>-1</sup><sub>DM</sub>. The content of Cr, Pb, and Ni in raw wastewater is at the level of about a few tens of  $\mu$ g L<sup>-1</sup> (SM: Table 4 and

Table 7), while the concentration in pellets c (median, Cr) = <195 mg kg<sup>-1</sup><sub>DM</sub>, c (median, Pb) = <96.5 mg kg<sup>-1</sup><sub>DM</sub>, c (median, Ni) = <110 mg kg<sup>-1</sup><sub>DM</sub>.



**Figure 11.** The statistical distribution pattern for obligatory heavy metals to specify pellets: a) median concentration for Sb, As, Co, and Cd, and b) median concentration in pellets for Cr, Pb, and Ni.


Globally, Hg poses a severe threat to the environment and human health. Replacing mercury lights with light-emitting diodes (LEDs) reduces electricity demand, the need for mercury, and the end-of-life management impacts of mercury-containing lamps. But on the other hand, LEDs potentially contain other heavy metals, including Ni, Pb and As, and should also be adequately managed at the end-of-life [58]. That Hg is a pronounced atmospheric deposit in wastewater was shown in 2010, when the CWWTPL was marked by heavy rains and floods (Figure 3).



**Figure 12.** Dynamics of pellets monthly concentrations from 2010 - 2021 for a) mercury and b) cadmium.

Figure 12a indicates that the Hg content in pellets was the highest in 2010 when most wastewaters was also collected. Figure 12a helps us understand the seasonal declining trend of Hg content in pellets from 2010-2021. The most pronounced decrease in the Hg content in the pellets is visible in the first three months of each year (Figure 12a). On the contrary, the Cd content in pellets (Figure 12b) has a concentration of around one mg kg<sup>-1</sup><sub>DM</sub>, regardless of larger volumes of wastewater. Only the value for August 2018 differs significantly, and the reason is not known.

The ratio Hg/NCV is the key environment characteristic of the SRF classification code [17, 18]. The two statistical values (median and 80<sup>th</sup> percentile) in a Hg data set determine one of the five Class codes (SM: Table 10; Figure 13a). For Hg, the higher of the two statistical values in a Hg data set determines the class. From 2010 – 2021, the value for the ratio Hg/NCV decreased from 0.230 mg MJ<sup>-1</sup><sub>ar</sub> (80<sup>th</sup> percentile) and 0.202 mg MJ<sup>-1</sup><sub>ar</sub> (median) to 0.079 mg MJ<sup>-1</sup><sub>ar</sub> (80<sup>th</sup> percentile) and 0.071 mg MJ<sup>-1</sup><sub>ar</sub> (median). The improvement in the quality of pellets as SRF (Figure 13) is due to the reduced Hg content on the global level. The year 2021 marks the beginning of a new decade, which should also bring a better climate on the global level by 2030 [58].




**Figure 13.** Review of Hg-fingerprint at the CWWTPL in 2010 – 2021, based on monthly representative sample: a) the ratio Hg/NCV - the key environment characteristic of the SRF classification code, summarised after [30] and supplemented with actual data for the year 2021), and b) the annual transferred amount of Hg to the stakeholder expressed in  $\mu\text{g Hg PE}_{\text{cod}}^{-1}$  in one day, and as  $\mu\text{g Hg}$  per one habitant (HBT) in one day.

Hg fingerprint for the Slovenian capital Ljubljana shows a tremendous decrease from 2010 – 2021 (Figure 13b). On average, from 2010 - 2016, the removal efficiency for Hg was  $70.4\% \text{ m/m} \pm 25.1\% \text{ m/m}$ , and in 2022  $78.3\% \text{ (SM: Table 6)}$ . Except in 2010, when the efficiency of Hg removal was only  $26.9\% \text{ m/m}$  due to large-scale floods, the effect of Hg removal from 2011-2016 was  $79.1\% \text{ m/m} \pm 14.9\% \text{ m/m}$  (SM: Table 6). Figure 7b and Figure 13b present the transferred annual Hg amount to stakeholders. Although the effect of Hg removal was worse in 2010-2011, the amount of removed Hg was the highest,  $10.12 \text{ kg Hg}$  in 2010 and  $8.82 \text{ kg Hg}$  in 2011. From 2010 - 2021, the annual transferred amount decreased to  $3.62 \text{ kg Hg}$  (Figure 13b), from  $92.7 \mu\text{g Hg per PE}_{\text{cod}}$  in one day to  $33.8 \mu\text{g Hg}$ , and from  $112.7 \mu\text{g Hg per habitant}$  in one day to  $34.8 \mu\text{g Hg}$  (Figure 13b).

Achieving the SDG on "Affordable and clean energy" based on treated sewage sludge is possible. With the help of activated sludge, enormous amounts of municipal wastewater are purified, and the final product of the treatment of excess sludge has a sufficient calorific value. By regularly monitoring the content of heavy metals in the treated sludge, the use of efficient flue gas cleaning techniques and monitoring the material flows of pollutants at the recipient's location, the energy utilisation of the sludge-derived SRFs can be environmentally non-harmful.

#### 3.4.5. The combustion plant operation - corrosion potential and ash production

According to the Technical Standard [64], the determination of the total sulphur, chlorine, fluorine and bromine content of SRF is necessary for environmental and technical reasons, both in the production and combustion process. During the combustion process, are usually converted to sulphates and halides. These reaction products could contribute to corrosion and environmentally harmful emissions. Via the CWWTPL, sulphates and chlorides in raw municipal wastewater are only transferred to the receiving surface water body. The effect of removal is negligible. The content of F and Br in wastewater is low and is checked periodically (Table 4). Chlorine is the key technical characteristic to evaluate the possibility of corrosion damage on parts of the combustion plant hardware.



**Figure 14.** Dynamics of pellets monthly concentrations from 2010 - 2021 in % m/m<sub>DM</sub> for a) chlorine and b) sulphur. .

On average, the pellets' chlorine content is 0.06 % m/m<sub>DM</sub> to 0.10 % m/m<sub>DM</sub>, and presents the 1<sup>st</sup> Quality Class code (Figure 14a). Chlorine has a great influence on the process of corrosion, slagging and fouling of boilers. The class boundaries are chosen to consider the SRF properties on the one hand and the requirements of the stakeholders on the other hand.

Sulfur is the constituent of cysteine, methionine, glutathione, and several coenzymes. Therefore, sulfur is present in denatured proteins, the fundamental pellets' constituents. The presence of sulfur in pellets means "natural background"; thus, the component considered must be an integral part of a comprehensive plan for optimal combustion facility management. On average, the pellets' sulphur content is 0.7 % m/m<sub>DM</sub> to 1.2 % m/m<sub>DM</sub> (Figure 14b). According to Slovenian legislation, the limit value for the sulfur content in SRF is 0.2 % m/m<sub>DM</sub> (Figure 14b) [61], which means that pellets as a single SRF may not be used in Slovenia unless they are processed in an energy recovery facility placed at the site of origin.

Combustion residues are an integral part of the incineration process. The content of non-volatile and non-combustible content significantly impacts the quality of SRF. Technical Report [16] presents an overview of the SRF quality with low and high ash content. The sludge-derived SRF contributes to substituting raw materials while decreasing the NCV value. That directly affects the Hg values using the unit mg Hg MJ<sup>-1</sup> and the Cd content (SM: Table 10). During incineration, the concentration of non-volatile macroelements can increase up to 3 times. Calculated on the obtained laboratory data (Table 1, ash content at 550 °C), for the period 2010 – 2021, the annual amount of ash reaches 1264 tonnes<sub>DM</sub> ± 36 tonnes<sub>DM</sub>. For the resulting ash, IED [23] prescribes that it is necessary to establish ash management and plan sustainable use. Regarding the macro-elements composition (Table 3), a dynamic circular economy is a condition for the successful material use of ash.

## 5. Conclusions

The mission of the UWWTs is the effective treatment of municipal wastewater. In the case of the CWWTPL, which is a large municipal wastewater treatment plant, the possibility is presented of a holistic approach to the management of sewage sludge, which enables the integrated implementation of wastewater treatment, SRF production, and the bridge to WtE in terms of the adopted waste hierarchy, reducing the carbon footprint and the pollution of the environment. All the crucial and characteristical data between 2010 and 2021 are listed. The generated pellets are evaluated as a smart material with a comprehensive review and assessment of their critical properties, essential to the functioning of energy production plants.

Pellets do not automatically fit into existing definitions of waste. Its larger quantities mean a higher amount of treated municipal wastewater, cleaner receiving surface water, better-protected groundwater, and larger quantities of renewable bioresources for sustainable CE. The case study of pellets produced at CWWTPL shows that pellets have been generated due to environmental protection and human health, and the utilisation of their

renewable energy must proceed in the same manner. Specifying and classifying pellets as non-hazardous alternative solid recovered fuel create a bridge between »treated sewage sludge as the tool to remove pollutants and nutrients from wastewater« and »preparation of the valuable material as an SRF that meets customer-specific requirements«.

Only treated sludge can achieve the relevant energy efficiency factor. The organic matter content allows a sufficiently high net calorific value (NCV = 13.8 MJ kg<sup>-1</sup> as received) so that the pellets classify in the 4<sup>th</sup> Quality Class code, which still allows the desired energy utilisation. Between 2010 and 2021, the pellets' mercury content decreased its annual amount at SRF delivery by 64.3 %. In 2021, the 80<sup>th</sup> percentile Hg/NCV ratio was 0.079 mg Hg MJ<sup>-1</sup>, which means the 3<sup>rd</sup> Quality Class code of SRF. The halogen contents of the pellets do not threaten corrosion to the facility, as the chlorine content defines the pellets in the 1<sup>st</sup> (the best) Quality Class code. Because pellets are a biogen material containing sulfur-containing proteins, SO<sub>2</sub> emissions are expected. In 2010 - 2021, the sulfur content in the representative monthly samples was 0.7 % m/m<sub>DM</sub> to 1.2 % m/m<sub>DM</sub>. With the operation recovery R 1, by proper flue gas cleaning and treatment of solid residues, we interrupt the circulation of pollutants in the environment, reduce the need for fossil fuels and prevent harmful climate change, and achieve the goals of the circular economy.

It is necessary to take a holistic approach to formulate the frame legislation and a global strategy in the treated sewage sludge management regarding the WtE. In addition to being sustainable material for SRF production, carefully controlled WtE procedures could prevent the circulation of pollutants in the environment. The pelletised sewage sludge represents the fingerprint of UWWTP in question, and secondly, it is an appropriate tool to reach the SDGs in the energy production and consumption field.

**Supplementary Materials:** Wastewater treatment efficiency at the CWWTPL, pellets preparation, and their assessment as non-hazardous waste.

## References

- [1] Sustainable Development, 2015, Department of Economic and Social Affairs, United Nations. [sdgs.un.org/goals](http://sdgs.un.org/goals). Website, accessed on 25 March 2022.
- [2] EU Commission, 2017, Fitness check, Latest news. [ec.europa.eu/environment/water/fitness\\_check\\_of\\_the\\_eu\\_water\\_legislation/index\\_en.htm](http://ec.europa.eu/environment/water/fitness_check_of_the_eu_water_legislation/index_en.htm). Website, accessed on 27 March 2022.
- [3] EU Consultation Strategy, 2020, Consultation Strategy Impact Assessment on the revision of the lists of pollutants affecting surface and ground-waters and the corresponding regulatory standards in the Environmental Quality Standards, Groundwater and Water Framework Directives, [ec.europa.eu/environment/water/fitness\\_check\\_of\\_the\\_eu\\_water\\_legislation/documents/Consultation%20Strategy.pdf](http://ec.europa.eu/environment/water/fitness_check_of_the_eu_water_legislation/documents/Consultation%20Strategy.pdf). Website, accessed on 27 March 2022.
- [4] Directive 2000/60/EC of the European Parliament and of the Council of 23 October 2000 establishing a framework for Community action in the field of water policy, OJ L 327, 22.12.2000, p. 1-73.
- [5] EQSD, Directive 2008/105/EC of the European Parliament and of the Council of 16 December 2008 on environmental quality standards in the field of water policy, amending and subsequently repealing Council Directives 82/176/EEC, 83/513/EEC, 84/156/EEC, 84/491/EEC, 86/280/EEC and amending Directive 2000/60/EC of the European Parliament and the Council OJ L 348, 24.12.2008, p. 84-97.
- [6] GWD, Directive 2006/118/EC of the European Parliament and of the Council of 12 December 2006 on the protection of groundwater against pollution and deterioration OJ L 372, 27.12.2006, p. 19-31.
- [7] FD, Directive 2007/60/EC of the European Parliament and of the Council of 23 October 2007 on the assessment and management of flood risks (Text with EEA relevance), OJ L 288, 6.11.2007, p. 27-34.
- [8] EU Commission, 2015, Better Regulation, [ec.europa.eu/info/law/law-making-process/planning-and-proposing-law/better-regulation-why-and-how\\_en](http://ec.europa.eu/info/law/law-making-process/planning-and-proposing-law/better-regulation-why-and-how_en). Website, accessed on 25 March 2022.
- [9] EU Country profiles, Country profiles on urban wastewater treatment, [water.europa.eu/freshwater/countries/uwwt](http://water.europa.eu/freshwater/countries/uwwt). Website, accessed on 24 May 2022.
- [10] ND, Council Directive 91/676/EEC of 12 December 1991 concerning the protection of waters against pollution caused by nitrates from agricultural sources, OJ L 375, 31.12.1991, p. 1-8.
- [11] UWWTD, Council Directive 91/271/EEC of 21 May 1991 concerning urban waste-water treatment. OJ L 135, 30.5.1991, p. 40-52.
- [12] Wilkinson, L. J., Boxall, B., A., A., Kolpin, W., D., ...(+123), and Teta, C., 2022. Pharmaceutical pollution of the world's rivers. The Proceedings of the National Academy of Sciences (PNAS). doi:10.1073/pnas.2113947119.
- [13] JP VOKA SNAGA, [vokasnaga.si/o-druzbi/centralna-cistilna-naprava-ljubljana](http://vokasnaga.si/o-druzbi/centralna-cistilna-naprava-ljubljana). Website, accessed on 25 March 2022.
- [14] Briefing note, 2021, Waste water treatment – sludge management, EurEau. [eureau.org/documents/drinking-water/briefing-note/5629-briefing-note-on-sludge-management/file](http://eureau.org/documents/drinking-water/briefing-note/5629-briefing-note-on-sludge-management/file). Website, accessed on 15 April 2022.

[15] Europe's water in figures, 2021. An overview of the European drinking water and wastewater sectors, 2021 Edition. EurEau, The European Federation of National Associations of Water Services. [eureau.org/resources/publications/eureau-publications/5824-europe-s-water-in-figures-2021/file](http://eureau.org/resources/publications/eureau-publications/5824-europe-s-water-in-figures-2021/file). Website, accessed on 27 March 2022.

[16] Technical Report, 2006, CEN/TR 15508:2006, Key properties on solid recovered fuels to be used for establishing a classification system, ICS: 75.160.10.

[17] Technical Standard, 2011, EN 15359:2011, Solid recovered fuels – Specification and classes, ICS: 75.160.10.

[18] Technical Standard, 2021, EN ISO 21640:2021, Solid recovered fuels – Specification and classes, ICS: 75.160.10.

[19] RED, 2018, Directive (EU) 2018/2001 of the European Parliament and of the Council of 11 December 2018 on the promotion of the use of energy from renewable sources (recast) (Text with EEA relevance.). PE/48/2018/ REV/1. OJ L 328, 21.12.2018, p. 82–209.

[20] European Green Deal, [ec.europa.eu/info/strategy/priorities-2019-2024/european-green-deal\\_en](http://ec.europa.eu/info/strategy/priorities-2019-2024/european-green-deal_en). Website, accessed on 24 September 2022.

[21] COM/2021/557 final, Proposal for a DIRECTIVE OF THE EUROPEAN PARLIAMENT AND OF THE COUNCIL amending Directive (EU) 2018/2001 of the European Parliament and of the Council, Regulation (EU) 2018/1999 of the European Parliament and of the Council and Directive 98/70/EC of the European Parliament and of the Council as regards the promotion of energy from renewable sources, and repealing Council Directive (EU) 2015/652.

[22] REPowerEU Plan, Communication from the Commission to the European Parliament, the European Council, the Council, the European Economic and Social Committee and the Committee of the Regions REPowerEU Plan.

[23] IED, Directive 2010/75/EU of the European Parliament and of the Council of 24 November 2010 on industrial emissions (integrated pollution prevention and control) Text with EEA relevance. OJ L 334, 17.12.2010, p. 17–119.

[24] EU Commission, 2014, The new Industrial Emissions Directive, [ec.europa.eu/environment/legal/law/1/module\\_2\\_18.htm](http://ec.europa.eu/environment/legal/law/1/module_2_18.htm). Website, accessed on 10 April 2022.

[25] BREF - Waste incineration, 2019, [eippcb.jrc.ec.europa.eu/reference/waste-incineration-0](http://eippcb.jrc.ec.europa.eu/reference/waste-incineration-0). Website, accessed on 10 April 2022.

[26] Mislej V., Novosel B., Vuk T., Grilc V., Mlakar E., 2012, Combustion Behaviour and Products of Dried Sewage Sludge – Prediction by Thermogravimetric Analysis and Monitoring the Co-incineration Process in a Cement Factory, Chemical Engineering Transactions, doi.org/10.3303/CET1229115

[27] Pinasseau, A., Zerger, B., Roth, J., Canova, M. and Roudier, S., 2018, Best Available Techniques (BAT) Reference Document for Waste treatment Industrial Emissions Directive 2010/75/EU (Integrated Pollution Prevention and Control), EUR 29362 EN, Publications Office of the European Union, Luxembourg, 2018, ISBN 978-92-79-94038-5 (online), doi:10.2760/407967 (online), JRC113018.

[28] EU Decision, 2019, Commission Implementing Decision (EU) 2019/2010 of 12 November 2019 establishing the best available techniques (BAT) conclusions, under Directive 2010/75/EU of the European Parliament and of the Council, for waste incineration (notified under document C(2019) 7987) (Text with EEA relevance). C/2019/7987, OJ L 312, 3.12.2019, p. 55–91.

[29] Communication from the Commission to the European Parliament, the Council, the European Economic and Social Committee and the Committee of the Regions, The role of waste-to-energy in the circular economy, 2017, COM (2017) 34 final.

[30] Mislej, V., Babič, R., Nastran, S., Grilc, V., Novosel, B., 2021. Sewage Sludge - a Sustainable Material for the Production of Solid Recovered Fuel. Chemical Engineering Transactions. doi: org/10.3303/CET2188176.

[31] Directive 2008/98/EC of the European Parliament and of the Council of 19 November 2008 on waste and repealing certain Directives (Text with EEA relevance). OJ L 312, 22.11.2008, p. 3–30.

[32] SSFD, Directive 86/278/EEC on the protection of the environment, and in particular of the soil, when sewage sludge is used in agriculture, 1986, OJ L 181, 4.7.1986, p. 6–12.

[33] UWWTD-C, 2014, Consolidated text: Council Directive of 21 May 1991 concerning urban waste water treatment (91/271/EEC), 1.1.2014.

[34] EurEau Position paper, Enabling the circular potential of sewage sludge within the EU legislative framework, A critical analysis of the current urban waste water treatment sludge legislation with respect to the circular economy. July 2021, Brussels, Belgium. [www.eureau.org/documents/drinking-water/position-papers/5835-position-paper-enabling-the-circular-potential-of-sewage-sludge/file](http://www.eureau.org/documents/drinking-water/position-papers/5835-position-paper-enabling-the-circular-potential-of-sewage-sludge/file). Website, accessed on 10 April 2022.

[35] JP VOKA SNAGA, [vokasnaga.si/o-druzbi/centralna-cistilna-naprava-ljubljana/obdelava-odvecnega-blata](http://vokasnaga.si/o-druzbi/centralna-cistilna-naprava-ljubljana/obdelava-odvecnega-blata). Website, accessed on 25 March 2022.

[36] Novosel, B., Mislej, V., Grilc, V., 2022, Basic Morphological, Thermal and Physicochemical Properties of Sewage Sludge for Its Sustainable Energy and Material Use in the Circular Economy. In M. Bartoli, M. Giorcelli (Eds.), Recent Perspectives in Pyrolysis Research. IntechOpen. doi.org/10.5772/intechopen.101898

[37] EU Commission, 2022, Renewable energy directive revision. [energy.ec.europa.eu/topics/renewable-energy/renewable-energy-directive-targets-and-rules/renewable-energy-directive\\_en](http://energy.ec.europa.eu/topics/renewable-energy/renewable-energy-directive-targets-and-rules/renewable-energy-directive_en). Website, accessed on 24 September 2022.

[38] Mislej, V., Grilc, V., Novosel, B., Mladenovič, A., Zalar, Serjun, V., 2022. Sewage sludge management at the central wastewater treatment plant Ljubljana—Characterization of its properties, possibilities for sustainable utilization and legislative obstacles. The Holistic Approach to Environment. doi: org/10.33765/thate.12.1.2

[39] Publication »Ljubljana Waste Water Treatment Plant«, 2009, KROG, Ljubljana.

[40] PSD, Directive 2013/39/EU of the European Parliament and of the Council of 12 August 2013 amending Directives 2000/60/EC and 2008/105/EC as regards priority substances in the field of water policy Text with EEA relevance OJ L 226, 24.8.2013, p. 1–17.

[41] Technical Report, 2008, CEN/TR 15716:2008, Solid recovered fuels – Determination of combustion behaviour, ICS: 75.160.10.

[42] JP VOKA SNAGA, 2021, Annex to Accreditation Certificate, LP-023, Priloga k akreditacijski listini (Preskuševalni laboratoriji) (slo-akreditacija.si). Website, accessed on 10 April 2022.

[43] NLZOH, 2014, National Laboratory of Health, Environment and Food, Department for Waste and Soil, nlzoh.si/o-nas/. Website, accessed on 10 April 2022.

[44] SI Decree, 2009, Decree on surface water status, Official Gazette of the RS, N° 14/09, 98/10, 96/13, 24/16 and 44/22 - ZVO-2. In Slovenian: Uredba o stanju površinskih voda.

[45] SI Decree on waste landfill, 2014, Official Gazette of the Republic of Slovenia, N°. 10/14, 54/15, 36/16, 37/18, 13/21 and 44/22 - ZVO-2. In Slovenian: Uredba o odlagališčih odpadkov.

[46] Commission Directive 2009/90/EC of 31 July 2009 laying down, pursuant to Directive 2000/60/EC of the European Parliament and of the Council, technical specifications for chemical analysis and monitoring of water status (Text with EEA relevance), OJ L 201, 1.8.2009, p. 36–38.

[47] E-PRTR Regulation (EC), 2006, N° 166/2006 of the European Parliament and of the Council of 18 January 2006 concerning the establishment of a European Pollutant Release and Transfer Register and amending Council Directives 91/689/EEC and 96/61/EC (Text with EEA relevance).

[48] Hartwig, P., 2012, Combined wastewater feed directly into final clarification – advantage for receiving rivers, Water Science and Technology. doi.org/10.2166/wst.2012.236

[49] Report on the investigation of hazardous properties of waste for the company JP VODOVOD KANALIZACIJA SNAGA d.o.o., Waste 19 08 05 - Sludge from municipal wastewater treatment, Document N° 88-62/19-1, National Laboratory of Health, Environment and Food, Department for Waste and Soil.

[50] Report on the investigation of hazardous properties of waste for the company JP VODOVOD KANALIZACIJA SNAGA d.o.o., Waste 19 08 05 - Sludge from municipal wastewater treatment, Document N° 54-51-1/22, National Laboratory of Health, Environment and Food, Department for Waste and Soil.

[51] Regulation (EC) No 1272/2008 of the European Parliament and of the Council of 16 December 2008 on classification, labelling and packaging of substances and mixtures, amending and repealing Directives 67/548/EEC and 1999/45/EC, and amending Regulation (EC) No 1907/2006 (Text with EEA relevance), OJ L 353, 31.12.2008, p. 1–1355.

[52] Commission Regulation (EU) No 1357/2014 of 18 December 2014 replacing Annex III to Directive 2008/98/EC of the European Parliament and of the Council on waste and repealing certain Directives Text with EEA relevance, OJ L 365, 19.12.2014, p. 89–96.

[53] Technical Report, 2006, CEN/TR 15441:2006, Solid recovered fuels – Guidelines on occupational health aspects, ICS: 13.100; 75.160.10.

[54] Technical Report, 2007, CEN/TR 15473:2007, Characterization of sludges – Good practice for sludges drying. ICS: 13.030.20.

[55] Henze, M., van Loosdrecht, M. C. M., Ekama, G. A., Brdjanovic, D., 2008, Biological Wastewater Treatment: Principles, Modelling and Design, IWA Publishing, UK, 2008.

[56] Prakash, B., O. 2020. Health Risks of Potentially Toxic Metals Contaminated Water. In: Kanayochukwu Nduka J, Nageeb Rashed M (Eds). Heavy Metal Toxicity in Public Health. IntechOpen. DOI:10.5772/intechopen.92141

[57] Circular economy action plan, 2020, ec.europa.eu/environment/strategy/circular-economy-action-plan\_en. Website, accessed on 15 April 2022.

[58] Chemical, Wastes and Climate change: Interlinkages and Potential for Coordinated Action, 2021. unep.org/resources/report/chemicals-wastes-and-climate-change-interlinkages-and-potential-coordinated-action. Website, accessed on 15 April 2022.

[59] Spinosa, L., 2016, Standardized characterisation procedures: a necessary support to regulations, Water Science and Technology, 74(1), 220 – 228.

[60] SI Decree on the recycling of non-hazardous waste into solid fuel, 2008, Official Gazette of the Republic of Slovenia, N°. 57/08 and 96/14. In Slovenian: Uredba o predelavi nenevarnih odpadkov v trdno gorivo.

[61] SI Decree, 2015, Decree on the recycling of non-hazardous waste into solid fuel and on its use, Official Gazette of the RS, N° 96/14 and 44/22 - ZVO-2. In Slovenian: Uredba o predelavi nenevarnih odpadkov v trdno gorivo in njegovi uporabi.

[62] Gačnik, S., J., 2016, Analysis of alternative chances for sludge treatment at new waste water treatment plant. Master's thesis, University of Nova Gorica Graduate School.

[63] Austrian legislation, 2010, Änderung der Abfallverbrennungsverordnung (AVV-Novelle 2010), BGBLA\_2010\_II\_476, ris.bka.gv.at/eli/bgbl/II/2010/476/20101227. Website, accessed on 5 May 2022.

[64] Technical Standard, 2011, EN 15408:2011, Solid recovered fuels - Methods for the determination of sulphur (S), chlorine (Cl), fluorine (F) and bromine (Br) content, ICS: 75.160.10.